



Illinois
Environmental
Protection Agency

Environmental Programs
2200 Churchill Road
Springfield, Illinois 62706

March 1986

IEPA/ENV/86-008 (final)

US EPA RECORDS CENTER REGION 5



448852

→ MARDI KLEVS 3/86
I.I.

THE SOUTHEAST CHICAGO STUDY:

An Assessment of Environmental Pollution and Public Health Impacts

THE SOUTHEAST CHICAGO STUDY:
An Assessment of Environmental Pollution and
Public Health Impacts

March 1986

- FINAL -

Environmental Programs
Illinois Environmental Protection Agency
2200 Churchill Road
Springfield, Illinois 62706

IEPA/ENV/86-008

Table of Contents

	<u>Page</u>
1.0 Introduction	1
1.1 Study Design and the IEPA's Commitment to the Citizens of the Lake Calumet Region	1
1.2 Description of the Study Area	2
2.0 Summary, Analysis, Conclusions and Recommendations	4
2.1 Summary of Water Pollution Impacts	4
2.2 Summary of Air Pollution Impacts	5
2.3 Summary of Land Pollution Impacts	7
2.4 Summary of Public Health Study	8
2.5 Analysis, Recommendations and General Conclusions	10
3.0 History of the Study Area (Land Use and Patterns of Industrial Growth)	15
3.1 Timeline Outlining Growth and Development of Southeast Chicago	15
3.2 Description of Neighborhood and Industrial Development	16
3.2.1 Background	16
3.2.2 Industrial Development	17
3.3 Examples of Three Neighborhood Developments	18
3.3.1 South Deering	18
3.3.2 Roseland and Pullman	19
3.3.3 East Side	20
3.4 Environmental and Health Concerns	21
3.4.1 Water Problems: Drinking Water Supplies and Sewage Disposal Needs	21
3.4.2 Health Effects	21
3.4.3 Recent History	27
3.4.3.1 Air Pollution	27

4.0	Land Pollution Assessment	34
4.1	Landfills in the Study Area	34
4.2	A Geologic Summary of the Lake Calumet Area	42
4.3	Alternatives to Landfilling	50
4.4	Land Pollution Sampling Program in the Study Area	57
4.4.1	Drilling and Sampling Methodology	57
4.4.2	Chemical Analysis of Metals in Soils	60
4.4.2.1	Introduction	60
4.4.2.2	Discussion of Results of Chemical Analysis of Metals in Soils	64
4.4.3	Chemical Analysis of Metals in Water Samples	66
4.4.4	Chemical Analysis of Organics in Soil Samples	70
4.4.5	Chemical Analysis for Organics in Groundwater Samples	70
4.4.6	Results and Recommendations Related to the Chemical Analysis of Soils and Groundwater	70
4.4.6.1	Results	70
4.5	Land Pollution Control Supplemental Sampling Program	71
4.5.1	Drilling and Sampling Methodology	71
4.5.2	Chemical Analysis of Metals in Soil	72
4.5.2.1	Introduction	72
4.5.3	Summary of Land Pollution Impacts -- Supplemental Study	73
5.0	Water Pollution Assessment	75

5.1	Water Resources and Surface Features	75
5.2	Description of the Waterway	76
5.3	Ambient Water Quality	77
5.4	Area Issues and Problems	80
5.5	Water Pollution Additional Studies	84
5.5.1	Lake Calumet Fish Flesh Sampling	84
6.0	Air Pollution Assessment	87
6.1	Introduction	87
6.1.1	Ambient Air Quality Standards	87
6.1.2	Non-Criteria Pollutants	87
6.1.3	State Implementation Plan Process	89
6.2	Description and Characterization of Air Pollutant Emissions and Major Emission Sources in the Southeast Chicago Study Area	90
6.2.1	Point Source Emissions Inventory	90
6.2.2	Major Point Sources	90
6.2.3	Area Sources	92
6.3	Description and Characterization of Ambient Air Pollution Levels	92
6.3.1	Air Quality Monitoring Network	92
6.3.2	Air Quality Summary and Trends	95
6.3.3	Summary of Health Effects Associated with Violations of the NAAQS	104
6.3.3.1	Particulate Matter	104
6.3.3.2	Sulfur Dioxide	104
6.3.3.3	Carbon Monoxide	105
6.3.3.4	Nitrogen Oxides	106
6.3.3.5	Ozone	106

6.3.3.6	Lead	107
6.4	Discussion of Pollutant Transport Mechanisms and Associated Analytical Techniques	108
6.4.1	Meteorology	108
6.4.2	Transport Mechanisms	110
6.5	Current Air Pollution Control Programs Affecting the Study Area	111
6.5.1	Permit Program	111
6.5.1.1	Compliance Review	111
6.5.1.2	Permit Conditions	111
6.5.1.3	Information Gathering	111
6.5.2	Field Operations Section Operating Program	112
6.5.2.1	Work Plan	112
6.5.2.2	Incident Response	114
6.5.2.3	Stack Testing	114
6.5.2.4	Continuous Monitoring	114
6.5.2.5	Citizen Complaints	114
6.5.2.6	Compliance Status of Major and Significant Facilities in the Southeast Chicago Study Area	115
6.6	Air Pollution Additional Studies	116
6.6.1	Introduction	116
6.6.2	Air Sampling Program	116
6.6.2.1	Mobile Toxic Monitoring	116
6.6.2.2	Airborne Dust Analysis	116
6.6.3	Results and Conclusions	119
6.7	Supplemental Air Pollution Studies	125
6.7.1	Introduction	125

6.7.2	Nitrosamine Air Sampling	125
6.7.3	Polychlorinated Biphenyls Air Sampling	125
6.7.4	Emissions Inventory of Toxic Air Pollutants	126
6.7.5	Odor Study	126
6.7.5.1	Elements of the Southeast Chicago Odor Study	127
6.7.5.1.1	Odor Log	127
6.7.5.1.2	Meteorological Data	127
6.7.5.1.3	Correlation of Data	127
7.0	Cancer Mortality in Selected Community Areas of Southeast Chicago, 1968-1982	128
7.1	Introduction	128
7.2	Methods	128
7.3	Results	129
7.3.1	Reanalysis of the Preliminary Study	131
7.3.2	Trends in Cancer Mortality	131
7.3.3	Detailed Analysis of Cancer Mortality	131
7.3.4	Analysis of Cancer Mortality for One Census Tract	138
7.4	Summary of Four Additional Studies	138
7.5	Recommendations	143
8.0	References	144

- Appendix A: Metal Concentrations in Soil Samples
- Appendix B: Laboratory Data Sheets - Organic Contaminants in Soil
- Appendix C: Soil Boring Logs
- Appendix D: Division of Water Pollution Control Ambient Network Data (1967-1977)
- Appendix E: Description of Treatment Processes, NPDES Permit Information and Compliance Data for Wastewater Discharges Entering the Calumet River
- Appendix F: DAPC Point Source Emissions Inventory
- Appendix G: Standard Industrial Classification Codes
- Appendix H: Lead Emissions in Study Area
- Appendix I: USEPA Studies in the Southeast Chicago Area
- Appendix J: Chicago Regional Port Authority Comprehensive Plan 1984
- Appendix K: Additional Soil Sampling

List of Tables

	<u>Page</u>	
4.1	Locations of Soil and Groundwater Bore Holes	59
4.2	Summary of Metals in Soils	62
4.3	General Use Water Quality Standards	67
4.4	Chemical Analysis of Metals in Groundwater Samples	68
4.5	Summary of Preliminary and Supplementary Chemical Analysis of Metals in the Soil at Five Sampling Locations	74
5.1	Fish Contaminant Analysis for Lake Calumet	86
6.1	Summary of National and Illinois Ambient Air Quality Standards	88
6.2	Total Suspended Particulate Trends (Annual Geometric Mean)	97
6.3	Total Suspended Particulate Trends (Second-High 24-Hour Average)	98
6.4	Lead Trends	99
6.5	Total Suspended Particulate Trace Analyses	100
6.6	Sulfur Dioxide Trends	101
6.7	Ozone Trends	102
6.8	Nitrogen Dioxide Trends	103
6.9	FY'84 Work Plan Investigative Priorities in the Southeast Chicago Area	113
6.10	Air Quality Survey Target Compounds	117
6.11	Sites Monitored During Air Quality Survey	118
6.12	Quantitative Results for Air Quality Survey by Site	121
6.13	MEG Values for Air Quality Survey of Non-Criteria Pollutants	122
6.14	Weighted Average Concentrations in Different Cities	123

	<u>Page</u>
6.15 Results for Air Quality Filter Analysis	124
7.1 Demographic Characteristics of Selected Community Areas of Chicago	130
7.2 Number of Cancer Deaths by Selected Community Areas of Chicago, 1968-1982	130
7.3 Comparison of Preliminary Report and Reanalysis	132
7.4 Community Areas of Southeast Chicago with Statistically Significant Excesses of Cancer Mortality, 1968-1982	141
7.5 Cancer Deaths in Census Tract 5101 of South Deering, Chicago, 1968-1982	142
7.6 Observed and Expected Cancer Deaths in Census Tract 5105, South Deering, Chicago, 1968-1982	142

List of Figures

	<u>Page</u>
1.1 South Chicago Study Area Boundaries	3
3.1 Annual Death Rates (per 1,000 population) from All Causes	23
3.2 Average Lifetime Remaining at Age 65 - Chicago, Illinois	24
3.3 Average Lifetime Remaining at Age 65 - State of Illinois	25
3.4 Average Lifespan - State of Illinois	26
3.5 Annual Death Rate (per 100,000 population) from Typhoid Fever	28
3.6 Annual Death Rate (per 100,000 population) from Malaria	29
3.7 Annual Death Rate (per 100,000 population) from Tuberculosis	30
3.8 Annual Death Rate (per 100,000 population) from Cancer	31
3.9 Annual Death Rate (per 100,000 population) from Heart Disease	32
4.1 Geographic Distribution of Landfills and Waste Handling Facilities in the South Chicago Study Area	35
4.2 Physiographic Division in the Chicago Area	44
4.3 Glacial Geology of Northeastern Illinois	45
4.4 Remnant Shorelines Near the Calumet River	46
4.5 Bedrock Surface - Chicago Area	47
4.6 Geologic Map of Illinois	48
4.7 Areal Geology of the Bedrock Surface and Major Structures in the Chicago Region	49
4.8 Stratigraphy and Water-Yielding Properties of the Rocks and Character of the Groundwater in the Chicago Region	51

	<u>Page</u>
4.9 Cross Sections of the Structure and Stratigraphy of the Bedrock and Piezometric Profiles of the Cambrian-Ordovician Aquifer in the Chicago Region	53
4.10 Sampling Grid for Soil and Groundwater Samples - Southeast Chicago Study Area	58
5.1 IEPA Historic (Pre-1977) Ambient Water Quality Monitoring Network	78
5.2 The Metropolitan Sanitary District of Greater Chicago Ambient Water Quality Monitoring Network	79
5.3 Total Cyanide Concentrations in the Calumet River in Illinois for 1970 through 1981	81
5.4 Total Suspended Solids Concentrations in the Calumet River in Illinois for 1970 through 1981	82
5.5 Wastewater Discharges Entering the Calumet River	83
6.1 Major Air Pollution Emission Sources in the Southeast Chicago Study Area	91
6.2 Roadways Analyzed as Area Sources in the Chicago Steel Mills Study Area	93
6.3 Southeast Chicago Ambient Air Monitoring Network in 1983	94
7.1 Trends in Age-Adjusted Cancer Mortality Rates By Sex, Study Area and Chicago	133
7.2 Trends in Cancer Mortality Rates for Males by Race, Study Area and Chicago	134
7.3 Trends in Cancer Mortality Rates for Females By Race, Study Area and Chicago	135
7.4 Trends in Cancer Mortality Rates By Site, Study Area and Chicago	136
7.5 Trends in Cancer Mortality Rates By Chicago Community Areas	137
7.6 Community Areas in the South Chicago Study Area	138

1.0 Introduction

Southeast Chicago, in the vicinity of Lake Calumet, is a heavily industrialized region that has a long history of serving as a disposal area for a wide variety of industrial, commercial, and residential wastes. In the late fall of 1982, the Illinois Environmental Protection Agency (IEPA) was asked by a citizens group, Irondalers to Abolish the Chemical Threat (I-ACT), to conduct a study of environmental pollution in this area with special emphasis directed toward waste disposal practices.

Subsequent to the initiation of work on the waste disposal study, additional concerns were raised by citizens and interest groups in the area and also by the Agency. These concerns, which related to the extent of toxic pollutant contamination which may have resulted from years of heavy industrial activity in the area, led to a significant expansion of the overall scope of the study to encompass all the major environmental programs (air, land, and water). Additionally, the size of the study area was increased.

The final scope of work included a broad range of environmental concerns relating to air, water and land pollution issues. This scope of work was reviewed and approved by the I-ACT liaison committee. Additionally, as part of the overall effort, an analysis of available health statistics was performed by the Illinois Department of Public Health (IDPH) to determine if cancer rates or the number of birth defects occurring in the area are unusual. This report summarizes the results of these study efforts.

It should be noted that available time and resources severely limited the extent to which each of the complex environmental issues could be investigated. Of principal concern was the question of whether there was imminent danger to human health in the area from environmental pollutants. Based upon the available data, this report concludes that this is not the case. However, since many of the health impacts of concern are long term in nature, this report should be viewed as a starting, rather than an ending, point. The quality of the environment in Southeast Chicago needs improvement; some pollutant concentrations do exceed acceptable levels. Ongoing health and environmental programs that affect this area must emphasize expeditious attainment of all health-related standards.

1.1 Study Design and the IEPA's Commitment to the Citizens of the Lake Calumet Region

Most of the intensive studies concerning environmental problems in Illinois have been directed toward specific sites or facilities, and have usually addressed single medium (i.e., air, land, or water) concerns. This investigation presented unique challenges in that the study area is relatively large, there is a great variety of pollutant emission sources (including landfills, an incinerator, steel mills, and chemical plants), and there is a full complement of environmental issues which need to be considered.

Because of the desire to complete the study in a relatively short time and without supplemental funding, the IEPA, in cooperation with the IDPH and Region V-USEPA, designed a special "toxics hot spot assessment" program for the study area. As part of this special program, historical data available from routine IEPA activities was combined with new information on the status of land, water, and air pollution. Analyses of these combined data sources have provided a better basis for future decision-making by the IEPA, local government and the public.

A major purpose of this study was to develop a compendium of environmental data for the study area to serve as a useful baseline for subsequent assessments of overall environmental quality and public health. A second purpose was to provide the citizens of the study area with an educational document to be used in making informed decisions regarding the environment and land use. A third purpose of the document was to assess what actions should be done next (i.e., are additional studies needed and to what extent are they warranted).

In order to make the best use of IEPA resources, the study utilized existing data bases as much as possible. However, it was necessary to conduct some additional field work. This included using the IEPA's drill rig to extract soil and groundwater samples throughout the study area for laboratory analysis, conducting ambient air toxic pollutant monitoring, taking fish flesh samples from Lake Calumet and a limited USEPA groundwater and soil sampling program. In addition, the IDPH analyzed available health statistics to compare cancer in the study area to those in the rest of Chicago.

1.2 Description of the Study Area

The boundaries of the study area, depicted in Figure 1.1, are as follows:

- North -- 95th Street
- South -- Sibley Boulevard
- East -- Illinois/Indiana Border (Avenue A)
- West -- King Drive/C. and E.I. Railroad Tracks




FIGURE 1.1

South Chicago Study Area Boundaries

2.0 Summary, Analysis, Conclusions and Recommendations

The following information is grouped by media and category consistent with the main body of the report.

2.1 Summary of Water Pollution Impacts

1. The quality of the fishery and associated biological communities varies within the study area. The quality of the Calumet River fishery upstream of the O'Brien locks appears to be very good and reflects the influence of the Lake Michigan fishery and dominance of the diversion water in the system. The fishery downstream of the O'Brien locks is of lower quality. Yellow perch dominate the lakeward half of the Calumet River while bluntnose minnows are the dominant fish species in the lower half. The fishery of Lake Calumet has game species including largemouth bass, black crappie and yellow perch. The northern portion of Lake Calumet generally has higher quality fish communities than the more industrial developed areas around the harbor complex. The lake apparently provides for a limited bass population in the river around the inlet. Localized conditions can provide for recreational fishing opportunities.
2. Lake Calumet fish flesh sampling was conducted in October of 1983. Contaminant analysis of largemouth bass, carp, and crappie was done. The analysis included testing for PCBs, hexachlorobenzene, hexachlorocyclohexanes, heptachlor epoxide, chlordanes, DDT and analogs, dieldrin, endrin, trans-Nonchlor, and percent fat. All contaminant concentrations measured were less than the Food and Drug Administration (FDA) action levels. FDA action levels are limits on the amount of contaminants present in fish flesh, and suggest limits on the consumption of fish with concentrations exceeding the levels.
3. The Metropolitan Sanitary District of Greater Chicago (MSDGC) currently maintains sampling stations on the Calumet River. A review of data collected for the period 1970 through 1981 concludes the following:
 - a. The concentrations of cyanide in the Calumet River have decreased over the period 1970 through 1981.
 - b. The concentrations of total suspended solids (TSS) in the Calumet River have decreased over the period 1970 through 1981.
4. The large industrial sources along the Calumet River no longer discharge their wastewater to the Calumet River. General industrial wastewater discharges from these sources are pretreated and discharged to MSDGC. In general, these sources release only cooling water or noncontaminated stormwater runoff.

5. The Agency maintained an ambient water quality network in the study area from 1967 through 1977. From 1978 to the present, a network is operated by MSDGC. The data collected at the Agency's stations indicate that the water quality for the Calumet River from Lake Calumet to Lake Michigan is generally good with few toxic substances in violation of secondary contact standards. The overall water quality of the Calumet River from Lake Calumet to Lake Michigan has been and continues to be generally good.

2.2 Summary of Air Pollution Impacts

1. Facilities which emit over 100 tons per year of any single pollutant are generally termed major point sources. There are twenty-two major facilities which have been identified in the study area. These facilities include steel mills, chemical plants, auto assembly plants, and a hazardous waste incinerator.
2. There is a wide diversity of so-called area-type sources in the study area. These include odor emissions from landfills and sludge drying beds and particulate emissions from general activity at major industrial complexes.
3. Ambient air monitoring has been conducted in and around the study area since 1960 by both state and local air pollution control agencies. The available air quality data base is composed primarily of total suspended particulate (TSP) data and data resulting from the chemical analysis of TSP samples. The monitoring network operated in the study area in 1984 consisted of four TSP monitors, two ozone continuous monitors, one sulfur dioxide continuous monitor, and one nitrogen oxides continuous monitor. The TSP monitors are located at Addams, Anthony, Carver, and Washington Schools. PM_{10} concentrations were measured at the Washington High School site in 1984. An additional PM_{10} and TSP monitor has been installed at Bright School and is collecting data in 1985. Although TSP concentrations have been decreasing significantly since 1976, as late as 1980 levels at all four TSP monitoring sites in the study area exceeded the annual health-related National Ambient Air Quality Standard (75 ug/m^3). However, in 1984 only one site (Washington High School) exceeded the annual, health-related standard. A decrease is also apparent in the peak 24-hour averages.
4. Ambient lead concentrations are also decreasing in the study area. Violations of the lead National Ambient Air Quality Standard (a quarterly average of 1.5 ug/m^3) were measured in 1974 and 1975, but there have been no violations since then. The areawide average of the peak quarterly lead values has decreased to less than a third of the national standard in the last two years.

5. Other than for lead, no ambient air quality standards exist for the TSP-related trace elements. However, when trace element averages in the study area are compared to Illinois statewide averages, the trace constituents listed are consistently higher in the study area than in the State as a whole. The trace elements measured are sulfates, nitrates, copper, iron, and manganese.
6. Nitrogen dioxide (NO_2) has been monitored at Addams Elementary School since 1974. During that time, the annual average had an upward trend from 1974-1979, followed by a downward trend from 1979-1984. The annual National Ambient Air Quality Standard (100 ug/m^3) was not exceeded during any of the years. The trend in NO_2 levels in the study area parallels that of other areas of Chicago and Cook County during these time periods. However, the magnitude of NO_2 concentrations in the study area has generally been lower than in other parts of Chicago and Cook County.
7. Ozone has been monitored at two sites since 1978 (Roseland and Southeast Police Stations). There is no real trend since 1978 in either the peak concentrations or the number of days exceeding the standard. Some years have been below the one-hour National Ambient Air Quality Standard (0.12 ppm) and other years have been above.
8. During warm summer days, odors emanating from industrial areas, landfills, sludge drying beds, and landfill runoff areas can be trapped just after sunset when winds die down and near-ground-level inversions start to form. The decreased dispersion associated with this meteorological phenomenon often results in short-term odor problems.
9. The IEPA, in cooperation with the Illinois Department of Energy and Natural Resources, funded a study of toxic air pollutants in the Lake Calumet area of Chicago. The study was conducted by TRC Environmental Consultants, Inc. The results of the study were as follows:
 - a. Of the 31 toxic pollutants monitored using a mobile trace gas monitoring system (TAGA 6000), only three were detected -- toluene, benzene, and xylene. Additionally, acetone was detected; however, it was not on the list of 31 toxic pollutants to be monitored. There are no air quality standards for these contaminants. However, the levels detected for these pollutants were all below the multimedia environmental goals (MEGs) suggested by the USEPA. MEGs describe levels of contaminants in ambient air that are predicted by USEPA not to produce negative effects in the surrounding population or ecosystems.

The levels of toluene, xylene and benzene measured in the study area were compared to levels found by the USEPA in other cities and another location in Chicago. A statistical comparison of the pollutant levels found in these ten cities and southeast Chicago shows that the values measured in southeast Chicago were not significantly greater (p less than 0.05) than the levels found in the other cities.

- b. Seven toxic substances were sampled, using selected fiberglass high-volume filters for analysis. The filters were from the four TSP monitors located in the study area. Sampling was conducted for dioxin, arsenic, beryllium, nickel, polychlorinated biphenyls (PCBs), cadmium and chromium. Dioxin and PCBs were not detected on any sample. Low values of the other five pollutants were found at various sampling locations. The results of the filter analyses for arsenic, beryllium, cadmium, chromium and nickel were compared to both (TLV/300 and TLV/420). TLVs (threshold limit values) are occupational exposure standards established by the American Conference of Governmental Industrial Hygienists. They are designed to protect the worker from adverse health effects based on an 8-hour workday and 40-hour workweek exposure. The TLV/300 figure has been used by some local, state and federal agencies as a guideline for safe ambient levels in lieu of National Ambient Air Quality Standards. TLV/420 may be viewed as equivalent to a MEG. All levels measured were below both TLV/300 and TLV/420.

2.3 Summary of Land Pollution Impacts

1. There are 31 (operating or retired) landfills and waste handling facilities in the study area (Figure 4.1). Most of the sites which are not retired are generally in compliance with permit conditions. However, there are some exceptions to this finding. These are discussed further in Chapter 4.
2. The IEPA took soil borings and conducted groundwater sampling in October of 1983. Samples were taken at twenty-two locations throughout the study area. Analyses were conducted for metals and organics in soil and groundwater. The results were as follows:
 - a. There were no significant amounts of organic compounds in any of the soil samples tested.

- b. Metals in soil samples were tested by acid digestion and compared to normal ranges and means. Total metal content as determined by acid digestion is not directly comparable to leached metals. How much a metal leaches out of the soil determines the health risk associated with that metal. However, it may be reasonably concluded that, if soil metals fall within a normal range, then there is not a leachable metal problem. This is borne out by the analysis of metals in groundwater. Some additional leach testing may be necessary for total metal soil samples which do not fall in a normal range. Levels of metals in some soil samples in the study area above the normal range and means were found for chromium, cadmium, manganese, selenium and zinc.
3. Iron, manganese and silver in groundwater were slightly above the General Use Water Quality Standards. The concentrations found, however, indicated little potential health hazard.
4. Low concentrations of several organic compounds were detected in groundwater samples taken at Grids No. 12 and 14 (by the entrance basin to Lake Calumet and near Republic Steel) and appear to be the result of the industrial activity in this area.
5. The Division of Land Pollution Control resampled soils at five locations. These sites were indicated as potentially hazardous due to their surface concentrations of certain heavy metals (selenium, chromium and cadmium). In general, metal acid digest results (total metal content in soil) indicated concentrations of one or more of these specific metals to be slightly above or in the upper end of their common range of concentrations in the soil. Although some of the metal acid digest test results were above the common range for the metal in soil, EP Toxicity test results, which determine the toxicity of the soil, were well below the accepted maximum concentrations for the metals. This indicates that the metals were "tied into the soil" and were not leaching into the groundwater.

2.4 Summary of Public Health Study

In response to a request from the IEPA, the IDPH conducted a detailed review of cancer mortality in the Southeast Chicago study area. The review involved four separate studies. The University of Illinois School of Public Health and the Illinois Cancer Council participated in one of the subsequent studies.

First, a reanalysis of the draft cancer mortality report was performed which used methods similar to the preliminary (draft) study. Second, a time trend analysis of cancer mortality rates assisted in the interpretation of cancer rates within the six community areas of Southeast Chicago. Third, a detailed analysis of cancer mortality by specific cancer types was done for each age, race and sex group of the community areas within the study area. Lastly, a separate study of cancer mortality was performed for one census tract of South Deering on the northwest side of Lake Calumet; the analysis was requested by Mr. Edward Vrdolyak and Mr. Ed Hernandez.

Unlike the first preliminary study, which was reported in the draft Southeast Chicago study, the additional analyses have corrected for the major influences of age, race and sex on the influence of cancer in Southeast Chicago. Failure to correct these influences will result in incorrect estimates of cancer rates. The additional studies have also taken a closer look at specific types of cancer. The draft preliminary analysis used a manual process to perform over 1,000 calculations; the additional analyses used over 24,000 calculations using computer programs.

The combined findings of these four different analyses support the existence of excess cancer mortality in the study area of Southeast Chicago.

Lung cancer deaths were significantly greater for white males in the study area than would be expected for men of similar age in Chicago. A consistently higher lung cancer mortality rate for the study area, when compared against all of Chicago, was noted. This excess may be related to occupational exposures in the distant past or to a higher proportion of cigarette smoking history in this male population.

Bladder cancer deaths were found to be in excess for white females. This excess may be related to previous occupational exposures or some other factors as yet unknown.

An excess of prostate cancers was found in elderly white males in Hegewisch. There are no known environmental associations with this form of cancer, although some occupational associations have been reported in the medical literature.

These findings generally support an excess of lung cancer deaths in white males and bladder deaths in white females. From other published research studies, these two types of cancer have been associated with environmental exposures to carcinogenic substances, primarily smoking tobacco and chemicals in the workplace. If another common environmental exposure (such as air or water) was associated with these excess cancers, we would have expected to find an excess in both males and females in both whites and non-whites. The fact that the excess in lung cancer mortality occurred only in white males suggests that some factor unique to this subgroup, such as smoking tobacco or previous occupational

exposures, might account for the excess. Similar risks might also explain the excess bladder cancer found in white females. However, since no excess lung cancer risk was found for white females, it is unlikely that this group smoked more cigarettes on the average than other white females in Chicago. Some other factor, such as occupational exposures, may be more likely to account for the excess bladder risk in white females.

Based upon the additional analyses, it cannot be concluded that excess cancers could be attributed to environmental exposures in the air or water.

2.5 Analysis, Recommendations and General Conclusions

The Southeast Chicago study area is a densely populated, highly industrialized area. This area represents a very unique concentration of industrial sources and landfills in the state of Illinois. As detailed in Chapters 4, 5 and 6, many of these sources have been (and continue to be) the subject of intense compliance monitoring and enforcement. The following table is a breakdown of the number of investigations, Compliance Inquiry Letters/Warning Letters, compliance conferences and enforcement cases initiated with/against facilities in the Southeast Chicago study area:

	<u>Inspections</u>	<u>CIL's/Warning Letters</u>	<u>Compliance Conferences</u>	<u>Enforcement Cases</u>
DLPC (1970-1984)	938	111	20	10
DAPC (1981-1984)	295	424	91	10
DWPC (1974-1984)	<u>97</u>	<u>27</u>	<u>9</u>	<u>6</u>
Totals	1330	562	120	26

The DLPC data is based on Agency activities with respect to the 31 waste facilities identified in Figure 4.1. The DAPC data is based on Agency activities with respect to the 22 major facilities (Figure 6.1) and 93 minor facilities in the study area. The DWPC data is based on Agency activities in regard to the twelve facilities identified in Figure 5.5.

Even though the individual sources in the study area are generally in compliance with current standards, the density of the source distribution itself poses environmental problems. Problems with air pollution and localized groundwater pollution exist in the study area.

In addition, citizens have reported odor problems. These problems are undoubtedly exacerbated by the density and types of different odor sources and their close proximity to residential areas. Possible odor sources contributing to the problem are landfills, steel mills, sludge drying beds, chemical plants, painting operations at manufacturing plants, and stormwater runoff collection basins. All these sources exist in close proximity to one another.

Several special studies were conducted in the preparation of this report, in addition to the in-depth review of routinely collected data. The studies did not indicate large scale pervasive environmental problems. The health statistics collected by the IDPH indicate that cancer rates generally associated with toxic pollutants are not higher than the City of Chicago in general. While toxic air and land pollutants as measured by these supplemental studies do exist in the study area, their concentrations and areawide disposition do not indicate large scale acute environmental problems.

However, we cannot be quite so certain about the more subtle, long-term adverse impacts which may well be taking place, but which lie beyond our current ability to fully document. The ability to be more conclusive about the effects of lengthy exposures to very low levels of chemical substances requires a new set of regulatory tools. Sophisticated laboratory techniques can detect minute amounts of chemical substances -- down to parts per billions and parts per trillion -- but it is much more difficult to assess how exposure to such low levels affects human health over the course of decades.

During the various phases of data gathering for this study, a considerable number of chemical compounds were encountered (either through actual monitored levels or through permitted pollutant releases). Listed by division programs they include:

Land Pollution

Arsenic
Barium
Cadmium
Chromium
Copper
Iron
Lead
Manganese
Mercury
Nickel
Selenium
Silver
Zinc
Benzene
Toluene
Xylenes
Ethylbenzene
Pyridine
Methylpyridine
Dibutylphthalate

Water Pollution

Ammonia
Lead
Zinc
Cyanide
Hexchromium
PCB
Hexachlorocyclohexane
Heptachlor
Chlordanes
DDT and analogs
Dieldrin
Endrin
trans-Nonchlor

Air Pollution

Sulfur Dioxide
Carbon Monoxide
Nitrogen Oxides
Ozone
Lead
Sulfates
Nitrates
Copper
Iron
Manganese
Toluene
Benzene
Xylenes
Acetone
Arsenic
Beryllium
Cadmium
Chromium
Nickel
Mineral Spirits
Hexane
Isopentane
Isopropyl Alcohol
Naphtha
Methyl Ethyl Ketone
Methanol
Methylene Chloride
Phenol

The results of the Southeast Chicago study reinforce the need for a renewed effort among federal and state environmental and public health agencies to promote new approaches to environmental regulation so that the public can be assured that the manufacture, use and disposal of chemicals is safe.

The techniques chosen for this study were not designed to fully assess impacts that were long-term in nature. In order to maximize the utility of the monies spent on this project, a hot-spot detection approach was used. These techniques best lend themselves to detection of acute environmental problems. Chronic or long-term environmental problems could not be fully assessed under the constraints of this study. For this reason, this study and report should be viewed as a starting point rather than an ending point. With this in mind, the IEPA recommends that the following programs be instigated or has instigated these programs subsequent to the release of the draft document as a follow-up to the Southeast Chicago study:

1. Further assessment of odor problems in the study area appears warranted and necessitates a local, state and public cooperative effort. The IEPA has prepared an odor assessment program which is currently operating.
2. The USEPA has followed-up on the IEPA's pilot toxics air pollutant monitoring with a study of their own. The USEPA has operated a monitoring site at the 111th Street Police Station since April of 1985. The site samples the 31 organics monitored for in the IEPA's pilot study. Data is not yet available from this program. This monitoring effort is serving as a national prototype study for air toxic pollutants.
3. The IEPA has undertaken monitoring of certain air toxic pollutant (PCBs and nitrosamines) in the study area.
4. Sampling of private wells in the area has been made available to area residents to test for pollutant levels.
5. Biological toxicity monitoring in the area should be performed by the IEPA as the necessary laboratory facilities and techniques become available. Testing merely for the presence of chemicals is not enough. Whether or not they have a toxic impact on test organisms should be determined.
6. Further health evaluations covering a wider range of environmental concerns (particularly chronic) should be conducted with possible follow-up by the Center for Disease Control.
7. The State is developing a cancer registry which would provide information on the incidence of specific cancers in the population. Current statistics only provide data on some cancer deaths. A more complete reporting system is needed to identify areas of concern due to unusual rates of cancer incidence.
8. The State should expand the base of available information regarding the location and handling of toxic chemical substances in community settings. This data is essential for comparison with health statistics to pinpoint potential "hot-spots". During the 1985 legislative session, the Illinois Chemical Safety Act was passed. This law will provide for better advance planning with respect to any sudden releases of toxic chemicals.
9. Future studies of exposure to levels of various chemicals of interest should be undertaken. These studies should be conducted as models of overall multimedia exposure become available. The Graphical Exposure Modeling System (GEMS) and the PIPQUIC multimedia environmental data base are being used by the IEPA to perform this evaluation. GEMS has been developed by the USEPA to provide a method for assessing and visually displaying multimedia environmental exposure levels in an area. It considers population, natural environmental data, and levels of the chemicals of interest. PIPQUIC allows "what if" type of analyses to be performed. The IEPA and the USEPA are cooperating in use of these models as well as in developing an air toxic pollutant emission inventory for the study area.

10. The IEPA will address the special surveillance activities necessary to adequately control the unique mix of industrial sites/landfills in the study area. Recommendations based upon this determination should be incorporated into the IEPA's future work plans.
11. This document should be used by interested parties in planning the land-use of the Southeast Chicago study area.

3.0 History of the Study Area (Land Use and Patterns of Industrial Growth)

3.1 Timeline Outlining Growth and Development of Southeast Chicago

The history of southeast Chicago parallels the development and growth of the greater metropolitan area. Following is a timeline which tracks that progress chronologically:

- 1830 -- U.S. government purchased much of Calumet region from Potawatomie Indians.
- 1833 -- Chicago incorporated.
- 1837 -- First settlers in Dolton and Riverdale area.
- 1840 -- First sewers laid in Chicago; first settlers in South Deering (Irondale, Jeffrey Manor, Memorial Park).
- 1847 -- First settlers in Roseland (West Pullman).
- 1848 -- Illinois and Michigan Canal completed.
- 1851 -- East Side becoming settled.
- 1854 -- Peak of cholera epidemic.
- 1856 -- Construction begun on first modern sewer system in Chicago.
- 1862 -- Feeder canal built from Little Calumet River to Illinois and Michigan Canal.
- 1869 -- Brown's mill opened (became Wisconsin Steel).
- 1871 -- Chicago began to use lake water from the Two Mile Crib; Chicago fire; first cargo vessels entered Calumet Harbor.
- 1873 -- Land subdivided for housing; plat maps drawn.
- 1880 -- Pullman Palace Car Works and town of Pullman began.
- 1883 -- Grand Crossing Track Company opened (became part of Republic Steel).
- 1889 -- Calumet region annexed to Chicago; Chicago Sanitary District created.
- 1891 -- Drinking water from Chicago first delivered to southeast area; typhoid epidemic reached its peak.

- 1892 -- Dolton and Riverdale incorporated.
- 1893 -- Columbian Exposition held in Jackson Park.
- 1898 -- South Chicago Steam Boiler Works begun (became U.S. Steel South Works).
- 1900 -- Sanitary and Ship Canal completed; began dredging and straightening of Calumet River.
- 1902 -- International Harvester formed; Inland Steel began operation in Indiana Harbor; Gary, U.S. Steel founded; first electric and gas energy in South Deering.
- 1905 -- Harvester purchased mill and renamed it Wisconsin Steel.
- 1907 -- Began installation of sewers in South Deering.
- 1916 -- Youngstown Sheet and Tube mill in Indiana Harbor constructed; Navy Pier completed.
- 1920 -- Began installation of sewers on East Side.
- 1922 -- Cal-Sag Channel completed; Calumet sewage treatment plant began operation.
- 1930 -- Republic Steel incorporated.
- 1933 -- World's Fair held in Chicago.
- 1938 -- Paved 103rd Street to become major industrial road.
- 1940 -- Dike built at 110th Street across Lake Calumet to develop garbage dump to north.
- 1957 -- Groundbreaking for city incinerator.
- 1958 -- Chicago Skyway completed.

3.2 Description of Neighborhood and Industrial Development

3.2.1 Background

When the glaciers receded, water covered most of the leveled land that is now part of the metropolitan area of Chicago. The waters, known as Lake Chicago, flowed southwest along the Illinois River valley. As the St. Lawrence Seaway was carved out, the level of Lake Chicago dropped and water on the land receded, exposing lake plains, flat and low. Large marshes with poor drainage were also formed. The water began to flow northeast, into Lake Michigan. Surface material was dense stony clay,

without layers or stratification. Stony Island Ridge (originally a reef) deflected currents toward the south, depositing sand and gravel, leaving a shallow lake. It is believed that this lake, Lake Calumet, originally extended from 103rd to 129th Streets, with an average depth of about three feet.

The earliest work activities were hunting, fishing, and farming. Later there was some sand mining and lumbering. A few fertilizer and rendering plants were also established. Through the 1850's, however, only a few railroad lines and homes were scattered through the region.

Prior to the founding of the iron and steel industry plants, no significant industrial, residential or even agricultural development had taken place. The land was marshy and sandy. Consequently, when the steel interests recognized the value of the lakeshore and the banks of the Calumet River to large scale industry, they were able to acquire all the land they needed in large blocks because no subdivision for residential purposes had taken place.

One of the chief requirements of the iron and steel industry was facilities to receive ore by boat. There were no natural harbors on the lakefront and the mouth of the Calumet River was accessible only to small boats. The low shore, the shallow water fronting it, and the character of materials underlying both the land and the lake (unconsolidated sand and clay till) made the dredging of artificial harbors and canals relatively easy and inexpensive.

3.2.2 Industrial Development

Although southeast Chicago was developed because of natural resources, the area has always been controlled by outside influences. James H. Bowan, a friend of President Lincoln, was an entrepreneur that promoted and developed the Calumet region. In 1869, Bowan used his personal yacht to bring bankers and influential businessmen from Chicago down the Calumet River to the opening of the Joseph H. Brown Iron and Steel Company. Brown's mill later became Wisconsin Steel. The mill was located on the west bank of the Calumet River at 109th Street. This location was excellent for the industry -- far enough away from the city to have inexpensive land, low land providing places to dump slag and improve drainage, abundant water, and developing transportation resources.

In 1869, wealthy bankers from Chicago formed the Calumet and Chicago Canal Company to develop the land. They persuaded Congress to appropriate funds to dredge and improve the Calumet Harbor and River.

In 1871, the first cargo vessels entered Calumet Harbor, generating an immediate real estate boom. Also, the Chicago fire of that year caused many to relocate to the Calumet region. There was a small commercial area present at 92nd Street and Commercial Avenue. In the late 1800's, numerous steelmaking ventures were initiated in the southeast Chicago

area. The steel and iron industry eventually grew to dominate life in these neighborhoods. By the early 1900's, after several mergers, sales and resales, several major steelmaking facilities had emerged: Inland Steel (1902); Wisconsin Steel (1905); U.S. Steel - South Works (1909); and Republic Steel (1930).

The first two decades of this century brought growth in traffic on the Calumet River until annually it was five times that of the Chicago River. The facilities on the river supported the expanding industrial activity of the southeast side. The U.S. Steel-Gary Works in the town of Gary, Indiana was completed in 1902. Standard Oil operated twelve cracking stills in 1913. The catalytic cracking process included plat-forming, polymerization, and alkylolation. These processes produced 100+ octane gasoline for the war effort. Until the plat-forming process developed, the results of coal processing were xylene, toluene, and benzene.

Electronics and radio manufacturing developed in the Chicago area during this time. Many innovations were made in steel production to meet the demand for steel in automobiles, stoves, fencing, and assembly lines, among other products.

Inland Steel completely electrified operations. They pioneered in the use of oxygen in open hearth furnaces. Between 1926 and 1930, three companies were consolidated to become Republic Steel, the third largest steel mill company in the United States.

During World War II, \$1.2 billion was spent for construction of war plant facilities in the Chicago metropolitan area, more than in any area of the country. This increased manufacturing capacity 50 percent. After World War II, those government-owned plants were sold to private companies, producing further industrial expansion.

3.3 Examples of Three Neighborhood Developments

3.3.1 South Deering

The neighborhood known today as South Deering was developed in three separate sections: Irondale, Jeffrey Manor and Memorial Park (Slag Valley). The first settlement in Irondale was on the west bank of the Calumet River at about 106th Street. Lake Calumet was about twice its present size and extended north to Trumbull Park (105th Street). Much of the area was low and marshy and flooded frequently.

By 1880, Irondale had grown to a population of 926, settling between 103rd and 110th Streets. The center of the business district was Torrence Avenue along 106th Street. At the turn of the century, Irondale was formally named South Deering.

In 1902, South Deering first obtained electric and gas energy because of combined efforts of International Harvester and the South Deering Improvement Association. By 1914, South Deering was residentially mature with single family, one story frame homes. Torrence Avenue was paved, while most other streets were sand. Some sewers had been installed, but an extensive sewer system was not operational until 1922.

In 1925-26, a study of housing and neighborhood conditions was made of the area between 108th and 109th Streets and Torrence Avenue to Calhoun Avenue. Smoke and dirt were prevalent; land in open spaces was low and marshy with rubbish heaps. The area on both sides of Torrence Avenue was rural with flocks of geese and sheep grazing. Small frame houses were predominant. The area north of 103rd Street has apparently been used for slag and waste dumping for decades. Homes were built on top of that slag in the 1940's. The area was first called Calumet Gardens, then Jeffrey Manor.

3.3.2 Roseland and Pullman

At its peak, the community of Pullman incorporated parts of what is known as Altgeld Gardens and Roseland. Each neighborhood developed separately until George Pullman purchased the land to develop his model town.

Immigrants from Holland arrived in Roseland in 1849. They settled on the most high and dry ground, at Michigan Avenue between 103rd and 111th Streets. Their first businesses were truck farming and selling cheeses and butter.

During the 1870's, Roseland was a growing community. The center of business and travel was at 111th Street and Michigan Avenue. Farms and grazing land surrounded it. Further subdividing and development occurred in Roseland west of Lake Calumet in the 1870's, providing shelter for the workers and their families for the new steel industry.

George W. Pullman began his Palace Car Company in 1880. He purchased much of Roseland, developing a model town for his employees up to the western shore of Lake Calumet. His goal for this community was complete self-sufficiency. He included every type of industry necessary to service the company and the town. He implemented his theory that labor/management problems could be averted if employees enjoyed a superior home environment with recreational opportunities in the community. He also theorized that this environment would attract skilled workers, resulting in greater productivity.

The community of Pullman was built west of Lake Calumet in a grid of 300 acres of the total industrial land area of 4,000 acres. The homes of the workers were row houses set in a highly planned area. The style and location of a home assigned a worker related directly to his rank in the workplace. Children attended Pullman Technical School (now Mendel High School).

Public ways were paved. Trash collection was included in the rental fees. The farm grew fresh produce, cash grain crop, and supported a dairy herd. Bricks for the homes were made at a Pullman brickyard. A 700-ton Corliss engine from the 1876 Centennial Exposition in Philadelphia was used to provide energy to both industry and homes.

Storm sewers were separated from sanitary sewers. Water from roofs and streets was carried down gutters to catch basins, then piped to Lake Calumet. Sewage was carried in glazed pipes to a 300,000 gallon reservoir located beneath a 75 foot water tower, then pumped to a sewage farm three miles away. Subsurface drainage was returned as effluent to lakes and rivers in the area. Public water supply was from Lake Michigan, stored in the 500,000 gallon water tower. Pullman also provided for recreational opportunities at Lake Calumet, landscaping, and open space in the community. Streets were tree lined. Parks and a reflecting pond near the train station were developed with carefully planned flowers and shrubs.

It was a grand experiment that had many advantages. However, it did not produce the results Pullman had sought. In 1894, the Pullman strike occurred, one of the landmark events in labor history. As a result, George Pullman was forced to dissolve his corporate interests in the town.

3.3.3 East Side

Until 1873, the area now called East Side was described as "open, flat, wet, desolate, reedy, and inhabited only by birds and waterfowl, especially migratory birds".

The growth of this area can be attributed to its strategic location between the east side of the Calumet River and Lake Michigan. The Pullman development encouraged growth in South Chicago, South Deering and the East Side.

By the turn of the century, the steel mills had stimulated as much growth in East Side as they had in South Deering. What was to become the Fair Elms subdivision in East Side was prairie and marshes with ridges. There were still only a few houses south of 106th Street.

Just after World War I, Frank J. Lewis purchased land at 112th Street from the Pennsylvania railroad tracks to the state line. His intention was to begin his sixth coal tar plant. However, Chicago put a moratorium on industrial development in that area because of a lack of housing. Lewis' property was rezoned residential. During the 1920's, Lewis installed low level sewers, leveled the land with slag fill, and laid out streets, lining them with elm trees. He sold his coal tar company but kept the land. He built apartment houses along 113th Street between Avenues G and L, but halted construction just before the depression. After that period, he developed the area in single family units. The community became known as Fair Elms.

3.4 Environmental and Health Concerns

3.4.1 Water Problems: Drinking Water Supplies and Sewage Disposal Needs

As early as the 1830's, local governments were concerned about the health and economic problems associated with industrial and human wastes disposed of in the waters of the metropolitan area. Chicago was incorporated in 1833, and one of the first acts by the Town Board was to pass an ordinance against disposal of dead animals in the Chicago River. In 1834, the Board of Trustees authorized construction of a public well. The first sewers -- largely wooden -- were installed in Chicago in 1840. But by 1854, one of every eighteen residents died of cholera. In 1856, construction began on Chicago's first modern sewer system which was a grid of self-flushing sewers with brick mains discharging into the Chicago River. The streets of the city were raised -- up to twelve feet -- to provide adequate drainage. Yet, in spite of these improvements, the water supply in the river and lake was again seriously threatened by pollution in 1858.

The public water supply intake was extended outward into the lake several times until 1869, when the city began to receive water through a new distribution system, new pumping works, and water tower. The new intake was two miles offshore, pumping through a tunnel under the floor of Lake Michigan.

With all of this innovation, the river was still highly polluted. The depth of the I and M Canal was obviously too shallow to reverse the flow of the Chicago River. To supplement the water volume and create more southwest flow, a supplementary canal was built in 1862. This canal fed water from the Little Calumet River in Blue Island to the I and M Canal to provide for barge navigation. The success was minimal; the Chicago River once again became stagnant and increasingly polluted and unsafe.

Other projects were undertaken to pump, dredge and dam the river, with only temporary results. Then the Chicago Sanitary District was created in 1889. By 1900, the new District had constructed the Sanitary and Ship Canal, finally reversing the flow of the Chicago River. This left the water supply in Lake Michigan protected, wastes were carried downstream, and a navigable waterway linked the Great Lakes to the Mississippi River.

3.4.2 Health Effects

The environment and health were closely related in several ways, and various actions were taken to recognize these conditions and improve them.

The typhoid epidemic reached its peak in 1891. As lake water from Chicago began to service the southeast area, health improved.

Through most of the developing years of the steel industry, employees remained unprotected while at the plant. It was common for them to suffer from silicosis, deafness, nervous disorders, and skin diseases. The average worker missed 1 and 1/2 weeks of work annually due to illness. But the companies and unions began to develop programs for safety, protection and compensation, which greatly improved the health of the employees.

A survey conducted in 1890 disclosed that there were 3,558 dwellings in South Deering averaging 7.26 people each. The 33rd ward covered 13,000 acres but residents lived in only one quarter of that land area. It was not long before the area had an average population density per acre but had severe overcrowding. The refuse from the Calumet River into Lake Michigan was described as being equivalent to a population of 700,000. Chicago tried to eliminate other health hazards farther north by not allowing sewer construction south of 95th Street because the sewage would drain into the Calumet River. The wind would carry the waste to the 68th Street pumping station which supplied drinking water to the south side of Chicago (39th Street or Pershing Road).

Until 1906, the only sewage system was to dig sand and gravel from the sides of roads, elevating it above water, and creating drainage trenches. Water from the trenches drained into cisterns, which were used by the Fire Department. In 1907, some sewers were installed.

Full sewage treatment began in 1922 with the operation of the Calumet plant of the Metropolitan Sanitary District of Greater Chicago. Improvements to that plant were made in 1935, 1960, 1965 and 1981. Chlorine treatment began in 1968.

Construction of the Calumet-Sag Channel began in 1911. Over sixteen miles long, its purpose was to drain sewage and runoff originating south of 87th Street. The flow of the Calumet River system was also reversed to protect the Lake Michigan water supply. The Channel was opened in 1922 and it became a federal waterway in 1930. Congress authorized appropriations for dredging the Channel in 1946. Major development of the Cal-Sag Channel and Lake Calumet began in 1955. Included in this project was dredging of the Channel and widening it from 60 feet to 225 feet.

Over the last 100-150 years, the annual death rate from all causes has dropped significantly in Chicago (Figure 3.1). Average life expectancy has increased in both Chicago and the State of Illinois (Figures 3.2, 3.3 and 3.4). These changes reflect improvements in health care and sanitation and a reduced incidence of air, water and soil-borne communicable diseases.




FIGURE 3.1

Annual Death Rates (per 1,000 population)
from All Causes




FIGURE 3.2

Average Lifetime Remaining at age 65 — Chicago, Illinois




FIGURE 3.3

Average Lifetime Remaining at age 65 — State of Illinois




FIGURE 3.4

Average Lifespan — State of Illinois

The incidence of contagious disease can be closely correlated with changes in air and water quality. For example, the original public water supply for Chicago was installed in 1840. Water was pumped to the city mains from Lake Michigan without treatment. Until the direction of flow of the Chicago River changed in 1900, the lake not only supplied drinking water but also received all of Chicago's sewage. There were no currents in Lake Michigan to move soil and sewage away from the water intakes, and typhoid fever flourished (Figure 3.5). The advent of chlorination in 1912 further reduced the incidence of such water-borne diseases to near zero.

Malaria was also a serious problem in Chicago. The area was flat, the water table high, and mosquitos abounded. The inauguration of drainage in 1854 greatly reduced the malaria death rate (Figure 3.6).

Spread of airborne infectious disease was not significantly reduced until the germ theory of disease gained acceptance in the 1890's. From approximately this decade on, Chicago made serious efforts to improve air quality and reduce the spread of acute respiratory diseases, such as tuberculosis (Figure 3.7). By 1907, a comprehensive smoke abatement ordinance was passed and, in 1910, the City instituted the first ventilation standards for public places, factories, and workshops.

As contagious diseases were controlled, the death rates for cancer and heart disease increased (Figures 3.8 and 3.9). This may be due, in part, to increased life spans and improved diagnostic techniques. When infectious diseases were routinely fatal, many individuals died before any chronic disease was apparent. In addition, methods of reporting causes of death have varied widely. A death from lung cancer could have been recorded as "consumption" in 1850 or an "obstructive lung disease" in 1910. In Chicago, death rates from both cancer and heart disease seem to have peaked between 1950 and 1970 (Figures 3.8 and 3.9). The cancer death rate for the whole State of Illinois appears to be following the same pattern. Improvements in environmental quality and healthier lifestyles, as well as recent medical advances, should continue to reduce these figures.

3.4.3 Recent History

3.4.3.1 Air Pollution

Air pollution grew with the development of the steel industry. During the 1950's and 1960's, air pollution reached its peak. Keeping a home clean was a constant chore. Household items such as slipcovers, drapes, blinds, shades and windows needed washing much more frequently than in other areas.

Atmospheric conditions in these neighborhoods varied from good to very poor, depending on the way the wind was blowing. Only a rare northeast wind meant cool, clean air.




FIGURE 3.5

Annual Death Rate (per 100,000 population)
from Typhoid Fever




FIGURE 3.6

Annual Death Rate (per 100,000 population)
from Malaria




FIGURE 3.7

Annual Death Rate (per 100,000 population)
from Tuberculosis




FIGURE 3.8

Annual Death Rate (per 100,000 population)
from Cancer




FIGURE 3.9

Annual Death Rate (per 100,000 population)
from Heart Disease

The City of Chicago built a dike at 110th Street across Lake Calumet in order to use the open space to the north as a 300 acre garbage dump. By 1953, residents in the area solicited aid from Alderman Pacini to discontinue use of the dump because the odors and fires were a nuisance. At first, the Alderman was unsuccessful.

In July of 1953, the city gave Pacini a commitment to eliminate the dump by January of 1954. This would be accomplished by either finding another site outside the city limits or building an incinerator. In August of 1954, citizens groups inspected the dump to observe the promised remedial measures. They found cover only on old garbage and no treatment of runoff into lakes, swamps and streams. But, by March of 1957, the groundbreaking was held for the incinerator at 103rd and Doty. The incinerator operated for several years until Waste Management purchased it and began operation of a transfer station. The garbage dump is presently used for sludge drying and disposal. After reaching capacity in 1990 or 1995, it will be used as open space.

The fallout from the steel mills regularly covered clothes and snow with dust and soot. In November of 1960, Mrs. E. Sorenson of the East Side organized residents to march on Mayor Daley's office concerning the particulates. In 1963, four of the steel mills developed air pollution reduction programs to be implemented over eight years. In return for their promise to clean house, the City of Chicago gave the steel companies a "variance" -- an exemption against prosecution for eight years. Air and water pollution became national issues in the late 1960's.

4.0 Land Pollution Assessment

4.1 Landfills in the Study Area

There are 31 (operating or retired) landfills and waste handling facilities in the study area. Figure 4.1 shows the approximate geographic distribution of these landfill facilities. The following descriptions are keyed to Figure 4.1 by number. The descriptions include a brief narrative on the type of landfill (solid waste/hazardous waste) and a description of the types of waste accepted. Also included, for the permitted sites, is a description of general operating practices and compliance performance.

1. 03160050 (ID No.) - Chicago/103rd Street transfer station
103rd Street and Doty Avenue
Permit No. 1980-29-DE - Issued 9/4/80

Method of Disposal or Treatment: This is a waste treatment facility (transfer station) operated by Waste Management, Inc., and owned by the City of Chicago. The waste accepted and transferred to IEPA permitted facilities is restricted to general municipal waste and excludes special and hazardous wastes.

Description of Past/Present Violations: The transfer station was cited April 6, 1983 for operating without a permit. An operating permit was subsequently issued on May 9, 1983.

Qualitative Assessment of Operation: Generally in compliance with rules and regulations.

2. 031600 (ID No.) - Chicago/Chicago Department of Streets and Sanitation
105th Street and Doty Avenue
The Metropolitan Sanitary District of Greater Chicago (MSD) is operating this site as a sludge drying and disposal site. The central portion of the site is a closed and covered general refuse sanitary landfill, known as Chicago/Chicago Municipal Landfill. It is not permitted by DLPC because of sludge spreading for vegetative growth. This does not come under the purview of the DLPC permit program; however, it is permitted by the DWPC.
3. 03160016 (ID No.) - Chicago/Chicago Regional Port District No. 2 (Terra)
111th Street and Doty Avenue
Operating landfill for demolition material only.
Not permitted by DLPC - earth and concrete to fill in low areas.
This does not come under the purview of the DLPC permit program.
4. 03165101 (ID No.) - Chicago/Interlake Landfill and Coke Plant
113th Street and Torrence Avenue
Permit Nos. 1982-26-DE and 1982-26-OP - Issued 12/3/82




FIGURE 4.1

Geographic Distribution of Landfills and Waste Handling Facilities in the South Chicago Study Area. (see Section 4.1)

Method of Disposal or Treatment: This is a waste treatment facility (storage of "decanter tank tar sludge"). This tar sludge is a hazardous waste. This waste is generated at the rate of four cubic yards per day and is stored on site in waste piles until it is neutralized in the coal processing operation.

Description of Past/Present Violations: This storage site is now in general compliance with its State permit. However, the facility was cited for RCRA-ISS violations pursuant to 40 CFR 265.73 for failure to keep an operating record at the facility (i.e., a recordkeeping violation).

Qualitative Assessment of Operation: Generally in compliance with rules and regulations.

5. 03160041 (ID No.) - Chicago/Liquid Dynamics
655 East 114th Street
Permit No. 1980-8-DE - Issued 4/15/80
Permit No. 1980-8-OP - Issued 10/31/80

Method of Disposal or Treatment: This is a closed hazardous waste treatment facility that operated a wastewater treatment plant to handle industrial wastewater from paint, coatings, adhesives, food, health, beauty care, chemical processing, metal treatment and other industries, through the use of PH adjustment and an electro-chemical separator.

Description of Past/Present Violations: The facility ceased operation on or about October 12, 1982 as a result of involuntary bankruptcy proceedings filed by its creditors. The Illinois Attorney General filed a complaint against Liquid Dynamics et. al., on March 18, 1983 for failure to close the facility in accordance with 35 Ill. Adm. Code 725.111, failure to remove all hazardous waste from the site, and failure to obtain Financial Assurance documents as required by 35 Ill. Adm. Code 725.213.

The facility was subsequently the subject of an immediate removal action by USEPA under Superfund. This action (BBL Removal) was completed by the end of May, 1983. Two "Equalizer" tanks were left on-site (approximately half full of waste); litigation is continuing at the State Attorney General's Office.

Qualitative Assessment of Operation: This site has been closed for over a year. Prior to closing, manifest and housekeeping problems were the rule rather than the exception.

6. 03165003 (ID No.) - Chicago/Sherwin Williams
11541 S. Champlain Avenue
Operating (on-site) hazardous waste treatment and incineration.
Not permitted by DLPC. This site is operating under a USEPA interim (Part A) RCRA permit. The site still has paperwork violation of its RCRA Part A permit.

7. 03165001 (ID No.) - Chicago/Inland Metal
119th Street and Calumet Expressway
Operating secondary smelter of metal bearing materials.
Not permitted by DLPC. This site is under a compliance order from
the USEPA and has a USEPA interim (Part A) RCRA permit.
8. 03160058 (ID No.) - Chicago/S.C.A. Chemical Services
11700 South Stony Island Avenue
Permit No. 1981-46-DE - Issued 8/10/81.
Permit No. 1981-46-OP (Exp.) Issued 1/24/83

Method of Disposal or Treatment: This is an operating treatment (incinerator or liquid hazardous waste) site. It treats nearly all types organic wastes, including oils, solvents, PCBs, etc. The residual wastes from this process are sent to a permitted disposal site in Indiana.

Description of Past/Present Violations: The site is in general compliance with its permit. However, the facility was cited on July 11, 1983 for not promptly reporting a small spill (leakage of 40 gallons of waste material) on or about June 7, 1983.

Qualitative Assessment of Operation: Site is in general compliance with rules and regulations.

9. 03160033 (ID No.) - Chicago/Paxton II
116th Street and Stony Island Avenue
Permit No. 1978-10-OP and 1978-11-OP - Issued 7/21/78

Method of Disposal or Treatment: This is an operating solid waste and nonhazardous special waste disposal site. The wastes are buried in trenches and covered on a daily basis.

Description of Past/Present Violations: The site is in general compliance with the State rules and regulations and its permit conditions. Prior violations concerned housekeeping and premature activity in nonpermitted areas.

Qualitative Assessment of Operation: The site is operating in general compliance with rules and regulations.

10. 03160002 (ID No.) - Chicago/Paxton
116th Street and Paxton Avenue
Permit No. 1971-23 - Issued 6/28/71

This is a closed (in 1978) and covered general refuse and special waste landfill.

11. 03160051 (ID No.) - Chicago/Chem-Clear
Stony Island Avenue and Butler Drive
Permit No. 1980-36-DE - Issued 10/27/80
Permit No. 1980-36-OP - Issued 10/22/81

Method of Disposal or Treatment: The treatment system consists principally of a chemical process for removal of heavy metals and suspended solids and a controlled environment activated sludge biological reduction process for removal of residual organics from aqueous waste streams.

Description of Past/Present Violations: At present, the site is in general compliance. Past violations involved minor housekeeping problems and paper work violations.

Qualitative Assessment of Operation: The site is operating in general compliance with rules and regulations.

12. 03160027 (ID No.) - Chicago/L.H.L. No. 2
117th Street and Oglesby Avenue
Permit No. 1975-47-DE - Issued 6/23/75
Permit No. 1975-47-OP - Issued 7/18/77

This is a closed (in 1978) and covered general refuse and special waste site.

13. 03160013 (ID No.) - Chicago/Calumet Harbor Development
118th Street and Oglesby Avenue
This is a closed and covered general refuse and special waste landfill.
Not permitted by DLPC - not operating.

14. 03160031 (ID No.) - Chicago/Alburn Incinerator
2200 East 119th Street
Temporarily closed hazardous waste incinerator. Bankrupt - USEPA cleanup.
Not permitted by DLPC - not operating

15. 03160035 (ID No.) - Chicago/U.S. Drum Disposal
119th Street and Yates Avenue
Illegal special and hazardous waste storage-transfer facility.
Not permitted by DLPC - the IEPA and the Illinois Attorney General are parties in litigation for this site.

16. 03160034 (ID No.) - Chicago/Land and Lakes No. 3
122nd Street and Stony Island Avenue
Permit No. 1978-2-DE - Issued 1/10/78
Permit No. 1978-2-OP - Issued 9/2/78

Method of Disposal or Treatment: This is an operating general refuse and special waste disposal landfill utilizing the trench method of disposal.

Description of Past/Present Violations: Several years ago, there was a problem with contaminated surface drainage; depth of daily cover and blowing litter is a recurring problem.

Qualitative Assessment of Operation: Except for periodic problems with depth of daily cover and blowing litter, the site is operating in general compliance with rules and regulations.

17. General - Chicago/119th Street and Paxton Avenue
Illegal special waste disposal site.
Not permitted by DLPC - the IEPA and the Illinois Attorney General are parties in litigation for this site.
18. 03160012 (ID No.) - Chicago/Avenue "O" and 118th Street
Closed illegal random dump.
Not permitted by DLPC.
19. 03160026 (ID No.) - Chicago/William H. Powers
State line and north Wolf Lake Boundary.
Solid waste disposal. Concrete and rock fill for erosion control.
Not permitted by DLPC - this type of filling operation does not come under the purview of the DLPC permit program.
20. 03160048 (ID No.) - Chicago/MSD No. 4
122nd Street and Oglesby Avenue
Operating municipal wastewater treatment sludge drying facility.
Not permitted by DLPC - this type of facility does not come under the purview of the DLPC permit program.
21. 03160022 (ID No.) - Chicago/U.S. Scrap
Chicago and Western Indiana Railroad and 122nd Street
Closed illegal hazardous disposal site.
Not permitted by DLPC - the IEPA and the Illinois Attorney General are parties in litigation for this site.
22. 03160021 (ID No.) - Chicago/MSD No. 3
125th Street and Doty Avenue
Municipal wastewater sludge drying facility.
Not permitted by DLPC - this type of facility does not come under the purview of the DLPC permit program.
23. 03160030 (ID No.) - Chicago/CID No. 2
134th Street and Calumet Expressway
Permit No. 1979-10-DE - Issued 3/12/79.
Permit No. 1979-10-OP - Issued 6/8/79.

Method of Disposal or Treatment: This is an operating general refuse and special waste disposal landfill. The site accepted hazardous waste for co-disposal prior to January 26, 1983 (the effective date of RCRA hazardous waste disposal regulations). This site has also obtained a NPDES permit for uncontaminated surface drainage.

Description of Past/Present Violations: Intermittent odor complaints occur and are reported from both CID No. 1 and this site.

Qualitative Assessment of Operation: The site is operating in general compliance with rules and regulations.

24. 03103901 (ID No.) - Calumet City/CID No. 1
138th Street and Calumet Expressway
Permit No. 1974-39-DE - Issued 6/4/74
Permit No. 1974-39-OP - Issued 2/14/75

Method of Disposal or Treatment: This is an operating treatment and disposal site for hazardous waste. The treatment process consists of storage, blending, acid neutralization, dewatering and pug milling for solidification of hazardous wastes. The disposal of the treated waste is in lined trenches located on the south side of the site.

Description of Past/Present Violations: A large portion of this site is a closed and covered general refuse and co-disposal (special and hazardous waste) site. Intermittent odor complaints occur at both this site and CID No. 2.

Qualitative Assessment of Operation: The site is operating in general compliance with rules and regulations.

25. 03160005 (ID No.) - Chicago/Land and Lakes No. 1
138th Street and Cottage Grove Avenue
Permit No. 1971-27 - Issued 8/9/71.
*See site 26 for discussion.

26. 03160028 (ID No.) - Chicago/Land and Lakes No. 2
138th Street and Cottage Grove Avenue
Permit No. 1975-46-DE - Issued 6/20/75.
Permit No. 1975-46-OP - Issued 7/16/76.

Sites 25 and 26 are adjacent and operated as one facility by the owner.

Method of Disposal or Treatment: These are operating solid and special waste disposal landfills.

Description of Past/Present Violations: Thickness of daily cover has been inadequate from time to time, fugitive dust and blowing litter have been observed, and sewage sludge has been used to supplement intermediate cover to an excessive degree.

Qualitative Assessment of Operation: This site moves in and out of compliance with respect to cover thickness, dust, litter, etc. It is receiving routine inspection and oversight by the Agency.

27. 03106905 (ID No.) - Dolton/Cottage Grove Landfill
138th Street and Cottage Grove Avenue
Permit No. 1976-24-DE - Issued 6/17/76
Permit No. 1976-24-OP - Issued 6/27/77

This is a closed solid waste landfill; no special or hazardous waste was permitted.

28. 03106906 (ID No.) - Dolton McKesson
138th Street and Cottage Grove Avenue
Permit No. 1981-37 DE - Issued 7/8/81
Permit No. 1981-37 OP - Issued 10/13/81

Method of Disposal or Treatment: This is a waste treatment facility that reclaims ketones, esters, ethers, alcohols, aliphatic and aromatic hydrocarbons from paint wastes.

Description of Past/Present Violations: On 4/14/83, in loading a transport tanker, overfilling of distilled lacquer thinner resulted in a 200 gallon spill. The spill was contained and removed within one hour.

Qualitative Assessment of Operation: The site is in general compliance with rules and regulations. In the past, manifest "paper violations" have occurred as well as problems with the spill reports associated with tanker loading.

29. 03106903 (ID No.) - Dolton/Land and Lakes
138th Street and Cottage Grove Avenue
Permit No. 1975-43-DE - Issued 6/13/75
Permit No. 1975-43-OP - Issued 7/19/77

Method of Disposal or Treatment: This is an operating solid and special waste landfill utilizing the trench method for disposal.

Description of Past/Present Violations: Past inspections have shown inadequacy of daily cover from time to time. Also, fugitive dust (fly ash) and blowing litter have been problems.

Qualitative Assessment of Operation: This site is in and out of compliance with respect to depth of cover, dust, litter, etc. It is receiving routine inspections and oversight by the IEPA.

30. 03106901 (ID No.) - Dolton/Municipal
Lake Cottage and Cottage Grove Avenue
Closed and covered municipal landfill.
Not permitted by DLPC.
31. 03160039 (ID No.) - Chicago/Calumet Container
136th Street and State Line Road
Temporarily closed hazardous waste treatment and disposal site.
Not permitted by DLPC.

4.2 A Geologic Summary of the Lake Calumet Area

The study area lies in the physiographic area known as the Chicago Lake Plain, which was at one time the bottom of glacial Lake Chicago (Figure 4.2). In terms of erosional surfaces, the lake plain is very youthful, as can be seen on the Lake Calumet Quadrangle map by the few streams and many swamps.

About 13,500 years ago, when the glaciers were slowly retreating north from the Chicago area, the meltwater from the glaciers created a large lake (eventually called Lake Chicago). This lake covered most of what is today the City of Chicago, and it was this lake that created the flatness of the present topography. Glacial moraines lying in crescentic ridges to the west and south provided a natural dam for the meltwater (Figure 4.3).

From wave cut ridges and beach deposits, geologists found three distinct remnant shorelines: the oldest, called the Glenwood stage, was 55 feet above the present lake level; the Calumet stage was 35 feet; and the Toleston stage was 20 feet above. Between each of these stages were corresponding low-water stages, which can be seen by the swamp and sand-filled stream channel deposits overlain by lake bottom clays and beach deposits (Figure 4.4).

Prior to Lake Chicago, great ice sheets covered the land. The tills (deposits of glaciers) found in the Chicago area are almost entirely Wisconsin in age. Although there is evidence of two previous glaciations, the Illinoian and possibly the Kansas, deposits of either of these advances cannot be found in Chicago. Thickness of these unconsolidated deposits ranges between 60-70 feet in this area.

Below the glacial deposits lies the bedrock surface, with its undulating plain and steep sloped valleys, some as much as 100 to 150 feet deep (Figure 4.5). The surface is fresh and unweathered under the unconsolidated glacial debris. The glaciers completely obliterated the bedrock, and rarely are the slopes of the bedrock parallel with the slopes of the present topography. Prior to the Ice Age, this area went through an extensive time period of erosion. This is evident from the fact that no rocks of the Tertiary, Cretaceous, Jurassic, Triassic and Permian ages exist in this area. Rocks of Pennsylvanian, Mississippian and Devonian are also missing in this area but are present in the fault blocks of the Des Plaines Disturbance.

The bedrock in Chicago is Silurian in age (Figure 4.6). During this time period, inland seas covered much of North America from the Gulf of Mexico to the Arctic Ocean. These seas left great deposits of limestone, which later altered to dolomite. The Silurian ranges in thickness between 230 and 500 feet.

Below the Silurian rocks lie the dolomites and sandstones of the Ordovician. The Ordovician rocks, like the Silurian, are all marine sediments. The thickness of the rock from this period ranges from 700 to 1,100 feet.

The thickest deposits are the rocks of the Cambrian System ranging from 3,000 to 4,000 feet thick. These rocks are also marine in origin. The upper half is dolomite, sandstone and siltstone, and the lower half is mostly sandstone and includes the Mt. Simon Formation.

Underlying all of the above are the oldest rocks of the Earth, the Precambrian rocks, ranging in age from 1 to 1.5 billion years old. Depth of the Precambrian rocks in the Chicago Loop area is approximately 4,500 feet. These rocks were identified from borings in the Joliet area as a red granite.

A major structural feature is the Kankakee Arch and, as a result of this structure, the strata in the Chicago area gently dip to the east. This tectonic movement also produced some local anticlinal and synclinal structures with east - west axes (Figure 4.7).

Most of the recent geologic changes have been created by man. Calumet Lake once covered an area of approximately three and one-third square miles but, due to marginal filling and channel dredging, has shrunk considerably in recent times. Filling of the land by local industries was indicated by the slag deposits noted in the boring logs resulting from this study. Many of the swamps have been drained and filled and large extensions of the land along Lake Michigan are also man-made.





FIGURE 4.2

Physiographic Division in the Chicago Area
 (Willman, Ill. Geol. Survey, Circular 460,
 fig. 22, p. 62, 1971)






FIGURE 4.4

Remnant Shorelines near the Calumet River
 (Bretz, Ill. Geol. Survey, Bull. 65, Part 1,
 fig. 31, p. 41, 1939)





FIGURE 4.5

Bedrock Surface - Chicago Area
 (Suter et al., Cooperative Ground-Water Report 1,
 fig. 13, p. 20, 1959)

Illinois State Geological Survey
Geologic Map of Illinois



Pleistocene and
Pliocene not shown



TERTIARY



CRETACEOUS



PENNSYLVANIAN
Bond and Mattoon Formations
Includes narrow belts of
older formations along
La Salle Anticline



PENNSYLVANIAN
Carbondale and Modesto Formations



PENNSYLVANIAN
Caseyville, Abbott, and Spoon
Formations



MISSISSIPPIAN
Includes Devonian in
Hardin County



DEVONIAN
Includes Silurian in Douglas,
Champaign, and western
Rock Island Counties



SILURIAN
Includes Ordovician and Devonian in Cathoun,
Greene, and Jersey Counties



ORDOVICIAN



CAMBRIAN



Des Plaines Disturbance - Ordovician to Pennsylvanian
Fault




FIGURE 4.6




FIGURE 4.7

Areal Geology of the Bedrock Surface and Major Structures in the Chicago Region
(Suter et al., Cooperative Ground-Water Report 1, fig. 16, p. 23, 1959)

There are four aquifer systems in this area: 1) sand and gravel deposits of the glacial drift; 2) shallow dolomite formations, mainly of Silurian age; 3) the Cambrian-Ordovician Aquifer; and 4) the Mt. Simon Aquifer of the lower Cambrian (Figures 4.8 and 4.9). The glacial drift and the shallow dolomite aquifer are hydrologically connected and this aquifer is separated from the Cambrian-Ordovician Aquifer by the less permeable shales of the Maquoketa Formation. The fine grained glacial tills and lake sediments in this area do not produce sufficient groundwater for wells. However, the sand and gravel outwash deposits can produce adequate quantities, the most productive being found in the bedrock valleys.

4.3 Alternatives to Landfilling

In the near term (10-15 years), there will always be a need for landfills as the ultimate repository for certain wastes and for the residues that remain after wastes have been treated. Wastes may be treated for volume reduction, may be rendered innocuous by neutralization or detoxified by physical, biological or chemical processes, and may be treated to produce phase changes such that portions are converted into gases, liquids or concentrated solids. Even though wastes are subjected to one or more treatment methodologies, some substance will remain (perhaps in a different form) that requires further handling and ultimate disposal.

SYSTEM	SERIES	GROUP OR FORMATION	HYDROLOGIC UNITS	LOG	THICKNESS (FT.)	DESCRIPTION	
Quaternary	Pleistocene		Glacial drift aquifers		0-350+	Unconsolidated glacial deposits - pebbly clay (till), silt, and gravel. Alluvial silts and sands along streams.	
Pennsylvanian		Carbondale Tradewater			0-175	Shale; sandstones, fine-grained; limestones; coal; clay.	
Mississippian	Kinderhook				0-365	Shale, green and brown, dolomitic; dolomite, silty.	
Devonian					0-25	Shale, calcareous; limestone beds, thin.	
Ordovician	Silurian	Port Byron Racine Waukesha Joliet	Silurian		0-465	Dolomite, silty at base, locally cherty.	
		Alexandrian Kankakee Edgewood					
	Cincinnatian	Maquoketa	Maquoketa		0-250	Shale, gray or brown; locally dolomite and/or limestone, argillaceous.	
		Galena Decorah Platteville	Galena-Platteville		220-350+	Dolomite and/or limestone, cherty. Dolomite, shale partings, speckled. Dolomite and/or limestone, cherty, sandy at base.	
		Glenwood					
		Chazyan	St. Peter		Glenwood-St. Peter	100-650	Sandstone, fine- and coarse-grained; little dolomite; shale at top. Sandstone, fine- to medium-grained; locally cherty red shale at base.
	Prairie du Chien	Shakopee New Richmond Oneota	Prairie du Chien		0-340	Dolomite, sandy, cherty (oolitic); sandstone. Sandstone, interbedded with dolomite. Dolomite, white to pink, coarse-grained, cherty (oolitic), sandy at base.	
	Cambrian	St. Croixian	Trempealeau		Trempealeau	0-225	Dolomite, white, fine-grained, geodic quartz, sandy at base.
			Franconia		Franconia	45-175	Dolomite, sandstone, and shale, glauconitic, green to red, micaceous.
Iron-ton			Iron-ton-Galesville		105-270	Sandstone, fine- to medium-grained, well sorted, upper part dolomitic.	
Galesville							
Eau Claire			Eau Claire (upper and middle beds)		235-450	Shale and siltstone, dolomitic, glauconitic; sandstone, dolomitic, glauconitic.	
			Sandstones		Mt. Simon	2000±	Sandstone, coarse-grained, white, red in lower half; lenses of shale and siltstone, red, micaceous.
Mt. Simon			Eau Claire (lower) & Mt. Simon				
Precambrian							

FIGURE 4.8

Stratigraphy and Water-Yielding Properties of the Rocks and Character of the Ground Water in the Chicago Region

DRILLING AND CASING CONDITIONS	WATER-YIELDING PROPERTIES	CHEMICAL QUALITY OF WATER	WATER TEMPERATURE °F
Boulders, heaving sand locally; sand and gravel wells usually require screens and development; casing required in wells into bedrock.	Sand and gravel, permeable. Some wells yield more than 1000 gpm. Specific capacities from 2.1 to 66 gpm/ft, av. 12 gpm/ft. Coefficient of trans. from 3400 to 100,000 gpd/ft, av. 25,000 gpd/ft.	McHenry County, hardness from 100 to 450 ppm., av. 275. Other counties, see Silurian below and text.	46° min. 52° av. 54° max.
Shale requires casing.	Jointed beds yield small supplies locally.		
	Limited areal extent; not used as aquifer.		
	Not consistent; some wells yield more than 1000 gpm. Crevices and solution channels more abundant near surface. Specific capacities from 0.1 to 550 gpm/ft. Highest av. specific capacities (54.4 gpm/ft) in Du Page Co. wells, lowest (5 gpm/ft) in Lake Co. Coefficient of trans. averages 100,000 gpd/ft in Du Page Co., 9000 gpd/ft in Lake Co.	Variable. Hardness, <100 to >1000 ppm. Iron >0.3 ppm in 80% of analyses.	54°
Upper part usually weathered and broken; extent of crevicing varies widely.			
Shale requires casing.	Shales, generally not water yielding, act as barriers between shallow and deep aquifers. Crevices in dolomite yield small amounts of water.		
Crevicing common only where formations underlie drift. Top of Galena usually selected for hole reduction and seating of casing.	Where formation lies below shales, development and yields of crevices are small; where not capped by shales, dolomites are fairly permeable.	Hardness < 100 ppm. H ₂ S often present.	54° to 55°
Lower cherty shales cave and are usually cased. Friable sand may slough.	Small to moderate quantities of water. Trans. probably about 15% of that of Cam.-Ord. Aquif.	Water similar in quality or slightly harder than that in Ironton-Galesville Sandstone.	53° to 56° 56° to 58° (Lake Co.)
Crevices encountered locally in the dolomite, especially in Trempealeau. Casing not required.	Crevices in dolomite and sandstone generally yield small amounts of water. Trempealeau locally well creviced and partly responsible for exceptionally high yields of several deep wells.		
Amount of cementation variable. Lower part more friable. Sometimes sloughs.	Most productive unit of Cam.-Ord. Aquif; trans. probably about 80% its total. Coefficients of trans. and storage of the Cam.-Ord. Aquif, av. 17,400 gpd/ft and 0.00035.	Hardness 200 to 250 ppm in northwest part of area, increasing toward east and south. Iron usually <0.4 ppm.	56° - 58° to 62° - 64°
Casing not usually necessary. Locally weak shales may require casing.	Shales, generally not water yielding, act as barrier between Ironton-Galesville and Mt. Simon.	Water soft in upper 100'; hardness increases downward (4000 ppm at elev. -2100'); chlorides 400 ppm at elev. -1600', increase at rate of 400 ppm each additional 25' depth.	66° at elev. -1300', increasing 1° with each additional 100' depth. Influenced by water from upper formations.
Casing not required.	Moderate amounts of water; permeability intermediate between that of Glenwood-St. Peter and Ironton-Galesville.		
crystalline rocks			

FIGURE 4.8 (CONTINUED)

(Suter et al., Cooperative Ground-Water Report 1, 1959)




FIGURE 4.9

Cross Sections of the Structure and Stratigraphy of the Bedrock and Piezometric Profiles of the Cambrian-Ordovician Aquifer in the Chicago Region (Suter et al., Cooperative Ground Water Report 1, fig. 15, p. 22, 1959)

The residues of other treatment systems are examples. Sludge results from the operation of municipal wastewater treatment plants and from industrial waste pretreatment works. The sludges may be dewatered, concentrated by chemical or drying techniques or even incinerated, but some residue, solid, ash (in the case of incinerators), or a gaseous waste stream and another sludge from a scrubber will result. These residues require further handling and disposal.

The above is also true for industrial waste treatment processes and for air pollution control devices and facilities. Sludges, dusts, ash, condensed fumes, vapors and entrained gases that result from treatment and collection require further handling and ultimate disposal.

The quantities and characteristics of wastes that are permitted to be ultimately landfilled may be limited and controlled to varying degrees and, thus, their potential as a threat to human health or to the environment can be minimized. Examples include the following:

1. In-plant industrial process changes.
 - a. Substitution and use of nonhazardous or less hazardous feedstocks or chemicals.
 - b. Adoption of waste management strategies that concentrate, reuse and/or segregate waste streams with separate management of the hazardous, reusable or difficult to landfill components.
2. Waste recovery and reuse.
 - a. Solvent, oil and other materials recovery and reclamation for reuse.
 - b. Recovery of heat value of certain wastes for steam generation and/or electrical energy production in boilers and for firing industrial furnaces.
 - c. Improved collection, pretreatment and reuse of valuable waste components. The recovery of chrome from metal plating baths and sludges is an example.
 - d. Separate collection and specialized recovery of other valuable waste components.
3. Regulatory preclusion of mobile or problem wastes (liquids) from landfill disposal where alternate technologies are available.

4. Specialized industrial waste treatment.
 - a. Volume reduction by dewatering and solidification techniques with treatment and discharge of excess liquids to sewers with approved permits.
 - b. Neutralization of acid or alkaline wastes.
 - c. Detoxification by chemical/physical treatment, volume reduction and separate handling of the resulting solid and liquid waste stream.
 - d. Volume reduction, destruction of hazardous organics and elimination of the liquid component by incineration.
5. Specialized waste treatment to facilitate disposal such as stabilization/solidification processes that decrease solubility and retard leaching.

There are variations on each of the above processes, and many are being used by generators (manufacturers and service industries) and the waste management facilities located within or served by sites in the study area. For example, hazardous waste sites do not accept wastes for disposal that contain free liquids. Liquid wastes must have been previously treated or solidified or retained within absorbents prior to disposal. Thus, their mobility, leachability and pollution potential have been greatly reduced.

An incinerator (SCA Chemical Services, Inc.) having a destruction/removal efficiency of 99.99 percent for toxic organics that has been permitted by both the USEPA and the IEPA is in operation in the study area. In addition to the destruction of toxic organics, a waste volume reduction to about one tenth of the original occurs. The residual is an ash and scrubber sludge. The facility can incinerate approximately 12.5 million gallons of specified wastes per year.

The majority of spent solvents that formerly were discarded is now separately collected and reclaimed for reuse. Several solvent recovery facilities (thin wall evaporation or other distillation processes) in Cook County annually recover over 3 million gallons of spent solvents for reuse in industry. Some of the custom recovery facilities are able to distill and reconstitute exotic and frequently expensive organic compounds to original specifications. The distillation bottoms that result from the recovery of spent solvents may be further treated in an environmentally safe manner by incineration.

Several waste treatment facilities have been established to address aqueous wastes (over 90 percent water) that have frequently been landfilled in the past. Chemical and physical treatment processes are

employed to neutralize, coagulate, precipitate, filter and otherwise concentrate the hazardous components into a filter residue that comprises less than 10 percent of the original volume and which may be safely landfilled. The treatment processes are sufficient to allow the resulting filtered liquids to be discharged to the sewage system. Oil-water separation equipment may also split off a separate oil/grease component that is collected for recovery and reuse. Specialized treatment may result in a detoxification or chemical alteration of the resulting filter residue so that it no longer has any hazardous properties and it may be further managed at other than hazardous waste facilities.

In 1982, approximately six million gallons of aqueous hazardous waste were treated by these methods in the study area.

Waste oils have caused major environmental problems when applied to land in the past. In the Chicago area, most of the waste oils that are managed off-site are re-refined into usable lubricants. The largest used oil refiner in the United States is located just west of Chicago and annually recovers over 10 million gallons of used oil for reuse as lubricants. Much of the remainder is also separately collected but transported to permitted facilities where it is blended with other high BTU value wastes (such as mixed solvents, distillation bottoms, and paint waste residues) into supplemental fuels that are burned in industrial furnaces or boilers in manufacturing plants, steel mills and asphalt plants.

The IEPA has been actively encouraging recycling, reuse, treatment and incineration of waste and discouraging land disposal of certain hazardous wastes such as those containing free liquids, halogenated and other organics, and extremely toxic substances. Incentives to treat and recover and disincentives to landfill are economic and regulatory. As an example, the hazardous waste disposal fee is not applicable to those wastes that are recovered for reuse but has recently been increased threefold for hazardous wastes that are landfilled.

In Illinois, a waste management facility must obtain a supplemental permit for each waste stream that it handles for each generator. A rigorous and frequently time consuming review is made by IEPA staff of each application and each one must be renewed on a periodic basis. Recently, the IEPA introduced the generic waste stream permit authorization program. Under this program, permitted waste management facilities may accept specified waste streams from any registered generator without first having to secure the supplemental permit if the waste is to be beneficially recovered, treated or incinerated. Generic waste stream authorization has given a competitive edge to waste treatment and recovery facilities and the percentage of total wastes that are managed off-site is increasing.

The waste of one company may be used as a raw feedstock in the manufacturing operation of another. Similarly, alkaline wastes of company A could be used to neutralize acidic wastes from company B. Specific waste streams, even in small quantities, such as used oils and spent solvents, can be combined with other similar small waste streams to make recovery and reuse economically feasible. They may also be blended into fuels for recovery of their BTU content. Waste exchanges are mechanisms whereby usable wastes from one industry may be matched for possible use by another industry.

The Illinois Industrial Materials Exchange Service has been operated cooperatively by the IEPA and the Illinois State Chamber of Commerce since April of 1981. It publishes a bi-monthly listing of specific categories of wastes and surplus products that are available for exchange and a listing of waste or off-specification products that are wanted or usable by other facilities. Its purpose is to encourage the recovery and reuse of valuable components of waste, to conserve valuable resources (many of which must be imported) and to reduce the quantity of wastes (many of which may cause environmental degradation or pose a threat to human health) that are land disposed. In its first two years of operation, approximately 7 million gallons of mostly hazardous waste were been recovered for reuse through use of the exchange. The disposal and material purchase costs that were avoided total over \$860,000 for that period.

In 1980, over 80 percent of the hazardous wastes in Illinois managed off the site of generation was landfilled and less than 20 percent was recycled, treated or incinerated. For 1983, it is estimated that only 40 percent will be landfilled and 60 percent recycled, treated or incinerated. There will be an increasing need for treatment and recycling facilities and decreasing dependence upon landfill sites.

4.4 Land Pollution Sampling Program in the Study Area

As part of this study, the Division of Land Pollution Control (DLPC) conducted a detailed soil and groundwater sampling program in the study area. The area was divided into grids encompassing approximately equal areas. Within the established geographic grid (Figure 4.10), a representative site was chosen for sampling (Table 4.1). Both soil and groundwater samples were taken for study. Drilling logs for the sampling are contained in Appendix C.

4.4.1 Drilling and Sampling Methodology

The IEPA's CME 55 Drill Rig, with a 3-1/4 inch inner diameter hollow stem auger, was used for the entire study. Within the auger, either a primary or secondary sampling device was used to retrieve soil specimens for geologic interpretation and soil sampling.



Sampling Grid for Soil and Groundwater Samples, South Chicago Study Area

Table 4.1

Locations of Soil and Groundwater Bore Holes

<u>Grid Numbers</u>	<u>Site</u>
1	Chicago State University
2	Olive Harvey College
3	Luella Playground School
4	Veterans Memorial Park
5	Calumet Park
6	Pullman Park
7	*
8	Bright School
9	Wolfe Playground Park
10	Addams Elementary School Playground
11	*
12	Chicago Port District
13	*
14	Republic Steel
15	Wolf Lake Conservation Area
16	New Carver High School
17	Beaubien Forest Preserve
18	Thomas J. O'Brien Lock and Dam
19	Mann Park
20	Wolf Lake Conservation Area
21	Lincoln Avenue Grade School
22	John W. Needles Park
23	Hoxie Tot Lot
24	Burnham Park
25	Burnham Woods Golf Course

*Unable to drill due to landfilling or Lake Calumet

The primary sampler is a unique device known as the CME Continuous Sampler, which consists of a 3-inch diameter split tube with a tapered cutting head. This allows retrieval of a 2-1/4 inch nearly undisturbed continuous sample up to 5 feet long.

The secondary sampler, a Standard Lynac Split Spoon, was only used when geologic conditions would not allow use of the primary device. This device is also a split tube, although only 2 inches in diameter, and it retrieves a 1-3/8 inch disturbed soil sample up to 18 inches long. This sample method is in accordance with ASTM Standard D-1586.

Upon removal from the split tubes, the soil sample is sliced along its entire length. Readings taken with an organic vapor analyzer (OVA) along the split sample as well as at the bore hole, would allow determinations of where to take organics samples. Samples were taken for metals analysis at regular intervals of 0 to 6 inches, 6 inches to 2 feet, and 2 feet to 10 feet.

When the desired depth was achieved and groundwater encountered, a 2-inch PVC threaded pipe with a 2-foot no. 10 (.01 inch) slotted screen was installed. Several volumes of water were bailed from the hole using a teflon bailer. Water samples for entire organics scan, including volatile organics, were bailed. Also, a water sample for metals analysis was pumped and field filtered. All samples were labeled, preserved in accordance with IEPA laboratory procedures, and iced in coolers for proper storage.

Upon completion of the sampling, the PVC pipe and screen were retrieved and the bore hole was filled in with cuttings. All drilling tools, sampling tools, PVC pipe, screen, and teflon bailer were cleaned using high pressure hot water between bore hole locations.

4.4.2 Chemical Analysis of Metals in Soils

4.4.2.1 Introduction

There are no formal standards for metals in soils, only ranges and means of metal concentrations found in soils. These ranges and means are based on samples taken from various localities around the world. The concentration of trace metals and trace elements can vary from site to site because soil chemistry varies due to differences in climate, vegetation, topography, geographic location (industrial versus agricultural), and the geologic parent material. Though these ranges and means are not applicable to this specific locale, they can provide a method of spotting any gross soil contamination.

In many of the borings, fill material was encountered, in which case the soil ranges are not a valid means for comparison. When analyzing the data, a check of the boring log description will indicate if the material tested was fill or natural.

Table 4.2

Summary of Metals in Soil (ppm)
 (Taken from Data in Appendix A for 21 Sampling Sites)

<u>Contaminant</u>	<u>0-6" depth</u>	<u>6"-2' depth</u>	<u>2'-10' depth</u>
Arsenic			
Mean	8.3	11.2	5.4
Highest	16.0	80.0	17.0
Lowest	2.4	0.7	1.5
Barium			
Mean	86.0	82.5	58.9
Highest	250.0	450.0	462.0
Lowest	<25.0	<2.5	<2.5
Cadmium			
Mean	<3.0	<2.5	<2.5
Highest	13.2	-	-
Lowest	<2.5	-	-
Chromium			
Mean	19.5	14.0	7.6
Highest	2500.0	77.5	21.0
Lowest	5.0	<2.5	<2.5
Copper			
Mean	31.4	18.8	11.9
Highest	95.0	52.5	45.0
Lowest	3.8	<2.5	<2.5
Iron			
Mean	18,902.2	17687.7	10,923.1
Highest	174,518.0	83,699.0	31,685.0
Lowest	6,088.0	3,919.0	4,095.0
Lead			
Mean	114.4	52.2	44.0
Highest	657.0	294.2	576.0
Lowest	33.0	<7.5	<7.5
Manganese			
Mean	657.0	1323.2	424.4
Highest	32,600.0	9250.0	2325.0
Lowest	135.0	42.5	175.0
Mercury			
Mean	0.08	0.07	0.03
Highest	0.27	0.29	0.24
Lowest	0.01	0.01	0.01
Nickel			
Mean	25.6	28.9	26.2
Highest	162.5	75.0	42.5
Lowest	<25.0	<25.0	<25.0
Selenium			
Mean	0.58	0.55	0.47
Highest	2.10	4.00	5.20
Lowest	0.20	0.10	<0.10

The laboratory test used to analyze the metal content is called an acid digest. This test gives the total metal concentration in a soil and does not indicate the amount of free or soluble metals present (which is needed to determine the toxicity of the soils).

At Grids No. 14 and 15, the regular sampling intervals were not taken due to difficulties in drilling through slag deposits. Instead, samples were taken from 5' to 6-1/2' and 6-1/2' to 9-1/2' at Grid No. 14, and 1-1/2' to 5' and 5' to 10' at Grid No. 15. All four of these samples fell within the normal soil metal content range for the various metals. Copies of the analysis for these irregular intervals are included in this report.

The results of the chemical analyses of metals in the soil samples are presented in Appendix A.

The following table (Table 4.2) summarizes the chemical analyses of metals in the soil samples taken in the study area.

Table 4.2 (Continued)

Summary of Metals in Soil (ppm)

Silver			
Mean	<2.50	2.7	<2.5
Highest	3.80	5.0	<2.5
Lowest	<2.50	<2.5	<2.5
Zinc			
Mean	186.1	73.1	56.7
Highest	550.0	220.0	340.0
Lowest	32.5	2.5	17.5

4.4.2.2 Discussion of Results of Chemical Analysis of Metals in Soils (see Appendix A)

Arsenic

Arsenic is found in all soils with the natural arsenic content in virgin soils ranging from 0.1 to 40 ppm. All the soil samples collected and analyzed within the study area fell within the normal range.

Barium

The common range for barium is 100 to 3000 ppm with a mean of 430 ppm in soils. All soil samples from this area were within this range and well below the normal mean. The interference in some of the samples was due to elements present in the soil with a higher ionization than barium, like sodium or potassium, which make it impossible to get a reading.

Cadmium

The common range for cadmium in soils is 0.01 to 0.70 ppm. However, the IEPA laboratory does not have the capability to detect cadmium at these very low levels. A visual and statistical comparison of the results shows one sample significantly higher, the 13.2 ppm from 0-6" depth at Grid No. 15, Wolf Lake Conservation Area.

Chromium

The common range for chromium in soils is from 1 to 1000 ppm with an average of 100 ppm. All but one sample fell into this range. This was at Grid No. 14 (Republic Steel) with 2,500 ppm and is probably due to the fact that the sample consisted of slag material and not virgin soil.

Copper

The normal concentration of copper in soils ranges from 2 to 100 ppm, the average being 30 ppm. All the soil samples analyzed for copper fell within the normal range.

Iron

The range of iron in soils is 7,000 to 550,000 ppm with an average of 38,000 ppm. All samples taken in this area fell within this range.

Lead

Lead levels in soils can vary greatly. From a USEPA study of surface soils in seventeen U.S. sites, an average lead concentration of less than 500 ppm was found. The mean lead concentration ranged from 99 to 1088 ppm. All the soil samples taken in this study fell within the above range.

Manganese

The U.S. Geological Survey began a study in 1961 of surface materials in the United States and found the manganese content to range from less than 1 to 7,000 ppm with a mean of 560 ppm. Cannon and Anderson collected 39 soil samples from remote areas of the United States to obtain background data on manganese content and found a soil mean of 660 ppm and a median of 500 ppm.

Soil samples in this area taken from 0 to 6 inches and 6 inches to 2 feet averaged above the normal mean of manganese concentrations. Many of the highs correspond to areas where slag was deposited. Since large quantities of manganese are used in the steelmaking process, contamination of the soils from dust and fumes in this area would be probable. The 6 inches to 2 foot depth sample at Grid No. 110 (Addams Elementary School) with concentrations of 9,250 ppm is 2,500 ppm above the highest surface concentrations found by the U.S. Geological Survey. There are few reports regarding man-made manganese contamination of soils.

Mercury

The range of mercury in soils is 0.01 to 0.3 ppm with an average of 0.03 ppm. All samples taken in this area fell within this range.

Nickel

Soils normally contain nickel at concentrations of 5 to 500 ppm with an average of 40 ppm. All soil samples taken fell within this range.

Selenium

The common range for selenium in soils is 0.1 to 2.0 ppm with a mean of 0.3 ppm. Four samples were above the normal range: 2' to 10' at Grid No. 3, 6" to 2' at Grid No. 8, 6" to 2' at Grid No. 10, and 0 to 6" at Grid No. 14.

Silver

The common range for silver in soils is 0.01 to 5.0 ppm. All soil samples from this area were in this range.

Zinc

Normal soils contain 10 to 300 ppm zinc. A study of industrial areas versus agricultural and residential areas showed an average of 56.6 ppm for industrial areas and 22.1 ppm for the other areas. Soil samples from this study for the 0 to 6" depth and the 6" to 2' depth were above the mean. The levels at Grid Nos. 14 and 15 are high because the borings were in areas where slag had been deposited. The 340 ppm from 2' to 10' at Grid No. 3 and 390 ppm at 0 to 6" depth at Grid No. 4 is over the normal range for zinc in soils.

4.4.3 Chemical Analysis of Metals in Water Samples

Analysis of groundwater samples showed that arsenic, barium, cadmium, chromium (total), copper, lead, nickel, selenium, and zinc concentrations fell below the General Use Water Quality Standards (35 Ill. Adm. Code 302.208). Only three of the metals analyzed (iron, manganese, and silver) were above these standards. Though several volumes of water were removed from the well casing prior to sampling, sufficient flushing to adequately remove sediments from the water was impossible. This, plus the industry waste in the area and the man-made fill deposits, especially the slag from the steel manufacturing, contributed to the above standard levels.

Levels of iron found in the groundwater over the 1.0 ppm standard ranged from 2.3 to 9.2 ppm. These above-standard concentrations were located in grids near the steel plants. Natural groundwater commonly has iron concentrations ranging from 0.5 to 10 ppm and the main purpose of setting the standard at 1.0 ppm was for aesthetic reasons. Acute iron toxicity from the groundwater in this area is highly unlikely, particularly since large quantities of iron must be ingested to produce intoxication. As an example, the average adult male would have to swallow 14 grams of elemental iron for a lethal dose.

Manganese was found at levels only slightly above the standard of 1.0 ppm at Grids No. 2 and 14 with concentrations of 1.18 and 1.21 ppm, respectively. Large quantities of manganese are used by the iron and steel industries. This, plus the fact that the soil samples taken in this area also contained high concentrations, would explain the slightly elevated levels in the groundwater.

Of the trace elements, manganese is the least toxic and, in fact, is an essential element in our diet. Studies conducted on the toleration of high amounts of dietary manganese on rats showed unaffected growth rates at concentrations as high as 2,000 ppm. The toxicity of manganese to man appears to be mainly through the inhalation of dust and fumes. The levels found in the groundwater samples in this area appear not to be a problem.

Two locations contained amounts of silver over the General Use Water Quality Standard (Table 4.3). Grids No. 2 and 16 both indicated 0.01 ppm. According to the USEPA Ambient Water Quality Criteria, natural water contains an average of 0.2 ppm. European scientists have found silver ions at concentrations of 100 to 200 ppm to be safe, stable, and long-lasting. These ions have been used in the purification of polluted water for drinking in space ships and orbiting stations. Based on the above data, these above standard silver concentrations could not be considered significant or a potential hazard. The results are shown in Table 4.4.

Table 4.3
General Use Water Quality Standards

Parameters	Concentration (in ppm)
Arsenic (total)	1.0
Barium (total)	5.0
Cadmium (total)	0.05
Chromium (total)	1.00
Copper (total)	0.02
Iron (total)	1.0
Lead (total)	0.1
Manganese (total)	1.0
Nickel (total)	1.0
Selenium (total)	1.0
Silver (total)	0.005
Zinc	1.0

Table 4.4

Chemical Analysis of Metals in Groundwater Samples
(results in ppm)

<u>Parameters</u>	<u>Grid No.</u>						
	<u>2</u>	<u>3</u>	<u>4</u>	<u>5</u>	<u>8</u>	<u>9</u>	<u>10</u>
Arsenic	0.006	0.005	0.003	0.003	0.002	0.001	0.011
Barium	Interference	Interference	0.200	0.000	0.000	0.000	Interference
Cadmium	0.000	0.000	0.000	0.000	0.000	0.000	0.000
Chromium (total)	0.010	0.000	0.000	0.000	0.000	0.000	0.000
Copper	0.000	0.000	0.000	0.000	0.000	0.000	0.000
Iron	0.200	0.100	7.300	5.400	4.800	0.300	9.200
Lead	<0.030	<0.030	<0.030	<0.030	<0.030	<0.030	<0.030
Manganese	1.180	0.310	0.220	0.560	0.330	0.340	0.350
Nickel	0.000	0.000	0.000	0.000	0.000	0.000	0.000
Selenium	<0.001	0.001	0.001	<0.001	<0.001	0.001	<0.001
Silver	0.010	0.000	0.000	0.000	0.000	0.000	0.000
Zinc	0.000	0.000	0.000	0.000	0.000	0.000	0.000

<u>Parameters</u>	<u>Grid No.</u>						
	<u>12</u>	<u>14</u>	<u>16</u>	<u>17</u>	<u>18</u>	<u>19</u>	<u>20</u>
Arsenic	0.044	0.000	0.009	0.003	0.015	0.002	0.001
Barium	Interference	0.000	Interference	0.000	0.200	Interference	0.300
Cadmium	0.000	0.000	0.000	0.000	0.000	0.000	0.000
Chromium (total)	0.000	0.000	0.010	0.000	0.000	0.000	0.000
Copper	0.000	0.000	0.010	0.000	0.000	0.000	0.000
Iron	0.100	8.000	0.200	0.000	3.700	2.300	9.200
Lead	<0.030	<0.030	<0.030	<0.030	<0.030	<0.030	<0.030
Manganese	0.000	1.210	0.360	0.030	0.260	1.000	0.300
Nickel	0.000	0.000	0.000	0.000	0.000	0.000	0.000
Selenium	0.003	0.001	<0.007	<0.001	0.001	<0.001	<0.001
Silver	0.000	0.000	0.010	0.000	0.000	0.000	0.000
Zinc	0.000	0.000	0.100	0.000	0.000	0.000	0.000

Table 4.4 (con't)

Chemical Analysis of Metals in Groundwater Samples

<u>Parameters</u>	<u>Grid No.</u>		
	<u>22</u>	<u>24</u>	<u>25</u>
Arsenic	0.007	0.003	<0.001
Barium	0.000	0.000	0.000
Cadmium	0.010	0.000	0.000
Chromium (total)	0.000	0.000	0.000
Copper	0.000	0.000	0.000
Iron	0.100	0.000	0.100
Lead	<0.050	<0.050	<0.030
Manganese	0.220	0.320	0.180
Nickel	0.000	0.000	0.000
Selenium	<0.001	0.001	0.003
Silver	0.000	0.000	0.000
Zinc	0.000	0.000	0.000

4.4.4 Chemical Analysis of Organics in Soil Samples

The portable organic vapor analyzer (OVA) was used at the drill site not only for the safety of the crew but also as a means of indicating if the soils were contaminated with organics. Where there was any detection on the OVA, sediment samples were taken. The laboratory results indicated that no significant amounts of organics were in the samples tested (Appendix B).

4.4.5 Chemical Analysis for Organics in Groundwater Samples

Groundwater samples taken at Grid No. 12 contained a number of solvents that can be toxic if ingested. These include benzene, toluene, xylenes, ethylbenzene and pyridine. The remaining organic compounds found at Grid No. 12 are indicative of the deposit found at this boring (i.e., slag), and may be toxic if ingested. Though these concentrations are low, no one should be allowed to drink the groundwater in the vicinity of Grid No. 12 (Chicago Port District).

Grid No. 14 indicated 20 ppb of pyridine which can be toxic by ingestion, and 15 ppb of methylpyridine which can be moderately toxic. These concentrations are also quite low.

It would appear at this time that these contaminants are a result of the industry in this area, since Grids No. 12 and 14 are located near industrial areas. Also, both boring logs indicated large slag deposits at each of these grids.

Dibutylphthalate, found at several grids in this area, is a contaminant which is often found in chemical analyses. Its presence could be due to a number of reasons, including the lubricants off the drill rig to the plastic bottles used in taking samples for metal analysis. All concentrations found of this contaminant were at low levels.

All other grids, except where dibutylphthalate was detected, indicated no detection of organic compounds. Results are shown on the laboratory data sheets found in Appendix B.

4.4.6 Results and Recommendations Related to the Chemical Analysis of Soils and Groundwater

4.4.6.1 Results

1. Metals analyses of soil samples in this area indicated values above the normal range and means for the following: chromium, cadmium, manganese, selenium, and zinc.
2. There was no significant amount of organic compounds in any of the soil samples tested.

3. Iron, manganese, and silver levels were slightly above the General Use Water Quality Standards. However, the concentrations found indicated no potential hazard.
4. Low concentrations of several organic compounds were detected in groundwater samples taken in Grids No. 12 and 14. These appear to be the result of industrial activity in this area.

4.5 Land Pollution Control Supplemental Sampling Program

Test results from the 1983 sampling study indicated five potential problem sampling sites. These five sites had one or more metal contaminants which were found at concentrations above the common ranges and means for certain metals in the soil. The metal contaminants were chromium, cadmium, selenium, manganese, and zinc. As part of the IEPA's continued commitment to the southeast Chicago area, a supplemental soil sampling program was conducted by the Division of Land Pollution Control (DLPC) in the fall of 1984. The five sites resampled in this sampling program were: Luella Playground/School (Grid #3), Bright School (Grid #8), Addams Elementary School Playground (Grid #10), Republic Steel (Grid #14), and Wolf Lake Conservation Area (Grid #15). The sampling grid established for the general study area also applied to this supplemental study.

Manganese and zinc contents in the soil were not retested in the supplemental study conducted by the DLPC because they are generally non-toxic by ingestion and pose more of a threat to human health when they occur as airborne particles or dust.

Soil samples were collected for the metal acid digest test to determine total heavy metal content of the soil and to serve as a comparison with results from the preliminary sampling study. To determine the amount of soluble metals present, which indicates toxicity of the soil, the EP Toxicity test was conducted on samples.

4.5.1 Drilling and Sampling Methodology

Soil samples were obtained using a stainless steel hand-operated bucket auger. Sampling sites were located as close to the preliminary sites as possible. Samples were collected from depths which were determined by previous test results. Sample depths were 0" to 6" at Grids No. 14 and 15, and 6" to 2' at Grids No. 3, 8 and 10. Because of the difficulty in penetrating the soil units with hand-operated equipment, sample location and depth at Grid No. 3 had to be adjusted. The supplemental sample was located approximately 50' from the original site and was sampled at a depth of 6" to 2'.

The hand auger and sampling tools were rinsed with deionized water between samples. Soil samples were placed in airtight glass jars, sealed with evidence tape and transported to the IEPA Chicago laboratory.

4.5.2 Chemical Analysis Metals in Soils

4.5.2.1 Introduction

Soil samples were taken for both the metal acid digest and the EP Toxicity tests. The metal acid digest determines the total metal concentration in the soil, but does not indicate the amount of those metals which are soluble. The soluble metal content determines the toxicity of the soil and is found by the EP Toxicity test.

The results of the chemical analyses of metals in the soil and drilling logs for the supplementary sampling study are presented in Appendix C.

Table 4.5 summarizes preliminary and supplementary chemical analyses of metals in the soil at five supplementary sampling locations.

A discussion of the results of the chemical analyses is presented below by grid location:

Grid No. 3 (Luella Playground)

A soil sample at Grid No. 3 was collected to test for selenium. Both the preliminary (5.2 ppm) and supplementary (4.3 ppm) metal acid digest results are slightly above the common range and mean for total selenium in the soil (Lindsay, 1979). However, the EP Toxicity value of 0.028 ppm is well below the accepted maximum concentration of 1 ppm (Title 40, CFR Part 261.24 -- Maximum Concentrations of Contaminants for Characteristics of EP Toxicity). The low concentration of soluble selenium indicates non-toxic soil conditions at this sampling location.

Grid No. 8 (Bright School)

Selenium was sampled for at Grid No. 8. The metal acid digest result (5.8 ppm) is slightly above the common range and mean for total selenium in the soil. This data is similar to the preliminary study result of 4.0 ppm. Although the values for total selenium are above the common range, the EP Toxicity result of 0.039 ppm is well below the accepted maximum concentration of 1 ppm. This low concentration indicates non-toxic soil conditions.

Grid No. 10 (Addams Elementary School)

At Grid No. 10, a sample was collected to test for selenium concentrations. The metal acid digest result of 1.8 ppm fell in the upper end of the common range for total selenium in the soil. This value was similar to the preliminary result of 2.3 ppm which is slightly above the common range. At this location, non-toxic soil conditions exist because of the low concentration of soluble selenium as indicated by the EP Toxicity result of 0.054 ppm. This concentration is well below the accepted maximum concentration of 1.0 ppm.

Grid No. 14 (Republic Steel)

At Grid No. 14, a sample was collected from the slag material that covers this site. This material was tested for selenium and chromium concentrations. The metal acid digest result for selenium (1.8 ppm) falls in the upper end of the common range. The preliminary result of 2.1 ppm is slightly above the common range for total selenium in the soil. For total chromium in the soil both the preliminary (2500 ppm) and the supplementary (1921 ppm) metal acid digest results, are above the common range. Although the total metal concentrations are above their common ranges, the EP Toxicity results for both selenium (0.054 ppm) and chromium (0.01 ppm) fell well below the accepted maximum concentrations (selenium - 1.0 ppm; chromium - 5.0 ppm) for these metals. These low concentrations indicate non-toxic soil conditions at this sampling site.

Grid No. 15 (Wolf Lake Conservation Area)

To determine cadmium concentrations, a sample was collected at Grid No. 15. Results of the metal acid digest indicated that the total cadmium content of the soil was in such low concentrations that it fell below the detectable level (E 2.5 ppm) of the IEPA laboratory. The preliminary metal acid digest result (13.2 ppm) was above the common range and mean for cadmium in the soil. This difference in results could be due to local variability in the metal concentrations at this site.

The EP Toxicity result (0.01) is well below the accepted maximum concentration (1.0 ppm) of soluble cadmium in the soil, indicating non-toxic soil conditions at this sampling site.

4.5.3 Summary of Land Pollution Impacts -- Supplemental Study

1. The Division of Land Pollution Control collected samples at five locations. These sites were indicated as potentially hazardous due to their surface concentrations of specific heavy metals (selenium, chromium, cadmium).
2. In general, metal acid digest results (total metal content in soil) indicated concentrations of specific metals to be slightly above or in the upper end of their common ranges.
3. Some differences occurred between supplementary and preliminary study metal acid digest results. These differences were probably due to sampling location differences and variability in metal concentrations at these sites.
4. Although some of the metal acid digest results were above the common range for the metal, EP Toxicity results, which determine toxicity of the soil, were well below the accepted maximum concentrations for the metals.

Table 4.5

Summary of Preliminary and Supplementary Chemical Analyses
of Metals in the Soil at Five Sampling Locations

CONTAMINANT	GRID LOCATION	TYPE TEST	SAMPLE DEPTH (ppm)		
			0"-6"	6"-2'	2'-10'
SELENIUM	3	MAD*	-	4.3	(5.2)
		EPT**	-	0.028	-
	8	MAD	-	5.8 (4.0)	-
		EPT	-	0.039	-
	00	MAD	-	1.8 (2.3)	-
		EPT	-	0.054	-
	04	MAD	1.8 (2.0)	-	-
		EPT	0.054	-	-
*Common range = (0.1-2.0 ppm) Mean = 0.7 ppm **Maximum concen- tration for EP Toxicity = 1.0 ppm					
CHROMIUM	14	MAD	1921 (2500)	-	-
		EPT	0.01 ppm	-	-
Common range = (1-1,000 ppm) Mean = 100 ppm Maximum concen- tration for EP Toxicity = 5.0 ppm					
CADMIUM	15	MAD	2.5 (13.2)	-	-
		EPT	0.01 ppm	-	-
Common range = (0.01-0.7 ppm) Mean = 0.06 ppm Maximum concen- tration for EP Toxicity = 1.0 ppm					

Explanation

* MAD = Metal Acid Digest Test

** EPT = EP Toxicity Test

. () = Numbers in parenthesis indicate preliminary sampling study test results for comparison

* Common ranges and means are for the total metal content in soil and are used in discussing metal acid digest results (Lindsay, 1979)

** Accepted maximum concentrations of contaminants for characteristics of EP Toxicity

5.0 Water Pollution Assessment

The Illinois Environmental Protection Act of 1970 and the Federal Clean Water Act of 1972 provide the regulatory framework for management of water quality in Illinois. Under this far reaching legislation, mechanisms are in place to establish water quality uses, water quality standards, point source controls, compliance monitoring and enforcement through the Illinois Pollution Control Board and courts when needed.

All point source discharges are required to have an NPDES (National Pollutant Discharge Elimination System) permit which sets forth specific numerical values of chemical constituents which are not to be exceeded. Laboratory testing of the discharge is required and results are submitted to IEPA on a monthly basis. IEPA reviews the results and enforcement actions are taken when values exceed numerical criteria.

In addition to point source control activities, the IEPA has responsibility for the management of sludge from wastewater treatment works, dredge and fill activities in waters of the State, ambient water quality monitoring, and the analysis of water quality standards.

5.1 Water Resources and Surface Features

Water is a dominant feature of the Southeast Chicago study area. The primary resources include Lake Michigan, Lake Calumet and the Calumet River. In addition, the study area also has interior drainage channels which carry storm runoff and seepage waters. The key factors which influence the water uses and characteristics are as follows:

1. The waterway is used for deep draft navigation and is economically significant.
2. The natural drainage has been altered by river flow reversal and is regulated by the O'Brien Lock.
3. The quality and quantity of water in the system is generally a function of diversion from Lake Michigan. The overall water quality of the river is good.
4. Storm runoff can temporarily alter the water quality and reverse the flow of the river toward Lake Michigan.
5. The interior drainage and the river have been extensively modified.
6. The waterway requires maintenance dredging to meet navigation needs.
7. Lake Calumet is partly isolated from the main water flow of the system and tends to be more affected by local conditions, storm drainage and seepage water.

8. Subpart C, Section 303.441 of Title 35 designates the Calumet River and Lake Calumet as Secondary Contact Waters. The general use and public water supply standards do not apply to these waters.
9. The Metropolitan Sanitary District treats the industrial process waste at their facility which discharges outside of the study area. The majority of wastewater discharges to the river consist of cooling water or site runoff water.

5.2 Description of the Waterway

The Calumet River is within the corporate limits of the City of Chicago and the jurisdiction of the Metropolitan Sanitary District of Greater Chicago (MSDGC). Historically, the natural flow of the Calumet River was to Lake Michigan. This natural flow was reversed after the completion of the Calumet-Sag Channel in 1922. The flow is regulated by the operation of the O'Brien Lock. On occasion, the flow is toward Lake Michigan during periods of excessive storm runoff. The opening of controls to reverse flows is quite rare.

The Calumet River, Little Calumet River and Calumet-Sag Channel are major links in the inland waterway system that connect Lake Michigan with the Gulf of Mexico. Most of the project area is maintained for deep-draft (18-28 foot) vessels for waterborne commerce. Movements of general cargo, grain, bulk liquids and containerized cargo occur in the system. Certain shipping terminals handle foreign trade and Great Lakes movements. Lake Calumet is a natural lake which has been extensively altered and is under the jurisdiction of the Chicago Regional Port District. The south end of the lake has been partly developed as a harbor. The north half of the lake consists of diked areas which were reserved by the Port District as potential areas to place dredged material from future development. The lake has wetland areas and associated land forms which differ markedly from the river system. These areas, although disturbed by urbanization, do provide limited fish and wildlife habitat in the project area.

The quality of the fishery and associated biological communities vary within the study area. The quality of the Calumet River fishery appears to be very good and reflects the influence of the Lake Michigan fishery and dominance of the diversion water in the system. The fishery downstream of the O'Brien Lock is of lower quality. Yellow perch dominate the lakeward half of the Calumet River while bluntnose minnows are the dominant fish species in the lower half. The fishery of Lake Calumet has game species including largemouth bass, black crappie and yellow perch. The northern portion of Lake Calumet generally has higher quality fish communities than the more developed areas around the harbor complex. The lake apparently provides for a limited bass population in the river around the inlet. Localized conditions can provide for recreational fishing opportunities. Lake Calumet receives drainage from adjacent areas and is affected during periods of intense runoff.

5.3 Ambient Water Quality

Since 1958, the IEPA and its predecessor, the Bureau of Water Pollution Control of the Department of Public Health, have conducted a program of ambient stream monitoring. The purpose of this ambient monitoring is to: (1) characterize and define trends in the physical, chemical, and biological condition of the State's surface waters; (2) establish baselines of water quality; (3) identify and quantify new or existing water quality problems or problem areas; and (4) act as a triggering mechanism for intensive surveys or other appropriate actions.

The IEPA's historic (pre-1977) ambient network for the Calumet study area is identified in Figure 5.1. Between July of 1977 and December of 1978, the statewide network was substantially revised (i.e., the network was reduced from 600 to 200 stream stations). The two Calumet network stations (HAA-01 and HAA-02) in the study area were eliminated in the network redesign. The reduction of IEPA sampling sites in the Chicago area recognized that the extensive monitoring activities conducted by the Metropolitan Sanitary District of Greater Chicago (MSDGC) should supplement the IEPA's monitoring. The network redesign eliminated redundant sampling stations and the potential for duplication of monitoring effort. The MSDGC sampling stations for the study area are identified in Figure 5.2.

Agency ambient network data for the period 1967 through 1977 is summarized in Appendix D. The violations by parameter for this 10-year period are identified below:

HAA-01 (Calumet River - South of Lake Calumet)

One ammonia violation in 1974.

Five fecal violations (one each during 1974, 73, 71, 70 and 69).

Two lead violations (one each in 1974 and 1970).

One zinc violation in 1974.

One D.O. violation in 1974.

HAA-02 (Calumet River - near Lake Michigan)

One ammonia violation in 1971.

Three fecal violations (two in 1971 and one in 1968).

Three lead violations (two in 1974 and one in 1970).

Three cyanide violations (two in 1971 and one in 1970).

One HexChromium violation in 1970.




FIGURE 5.2

The Metropolitan Sanitary District of Greater Chicago
Ambient Water Quality Monitoring Network

A review of chemical water quality monitoring data from MSDGC for the period of 1970 through 1981 concludes the following:

1. "Concentrations of cyanide in the waters of the Grand Calumet River downstream of U.S. Steel Gary Works, IHC, Indiana Harbor, Lake Michigan and Calumet River have shown significant decreases over the period 1970 through 1981" (Figure 5.3).
2. "Concentrations of total suspended solids in the Grand Calumet River downstream of U.S. Steel Gary Works, IHC, Indiana Harbor, Lake Michigan and Calumet River have shown decreases over the period 1970 through 1981" (Figure 5.4).

In summary, the overall water quality of the Calumet River from Lake Calumet to Lake Michigan has been and continues to be generally good.

The physical and chemical properties of surface waters play an important role in determining its suitability for maintaining biological life. The waterway is greatly influenced by the high quality diversion waters from Lake Michigan. The quality is affected by local runoff during storm events, seepage return water, sediment reentrainment, incidental spills, and waste discharges.

Wastewater discharges entering the Calumet River are located in Figure 5.5. The general description of treatment processes, National Pollutant Discharge Elimination System (NPDES) permit information, and compliance data are contained in Appendix E. In general, most discharges release cooling water or noncontaminated stormwater runoff. These discharges have been previously found to be in substantial compliance with the National Pollution Discharge Elimination System.

Most of the industrial process waste is tributary to the MSDGC system and is treated and discharged outside of the study area. However, pollution can occur during storm periods if the sewer system becomes overloaded and can result in a combined sewer overflow to the river.

5.4 Area Issues and Problems

Various water pollution control problems have occurred which are routinely handled by ongoing programs or special efforts. Periodic navigation hazards, such as spills, are handled by the IEPA's Emergency Response Unit and usually include coordination with other agencies, such as the U.S. Coast Guard, Corps of Engineers, MSD, the Department of Conservation, and the Illinois Division of Water Resources. Since MSD has assumed the primary responsibility for monitoring of waterways within its jurisdiction, they are often involved with these efforts.




FIGURE 5.3

Total Cyanide Concentrations in the Calumet River in Illinois for 1970 through 1981




FIGURE 5.4

Total Suspended Solids Concentrations in the
Calumet River in Illinois for 1970 through 1981




FIGURE 5.5

Wastewater Discharges Entering the Calumet River

An Interagency Task Force composed of the Illinois Division of Water Resources, the IEPA and the Metropolitan Sanitary District is currently responding to issues raised by the Chicago Regional Port District. As a result of a meeting held in November of 1982, a reconnaissance study is underway to monitor and evaluate tributary inflow impacts on Lake Calumet. The MSD has undertaken a sampling program which responds to potential runoff problems from the Venetian Canal. Analyses of information and data, once collected, will determine if a problem exists and the extent of the problem. Preliminary findings indicate that the canal discharge, which includes operation of a pump station near the expressway, contains a large solids content during storms. The Department of Transportation has already taken certain remedial steps in the right-of-way of the expressway and pumping station.

The Corps of Engineers has filed a final Environmental Impact Statement for "Chicago Area Confined Disposal Facility and Maintenance Dredging" in Cook County, Illinois. The project is designed to handle disposal of material from the Calumet River and harbor to maintain federal deep-draft navigation channels. A waiver of the 25 percent non-federal contribution of the Port District required a certified Water Quality Management Plan and compliance of dischargers in the area. The IEPA certified the Lake Michigan South plan, which was approved by USEPA on September 16, 1981. Based upon this plan and the determination that compliance of facility dischargers is processed according to the plan, the USEPA provided a waiver requested under Section 123(d) of the Rivers and Harbors Act of 1970. An IEPA permit to the Corps of Engineers has been issued for the facility construction and operation. The Confined Disposal Facility (CDF) is located at the mouth of the Calumet River, adjacent to Iroquois Landing Lakefront Terminal. The two year construction period is nearly completed, and the CDF is expected to begin receiving dredged material in the fall of 1985.

In January of 1984, the Chicago Regional Port District released the Comprehensive Plan 1984, a new ten year master plan for the development of Lake Calumet. The plan proposes redesigning Lake Calumet to provide more landfill area for non-shipping uses such as industrial, commercial, and service establishments, a marina, and a recreational lake and park. A copy of the Comprehensive Plan 1984 is included in Appendix J.

The Port District's enabling act requires that all changes and modifications to existing harbor plans and any comprehensive plan for the Port District shall be submitted to the Illinois Department of Transportation for approval.

5.5 Water Pollution Additional Studies

5.5.1 Lake Calumet Fish Flesh Sampling

As part of the IEPA commitment to this study, the Division of Water Pollution Control (DWPC) collected fish flesh samples in Lake Calumet. The sampling took place on October 6, 1983 and was jointly conducted by the IEPA and the Chicago Metropolitan Sanitary District. The laboratory analyses of the fish samples were conducted by the Illinois Department of Public Health.

The results of contaminant analyses for the fish are given in Table 5.1. As indicated in the table, all sample contaminant levels were below the Food and Drug Administration action levels. Action levels are limits on the amount of contaminants present in fish flesh. When action levels are exceeded, it is recommended that the fish not be consumed. Based upon the samples taken in Lake Calumet on October 6, 1983 and the information contained in Table 5.1, a problem does not appear to exist with fish in Lake Calumet.

Table 5.1

Fish Contaminant Analysis for Lake Calumet

<u>Parameter</u>	<u>Action Level</u>	<u>LM Bass</u>	<u>Carp</u>	<u>W. Crappie</u>
PCB (estimated as 1254)	5.0	0.219	0.631	0.263
Hexachlorobenzene	-	Tr	Tr	Tr
Hexachlorocyclohexanes (BHC)	-	Tr	Tr	Tr
Heptachlor epoxide	0.3	Tr	Tr	Tr
Chlordanes	0.3	Tr	0.014	Tr
DDT and analogs	5.0	0.018	0.069	0.022
Dieldrin	0.3	Tr	Tr	Tr
Endrin	-	Tr	-	-
trans-Nonachlor	-	Tr	Tr	Tr
Percent Fat	-	1.6	2.8	1.2

Tr = <0.01 ppm

Contaminant analysis of largemouth bass, carp, and white crappie fillets collected in 10/6/83 in Lake Calumet. Fish lengths/weights are provided below. Concentrations are given in mg/kg (parts per million).

	<u>lengths</u>	<u>weights</u>
L.M. Bass	(180/169/159/163/165 mm)	(75/62/44/59/69 g)
Carp	(520/578/493/516/511 mm)	(4.0/5.5/3.3/4.0/4.4 lbs)
W. Crappie	(209/187/199/163/181 mm)	(120/72/98/34/72 g)

6.0 Air Pollution Assessment

6.1 Introduction

6.1.1 Ambient Air Quality Standards

The 1970 Clean Air Act Amendments required the Administrator of the USEPA to promulgate National Ambient Air Quality Standards (NAAQS) for five pollutants: total suspended particulates (TSP), sulfur dioxide (SO₂), nitrogen oxides (NO_x), ozone (O₃), and carbon monoxide (CO). These standards were promulgated in early 1971. In addition, an NAAQS was established in 1978 for lead (Pb).

Consistent with the intent of the Illinois Environmental Protection Act and the Federal Clean Air Act, Illinois has adopted ambient air quality standards that specify maximum permissible short-term and long-term concentrations of various contaminants in the atmosphere. These standards are set for the purpose of protecting the public health and welfare.

Air contaminants increase the aggravation and the production of respiratory and cardiopulmonary diseases. Air quality standards which have been set to protect public health are called primary standards.

Public welfare includes, among other things, effects on crops, vegetation, wildlife, visibility and climate, as well as effects on materials, economic values and on personal comfort and well-being. Standards set to protect public welfare are called secondary standards.

The Illinois and National Ambient Air Quality Standards are presented in Table 6.1. These standards are legally enforceable limitations, and any person causing or contributing to their violation is subject to enforcement proceedings under the Environmental Protection Act. The standards have been used as a basis for the development of implementation plans by the State for the abatement and control of pollutant emissions from existing sources, and to ensure that population, industrial and economic growth trends do not add to the region's air pollution problems.

6.1.2 Non-Criteria Pollutants

Pollutants not regulated by NAAQS, or "non-criteria" pollutants, may be regulated through other mechanisms. USEPA uses Sections 111 (New Source Performance Standards, NSPS) and 112 (National Emission Standards for Hazardous Air Pollutants, NESHAPS) of the Clean Air Act to control several other pollutants on a source-by-source basis. In general, Section 112 (NESHAPS) is used to control highly toxic and widespread pollutants, while Section 111 (NSPS) is used to control pollutants of lesser toxicity. Regulations under both sections take the form of performance standards for control of specific pollutants from specific sources.

Table 6.1

**Summary of National and Illinois¹
Ambient Air Quality Standards**

<u>POLLUTANT</u>	<u>TIME OF AVERAGE</u>	<u>PRIMARY STANDARD (AT 25°C and 760 mm of HG)</u>	<u>SECONDARY STANDARD</u>
Particulate Matter (TSP)	Annual Geometric Mean 24-hour	75 ug/m ³ 260 ug/m ³	60 ug/m ³ 150 ug/m ³
Sulfur Dioxide (SO ₂)	Annual Arithmetic Mean 24-hour 3-hour	0.03 ppm (80 ug/m ³) 0.14 ppm (365 ug/m ³) None	None None 0.5 ppm (1300 ug/m ³)
Carbon Monoxide (CO)	8-hour 1-hour	9 ppm (10 mg/m ³) 35 ppm (40 mg/m ³)	Same as Primary Same as Primary
Ozone (O ₃)	1-hour/day	0.12 ppm (235 ug/m ³)	Same as Primary
Nitrogen Dioxide (NO ₂)	Annual Arithmetic Mean	0.05 ppm (100 ug/m ³)	Same as Primary
Lead (Pb)	Quarterly Arithmetic Mean	1.5 ug/m ³	Same as Primary

¹ Illinois Air Quality Standards are identical to National Air Quality Standards.

NOTE: All standards with averaging time of 24 hours or less are not to be exceeded more than once per year.

The standard setting process begins with a screening and ranking of possible toxic pollutants. For the highest ranked pollutants, health assessments and population exposure assessments are performed to determine the potential magnitude of the public health hazard associated with a given pollutant. Based upon the results of these assessments, the decision is made regarding whether a pollutant should be regulated under Section 112, Section 111, or not regulated at all, depending upon the severity of the hazard posed.

Once it has been decided to regulate a pollutant under either Section 111 or 112, the source categories (types of industries) are ranked according to the efficiency and effectiveness of achieving hazard reductions by regulating that source. Performance standards are then developed and promulgated for the highest ranked source categories. The Illinois Environmental Protection Act provides for the adoption of these standards as law in Illinois.

To date, regulations are in effect under Section 112 for mercury, vinyl chloride, beryllium, and asbestos. Regulations have been proposed by USEPA for benzene, arsenic, and radionuclides. The pollutants regulated under Section 111 are sulfuric acid mist, hydrogen sulfide, reduced sulfur compounds, and fluorides. Also, regulations have been proposed by USEPA for certain solvents.

6.1.3 State Implementation Plan Process

Under the requirements of the federal Clean Air Act, each state is given the responsibility of developing and administering its own air pollution control program to attain and maintain the national ambient air quality standards for various pollutants. That program is known as the State Implementation Plan (SIP) for air pollution control. The Illinois SIP is a massive, technical blueprint for restoring and preserving a healthy air-pollution-free environment. It is more than a compendium of specifications that air quality must meet and more than a list of the minimum technical requirements that air pollution sources must adhere to: it defines the process by which air pollution goals will be achieved, explains why certain air pollution controls were selected over alternatives, and describes the relationships among the organizations involved in restoring and maintaining a healthy environment.

The SIP is a dynamic document that changes in response to changing Clean Air Act requirements and State environmental goals. The air pollution regulations limiting the quantities of pollutants emitted from various industrial processes are the heart of the SIP and are subject to a public hearing process before the Illinois Pollution Control Board. After this process is complete, the final rules are incorporated in a comprehensive SIP document for review and approval by the USEPA. Once approved by the USEPA, the rules formally become a part of the approved SIP and, as such, are federally enforceable.

6.2 Description and Characterization of Air Pollutant Emissions and Major Emission Sources in the Southeast Chicago Study Area

6.2.1 Point Source Emissions Inventory

To conduct air quality analyses, a vast amount of data is needed concerning air pollution sources and the pollutants they discharge. The term "emissions inventory" has become the umbrella term for the wide range of information needed for air pollution studies. The data that compose the core of any inventory are the listing of sources and the amounts of air pollutants they discharge into the atmosphere. Other data common to most inventories include type of fuel used, hours of operation, average and maximum throughput, and controlled and uncontrolled emission rates.

The emissions inventory used in this study, included in Appendix F, along with the map of air pollution emission sources (Figure 6.1), allow the reader to determine the type and density of air pollution sources in different sectors of the defined study area.

6.2.2 Major Point Sources

Facilities which emit over 100 tons per year of any single pollutant are generally termed major point sources. Such facilities are identified in Appendix F as those facilities which have a sequential number written in the left margin. The locations of these facilities with their identifying number have been plotted on a map of the study area in Figure 6.1. Twenty-two major facilities are identified.

LB:sp/219d/1-100




FIGURE 6.1

Major Air Pollution Emission Sources in the South Chicago Study Area

6.2.3 Area Sources

Normally, the term "area sources" is applied to sources of pollution which are spread over large expanses or are too small and numerous to treat individually. Agricultural areas which are sources of windblown dust or automobile traffic on city streets are examples of area sources. Residential heating units as a source of sulfur dioxide would represent a class of area sources which are both small and numerous. Odor emissions from landfill sites are another example of an area source. How area sources are dealt with really depends upon the pollutant being investigated and the scale of the study area.

Previously, emissions of O_3 , TSP, SO_2 and NO_x have been studied by the IEPA in regional analyses of the Chicago area. Area sources of these pollutants were allocated throughout the Chicago region including the Lake Calumet area. The emissions inventories are available in IEPA reports. The usefulness of these inventories should be reevaluated if they are to be applied to a smaller scale study of the Lake Calumet area. Additionally, emissions of lead (both point and area sources) have been studied, specifically in the steel mill area. Figure 6.2 shows the roadways analyzed as area sources in the study area. Composite exhaust emissions for the steel mill study area are shown in Appendix H. These values were determined from the following data sources: traffic volumes obtained from the Chicago Area Transportation Study (CATS) and the Illinois Department of Transportation (IDOT); average vehicle speeds also obtained from CATS; traffic composition, that is, fractions of vehicle miles traveled (VMT) by vehicle type were specified for freeways and arterial streets based on data developed by CATS; and VMT growth factors which were determined by comparing 1978 volume to 1983 and 1985 estimates provided by CATS.

6.3 Description and Characterization of Ambient Air Pollution Levels

6.3.1 Air Quality Monitoring Network

Ambient air monitoring has been conducted in and around the study area since the early 1960's by both state and local air pollution control agencies. The available air quality data base is composed primarily of total suspended particulate (TSP) data and data resulting from the chemical analysis of TSP filter samples. The air quality data base is maintained both at the IEPA headquarters and at the USEPA's National Aerometric Data Bank (NADB).

The monitoring network operated in 1984 is depicted in Figure 6.3. TSP monitors were located at the Addams, Anthony, Carver and Washington sites. The Addams site also measured NO_2 levels. Ambient O_3 concentrations were measured at the Roseland and Southeast (S.E.) Police Station sites with the S.E. Police Station site also measuring SO_2 levels. PM_{10} concentrations were measured at Washington High School in 1984. An additional PM_{10} and TSP monitor has been installed at Bright School and is collecting data in 1985.




FIGURE 6.2

Roadways Analyzed as Area Sources in the Chicago Steel Mills Study Area




FIGURE 6.3

South Chicago Ambient Air Monitoring Network
in 1983

Total suspended particulate, PM₁₀ and NO₂ data are of the noncontinuous type; that is, the monitors collect an integrated sample over a 24-hour period which is normally a calendar day. Samples are collected on a USEPA nationally coordinated sampling schedule which specifies samples to be collected once every six days, translating to about 60 sampled days per year.

Continuous measurements are made for SO₂ and O₃ and are reported as hourly averages. The monitors utilized are either reference method instruments or equivalent, as required by the USEPA, and are subjected to the statewide quality assurance program.

6.3.2 Air Quality Summary and Trends

The following criteria pollutants are currently being monitored in the study area and have historical data from which to determine trends: total suspended particulates (TSP), lead (Pb), sulfur dioxide (SO₂), nitrogen dioxide (NO₂), and ozone (O₃). The only criteria pollutant not currently monitored in the study area is carbon monoxide (CO). In addition to criteria pollutants, trace analyses are performed on the TSP filters for sulfates, nitrates, copper, iron, and manganese.

Although TSP concentrations have been decreasing significantly since 1976, as late as 1980 all four sites in the study area exceeded the primary annual standard (Table 6.2). In 1984, only the Washington H.S. site in the study area exceeded the primary annual standard. A decrease is also apparent in the peak 24-hour averages as represented by the second high value for each year (Table 6.3). Year-to-year fluctuations are inherently greater in the short-term averages; however, the short-term values have been lower in the most recent years, especially 1981, 1982 and 1984.

Lead concentrations are also decreasing as represented by the peak quarterly averages in each year (Table 6.4). Violations of the current lead standard were recorded in 1974 and 1975 but there have been no violations since then. The area average of the peak quarterly lead values has decreased to less than a third of the standard in the last three years.

Since no air quality standards exist for the TSP trace element analyses (other than lead), the study area averages are compared to Illinois statewide averages (Table 6.5). On this basis, the study area averages for the trace constituents listed are consistently higher than the statewide averages.

Sulfur dioxide has been monitored with continuous instruments in the study area for less than three years, an insufficient time to determine trends. However, the most recent data indicates SO₂ concentrations well below the annual and 24-hour primary standards and the 3-hour secondary standard (Table 6.6).

Ozone has been monitored at two different sites since 1978. Although one of the sites, Roseland Pump Station, is located outside the study area, the data should be representative of the area. There is no clear trend since 1978 in either the peak concentrations or the number of days exceeding the standard (Table 6.7). Some years have been below the standard and other years have been above the standard.

Nitrogen dioxide has been monitored at Addams Elementary School since 1974 (Table 6.8). The annual averages had an upward trend from 1974-1979, followed by a downward trend from 1979-1984. The annual primary standard was not exceeded during any of the years. The trend in NO₂ levels in the study area parallels that of other areas of Chicago and Cook County during this time period. However, the magnitude of NO₂ concentrations in the study area has generally been lower than in some other parts of Chicago and Cook County.

Table 6.2

Total Suspended Particulate Trends

<u>Site</u>	<u>Address</u>	<u>Annual Geometric Means (ug/m³)</u>										
		<u>0974</u>	<u>0975</u>	<u>0976</u>	<u>0977</u>	<u>0978</u>	<u>0979</u>	<u>0980</u>	<u>0980</u>	<u>0982</u>	<u>0983</u>	<u>0984</u>
Addams Elementary School	10810 S. Ave H	129	105	131	118	108	107	94	86	78	78	75
Anthony Elementary School	9800 S. Torrence	95	86	90	88	88	96	96	84	66	68	68
Carver High School	801 E. 133rd Place	73	73	91	83	85	92	96	75	71	--	70
Washington High School	3500 E. 114th St.	153	148	175	170	121	129	119	111	86	93	85
Study Area Average		113	103	122	115	101	106	101	89	75	80	75

Table 6.3

Total Suspended Particulate Trends

<u>Site</u>	<u>Address</u>	<u>Second-High 24-Hour Average (ug/m³)</u>										
		<u>0974</u>	<u>0975</u>	<u>0976</u>	<u>0977</u>	<u>0978</u>	<u>0979</u>	<u>0980</u>	<u>0980</u>	<u>0982</u>	<u>0983</u>	<u>0984</u>
Addams Elementary School	10810 S. Ave H	318	229	494	351	244	220	188	177	189	265	179
Anthony Elementary School	9800 S. Torrence	250	197	202	248	230	330	226	175	155	190	148
Carver High School	801 E. 133rd Place	211	167	317	285	199	248	373	164	193	215	209
Washington High School	3500 E. 114th St.	506	367	452	688	278	294	226	229	198	317	233
Study Area Average		321	240	366	393	238	273	253	186	184	247	192

Table 6.4

Lead Trends

<u>Site</u>	<u>Address</u>	<u>Maximum Quarterly Average (ug/m³)</u>										
		<u>0974</u>	<u>0975</u>	<u>0976</u>	<u>0977</u>	<u>0978</u>	<u>0979</u>	<u>0980</u>	<u>0980</u>	<u>0982</u>	<u>0983</u>	<u>0984</u>
Addams Elementary School	10810 S. Ave H	.90	.80	.50	.40	.70	.73	.48	.39	.41	.55	.44
Anthony Elementary School	9800 S. Torrence	1.70	.70	.80	.40	.90	1.00	1.10	.49	.44	.41	.33
Carver High School	801 E. 133rd Place	.70	.50	.60	.40	.70	.80	.65	.32	.28	.38	.35
Washington High School	3500 E. 114th St.	1.60	1.60	1.20	1.20	.80	.91	1.18	.89	.81	.66	.68
Study Area Average		1.23	.90	.78	.60	.78	.86	.85	.52	.49	.50	.45

Table 6.5

Total Suspended Particulate Trace Analyses

1982 Annual Arithmetic Means (ug/m³)

<u>Site</u>	<u>Address</u>	<u>Sulfate</u>	<u>Nitrate</u>	<u>Copper</u>	<u>Iron</u>	<u>Manganese</u>
Addams Elementary School	10810 S. Ave H	13.6	6.3	.29	1.06	.18
Anthony Elementary School	9800 S. Torrence	10.9	6.0	.25	.80	.12
Carver High School	801 E. 133rd Place	11.8	6.4	.36	.75	.11
Washington High School	3500 E. 114th St.	13.7	6.6	.11	1.79	.27
Study Area Average		12.5	6.3	.25	1.10	.17
Illinois Statewide Average		10.5	5.0	.21	.75	.05

Table 6.6

Sulfur Dioxide Trends

<u>Site</u>	<u>Address</u>	<u>Annual Arithmetic Means (ppm)</u>			
		<u>0980</u>	<u>0982</u>	<u>0983</u>	<u>0984</u>
Southeast Police Station	103rd and Luella	+	.008	.008	.008

<u>Site</u>	<u>Address</u>	<u>Second-High 24-Hour Averages (ppm)</u>			
		<u>0980</u>	<u>0982</u>	<u>0983</u>	<u>0984</u>
Southeast Police Station	103rd and Luella	.064	.061	.050	.053

<u>Site</u>	<u>Address</u>	<u>Second-High 3-Hour Averages (ppm)</u>			
		<u>0980</u>	<u>0982</u>	<u>0983</u>	<u>0984</u>
Southeast Police Station	103rd and Luella	.119	.106	.107	.126

+ Insufficient data for valid annual average

Table 6.7

Ozone Trends

<u>Site</u>	<u>Address</u>	<u>Maximum Hourly Average (ppm)</u>						<u>0984</u>
		<u>0978</u>	<u>0979</u>	<u>0980</u>	<u>0980</u>	<u>0982</u>	<u>0983</u>	
Roseland Pump Station ^A	351 W. 104th St.	.159	.111	--	.167	--	--	--
Southeast Police Station	103rd and Luella	--	--	--	--	.119	.163	.114

<u>Site</u>	<u>Address</u>	<u>Number of Days with Hours \geq 0.02 ppm</u>						<u>0984</u>
		<u>0978</u>	<u>0979</u>	<u>0980</u>	<u>0980</u>	<u>0982</u>	<u>0983</u>	
Roseland Pump Station ^A	351 W. 104th St.	10	0	--	2	--	--	--
Southeast Police Station	103rd and Luella	--	--	--	--	0	2	0

-- Site not in operation during year

^ASite not located in study area, but data should be representative of study area

Table 6.8

Nitrogen Dioxide Trends

<u>Site</u>	<u>Address</u>	<u>Annual Arithmetic Means (ppm)</u>										
		<u>0974</u>	<u>0975</u>	<u>0976</u>	<u>0977</u>	<u>0978</u>	<u>0979</u>	<u>0980</u>	<u>0980</u>	<u>0982</u>	<u>0983</u>	<u>0984</u>
Addams Elementary School	10810 S. Ave H	.031	.031	.034	.038	.037	.045	.036	.031	.028	.030	.029

6.3.3 Summary of Health Effects Associated with Violations of the NAAQS

6.3.3.1 Particulate Matter

Particulate matter in the atmosphere consists of solids, liquids, and liquids-solids in combination. Suspended particulates generally refer to particles less than 100 microns in diameter (human hair is typically 100 microns thick). Particles larger than 100 microns will settle out of the air under the influence of gravity in a short period of time. Particles which cause the most health and visibility difficulties are those less than 1.0 microns in size because they can penetrate to the deep lung. These particles are also the most difficult to reduce in numbers by the various industrial removal techniques. Rainfall-washout accounts for the major removal of these smaller particles from the air. Particulate pollutants enter the human body by way of the respiratory system and their most immediate effects are upon this system. The size of the particle determines its depth of penetration into the respiratory system. Particles over 5 microns are generally deposited in the nose and throat. Those that do penetrate deeper in the respiratory system to the air ducts (bronchi) are often removed by ciliary action. Particles ranging in size from 0.5 - 5.0 microns in diameter can be deposited in the bronchi, with few reaching the air sacs (alveoli). Most particles deposited in the bronchi are removed by the cilia within hours. Particles less than 0.5 microns in diameter reach and may settle in the alveoli. Removal of particles from the alveoli is much less rapid and complete than from the larger passages. Some of the particles retained in the alveoli are absorbed into the blood.

Besides particulate size, the oxidation state, chemical composition, concentration, and length of time in the respiratory system contribute to the health effects of particulates. In addition, the presence of other pollutants in the atmosphere, especially sulfur dioxide (SO_2), may affect the hazard posed by particulates. In fact, because particulates and SO_2 are almost always present together, it has been difficult to determine what the health effects are of particulates alone.

Epidemiological studies have demonstrated that excessive particulate levels have been associated with increased mortality and sickness, particularly among the elderly and the chronically ill. Aggravation of chronic respiratory diseases (asthma, bronchitis, emphysema) and heart diseases are most commonly associated with particulate pollution.

6.3.3.2 Sulfur Dioxide

Once in the atmosphere, some SO_2 can be oxidized (either photochemically or in the presence of a catalyst), to SO_3 (sulfur trioxide). With water vapor present, SO_3 is readily converted to sulfuric acid mist. Other basic oxides combine with SO_3 to form sulfate aerosols. Sulfuric acid droplets and other sulfates are thought to account for about 5 to 20 percent of the total suspended particulate

matter in urban air. Additionally, these compounds can be transported long distances and come back to earth as a major constituent of acid precipitation. Many of the resultant health problems attributed to SO_2 may be a result of the oxidation of SO_2 to other compounds.

The effects of SO_2 on health are irritation and inflammation of tissue that it directly contacts. Inhalation of SO_2 causes bronchial constriction resulting in an increased resistance to air flow, reduction of air volume, and an increase of respiratory rate and heart rate.

Sulfur dioxide can exacerbate pre-existing respiratory diseases (e.g., asthma, bronchitis, and emphysema). The enhancement (synergism) by particulate matter of the toxic response to SO_2 has been observed under conditions which would promote the conversion of SO_2 to sulfuric acid. The degree of enhancement is related to the concentration of particulate matter. A twofold to threefold increase of the irritant response to SO_2 is observed in the presence of particulate matter capable of oxidizing SO_2 to sulfuric acid.

Sulfuric acid inhalation causes an increase in the respiratory system's mucous secretions, which reduces the system's ability to remove particulates via mucociliary clearance. This can result in an increased incidence of respiratory infection.

6.3.3.3 Carbon Monoxide

The toxic effects of high concentrations of carbon monoxide (CO) on the body are well known. Carbon monoxide is absorbed by the lungs and reacts with hemoglobin (the oxygen carrying molecule in the blood) to form carboxyhemoglobin (COHb). This reaction reduces the oxygen carrying capacity of blood because the affinity of hemoglobin for CO is over 200 times that for oxygen. The higher the percentage of hemoglobin bound up in the form of carboxyhemoglobin, the more serious is the health effect.

The level of COHb in the blood is directly related to the CO concentration of the inhaled air. For a given ambient air CO concentration, the COHb level in the blood will reach an equilibrium concentration after a sufficient time period. This equilibrium COHb level will be maintained in the blood as long as the ambient air CO level remains unchanged. However, the COHb level will slowly change in the same direction as the CO concentration of the ambient air as a new equilibrium of CO in the blood is established.

The lowest CO concentrations shown to produce adverse health effects result in aggravation of cardiovascular disease. Studies demonstrate that these concentrations have resulted in decreased exercise time before the onset of pain in the chest and extremities of individuals with heart or circulatory disease. Slightly higher CO levels have been associated with decreases in vigilance, ability to discriminate time intervals, and exercise performance.

Evidence also exists indicating a possible relationship between CO and heart attacks, the development of cardiovascular disease, and fetal development.

Studies on the existing ambient levels of CO do not indicate any adverse effects on vegetation, materials, or other aspects of human welfare.

6.3.3.4 Nitrogen Oxides

There is a lack of strong evidence associating health effects with most nitrogen oxide compounds (NO_x). NO_2 , however, has been clearly established as exerting detrimental effects on human health and welfare.

NO_2 can cause an impairment of dark adaptation at concentrations as low as 0.07 ppm (parts per million). NO_2 can cause an increase in airway resistance, an increase in respiratory rate, an increase in sensitivity to bronchoconstrictors, a decrease in lung compliance, and an enhanced susceptibility to respiratory infections. NO_2 is a deep lung irritant capable of producing pulmonary edema if inhaled in sufficient concentrations. When NO_2 is inhaled in concentrations with other pollutants, the effects are additive.

NO_x may also react with water to form corrosive nitric acids, a major component of acid precipitation. Additionally, NO_x and various other pollutants (e.g., hydrocarbons) may react in the presence of sunlight to produce photochemical oxidants. These are extremely unstable compounds which damage plants and irritate both the eyes and respiratory system of people. Ozone and a group of chemicals called peroxyacetylnitrates (PAN) are the major constituents of photochemical oxidants.

6.3.3.5 Ozone

Injury to vegetation is one of the earliest manifestations of photochemical air pollution, and sensitive plants are useful biological indicators of this type of pollution. The visible symptoms of photochemical oxidant produced injury to plants may be classified as: (1) acute injury, identified by cell collapse with subsequent development of necrotic patterns (visible damage caused by the death of tissue); (2) chronic injury, identified by necrotic patterns or with other pigmented patterns; and (3) physiological effects, identified by growth alterations, reduced yields, and changes in the quality of plant products. The acute symptoms are generally characteristic of a specific photochemical oxidant, though chronic injury patterns are not. Ozone injury to leaves is identified as a strippling or flecking. Adverse effects on sensitive vegetation have been observed from exposure to photochemical oxidant concentrations of about 100 ug/m^3 (0.05 ppm) for four hours.

Adverse effects on materials (rubber products and fabrics) from exposure to photochemical oxidants have not been precisely quantified, but have been observed at the levels presently occurring in many urban atmospheres (including the study area).

Ozone accelerates the aging of many materials, resulting in rubber cracking, dye fading, and paint erosion. These effects are linearly related to the total dose of O_3 and can occur at very low levels, given long duration exposures.

Ozone is a pulmonary irritant that affects the respiratory mucous membranes, other lung tissues and respiratory functions. Clinical and epidemiological studies have demonstrated that O_3 impairs the normal mechanical function of the lung, causing alterations in respiration, the most characteristic of which are shallow, rapid breathing and a decrease in pulmonary compliance (ability of the lung to expand and contract during normal breathing). Exposure to O_3 results in clinical symptoms such as chest tightness, coughing, and wheezing. Alterations in airway resistance can occur, especially to those with respiratory diseases (asthma, bronchitis, emphysema). These effects may occur in sensitive individuals, as well as in healthy exercising persons, at short-term ozone concentrations between 0.15 and 0.25 ppm.

Ozone exposure increases the sensitivity of the lung to bronchoconstrictive agents such as histamine, acetylcholine, and allergens, as well as increasing the individual's susceptibility to bacterial infection. Simultaneous exposure to O_3 and SO_2 can produce larger changes in pulmonary function than exposure to either pollutant alone.

6.3.3.6 Lead

Lead is a stable compound which persists and accumulates both in the environment and in the human body. Lead enters the human body through ingestion and inhalation with consequent absorption into the blood stream and distribution to all body tissues. Clinical, epidemiological and toxicological studies have demonstrated that exposure to lead adversely affects human health.

Low level lead exposure has been found to interfere with specific enzyme systems and blood production. Kidney and neurological cell damage has also been associated with lead exposure. Animal studies have demonstrated that lead can contribute to reduced fertility and birth defects. Children are the population segment most sensitive to many of lead's adverse effects.

Other serious potential effects from lead exposure are behavioral. Brain damage has been well documented in cases of severe lead poisoning in children. Restlessness, headaches, tremors, and general symptoms of mental retardation have been noted. The brain seems to be particularly

sensitive to lead poisoning, yet it is unclear whether low level exposure will result in brain disfunction. Although evidence exists which indicates that children with above-normal blood lead levels are more likely to demonstrate poor academic performance, the studies remain inconclusive.

6.4 Discussion of Pollutant Transport Mechanisms and Associated Analytical Techniques

6.4.1 Meteorology

The Chicago study area is along the southwest shore of Lake Michigan and occupies a plain which, for the most part, is only some tens of feet above the lake. Lake Michigan averages 579 feet above mean sea level. Topography does not significantly affect air flow in or near the study area, except that lesser frictional drag over Lake Michigan causes winds to be frequently stronger along the lakeshore, and often permits air masses moving from the north to reach shore areas an hour or more before affecting western parts of the city.

Chicago is in a region of frequently changeable weather. The climate is predominately continental, ranging from relatively warm in summer to relatively cold in winter. However, the continentality is partially modified by Lake Michigan, and to a lesser extent by other Great Lakes. In late autumn and winter, air masses that are initially very cold often reach the city only after being tempered by passage over one or more of the lakes. Similarly, in late spring and summer, air masses reaching the city from the north, northeast or east are cooler because of movement over the Great Lakes. Very low winter temperatures most often occur in air that flows southward to the west of Lake Superior before reaching the Chicago area. In summer, the higher temperatures are with south or southwest flow and are therefore not influenced by the lakes, the only modifying effect being a local lake breeze. Strong south or southwest flow may overcome the lake breeze and cause high temperatures to extend over the entire city.

During the warm season, when the lake is cold relative to land, there is frequently a lake breeze that reduces daytime temperature near the shore, sometimes by 10° or more below temperatures farther inland. When the breeze off the lake is light, this effect usually reaches inland only a mile or two, but with stronger on-shore winds the whole city is cooled. On the other hand, temperatures at night are warmer near the lake so that 24-hour averages on the whole are only slightly different in various parts of the city and suburbs.

In summer, a combination of high temperature and humidity may develop, usually building up progressively over a period of several days when winds continue out of the south or southwest, becoming oppressive for one or perhaps several days, then ending abruptly with a shift of winds to northwest or northerly. The change may be preceded or accompanied by thundershowers. High relative humidity often results from wind flow off the lake, but the air is then cooler and not oppressive.

Chicago Midway Airport, which is approximately 10 miles northwest of the study area, has complete climatological records available. The annual mean temperature at Chicago Midway Airport is 50°F, and the monthly normal mean temperatures range from 26° in January to 76° in July. In January, the mean daily maximum temperature is 33°, the mean minimum 19°. In July, the corresponding figures are 86° and 66°. The lowest official temperature ever recorded is -23°, measured downtown in December of 1872. The highest temperature to occur at Midway Airport since it became the official station is 104° in June of 1953, but an official record of 105° was recorded at The University of Chicago on July 24, 1934, and a still higher temperature of 109° occurred on July 23, 1934 at Midway Airport before it was the official station. The average annual number of days at Midway Airport with 0° or lower is 7, and with 90° or higher is 26. The number of days with 90° or higher is considerably less near the lake shore. The normal number of heating degree days is 6,113.

Precipitation that falls in the study area normally results from air that has passed over the Gulf of Mexico. But, in winter, there is sometimes snowfall, light inland but locally heavy near the lakeshore, with Lake Michigan as the principal moisture source. The heavy lakeshore snow occurs when colder air moves from the north with a long trajectory over Lake Michigan and impinges on the Chicago lakeshore. In this situation, the air mass is warmed and its moisture content increased up to a height of several thousand feet. Snowfall is produced by upward currents that become stronger because of frictional effects, when the air moves from the lake onto land. This type of snowfall, therefore, tends to be heavier and to extend farther inland in south-shore areas of the city and in Indiana suburbs, where the angle between wind-flow and shoreline is greatest. The effect of Lake Michigan, both on winter temperatures and lake-produced snowfall, is enhanced by non-freezing of much of the lake during the winter, even though areas and harbors are often ice-choked. This type of local heavy snowfall may occur once or a few times in a normal season.

Summer thundershowers are often locally heavy and variable; parts of the city may receive substantial rainfall and other parts none. Longer periods of continuous precipitation are mostly in autumn, winter, and spring. About one-half the precipitation in winter, and about 10 percent of the yearly total precipitation, falls as snow. Snowfall from month to month and year to year is greatly variable. There is a 50 percent likelihood that the first and last 1-inch snowfall of a season will occur by December 5 and March 20, respectively. The corresponding dates for the first and last 3-inch snowfall are December 24 and March 2. Freezing rain sometimes occurs but is usually light. During the cold season, slight melting and refreezing of precipitation is a fairly common hazard to highway traffic.

Fog is infrequent. Visibility is much more often restricted by local air pollution, a condition that is worst during the heating season, but which continues throughout the year because of extensive industrial activity.

The amount of sunshine is moderate in summer and quite low in winter. A considerable amount of cloudiness, especially in winter, is locally produced by the lake effect. Days in summer with no sunshine are rare. The total sunshine in December, partly because of shorter days, is only a little over one-third the July total.

For much of the time in autumn, winter and spring, smoke and other air pollution is carried away by winds, sometimes rapidly; however, on some occasions when there is little or no wind, the pollution accumulates, especially during night and early morning hours. Summertime air pollution may be less, partly because of lesser output, but also because of better vertical dispersal; on the other hand, on many summer days surface wind flow converges into the city, preventing or lessening horizontal outflow at the ground.

Additionally, during warm summer days, odors emanating from industrial areas and landfills can be trapped just after sunset when winds die down and near ground level inversions start to form. The decreased dispersion associated with these meteorological phenomena often results in short-term odor episodes.

6.4.2 Transport Mechanisms

Air pollutants are transported from their point of origin by the action of the wind. Different meteorological conditions are conducive to varying degrees of pollutant dispersion depending upon source configuration and type. For instance, TSP emissions from flat bare areas increase directly with wind speed (i.e., mechanical force). Ground level emissions often have their greatest impact during early evening hours when the dispersion ability of the atmosphere is decreased due to light winds and ground level inversions. Emissions from industrial boilers and processes are frequently at high temperatures which enhances plume rise. High stacks and plume rise allow the pollutant to become diluted before reaching ground level, resulting in lower concentrations at farther distances from the source than would be possible with ground level emissions. Turbulent meteorological conditions may result in lower concentrations downwind of a source, but they can also result in higher maximum concentrations near the source. Mechanical turbulence from wind passing over a building and stacks can cause a plume to be "downwashed," resulting in higher concentrations. Some pollutants may be transformed or leave the plume during transport. Particulates may fall out of a plume. Sulfur dioxide undergoes chemical reactions which may decrease the SO₂ concentrations and form small particulates in the process. Transport mechanisms are dependent upon meteorological conditions, source configuration, and pollutant mix.

6.5 Current Air Pollution Control Programs Affecting the Study Area

6.5.1 Permit Program

The Illinois Pollution Control Board's regulations for air pollution control require permits for the construction and operation of most sources of air pollution or equipment designed to control air pollution. Construction permits are to be obtained before construction is commenced on a new or modified source. Operating permits are required when the source begins operation and must be periodically renewed. Failure to hold appropriate permits is grounds for enforcement under the Illinois Environmental Protection Act.

Sources typically subject to the permit requirement include boilers at electric utilities, industrial plants, and large institutions; process equipment at petroleum refineries, steel mills and manufacturing plants which release dust or vapor to the air; grain elevators, tank farms and other material storage or handling operations; and incinerators. Air pollution control permits are not currently required for landfills, although they are required for almost all other waste treatment or disposal facilities because of the potential for discharges of vapor or fumes to the atmosphere.

As with the other permit programs, the air permit program serves several functions.

6.5.1.1 Compliance Review

The IEPA is only authorized to issue permits if the applicant provides adequate proof of compliance with substantive air pollution control requirements. Thus, the issuance of a permit implies that substantive requirements applicable to a source have been determined, and the application has shown compliance with these requirements.

6.5.1.2 Permit Conditions

The IEPA is authorized to place conditions on permits as needed to control air pollution. These conditions may simply state the requirements or limitations under which a source is to operate, to avoid future misunderstanding. These conditions may to a certain extent also require testing, recordkeeping, etc., to verify compliance or additional control measures to respond to the circumstances of the particular source.

6.5.1.3 Information Gathering

Permit applications provide a basic supply of information about sources of pollution. This goes beyond identification of the source and compliance information to include quantity, quality and location of pollutant discharges generally. Although air permit applications are most directed at air emissions and control of criteria pollutants, they sometimes provide information about industrial processes and the presence of hazardous materials.

Plants located in the study area which currently have permits from the Division of Air Pollution Control are listed in Appendix F (the TAS emissions inventory).

6.5.2 Field Operations Section Operating Program

The Field Operations Section (FOS) functions within the guidelines of an Operating Work Plan. Although structured along definite guidelines, this Work Plan contains built-in flexibility to allow prioritizing of actual day-to-day activities in response to the changing aspects of environmental problems.

6.5.2.1 Work Plan

The Work Plan is a systematic attempt to organize FOS's daily activities. Its framework is carefully reviewed, evaluated and prioritized each year in light of the IEPA's goal of protecting the air environment. The Work Plan provides for the detailed inspection of each and every major facility in nonattainment areas at least once a year on a priority basis. The frequency of inspection may be increased to further assess compliance, to monitor facilities' programs, or to review compliance with operating permit conditions. Inspections of major facilities in areas attaining the National Ambient Air Quality Standards and which have a history of good compliance may be deferred to once every 24 months, provided that no complaints are received and no observations of non-compliance are noted.

Table 6.9 is an excerpt from the Work Plan. It lists the investigative priorities in the study area for Fiscal Year 1984.

Facilities which pose a significant health threat are given the highest priority in the Work Plan.

Several major facility categories are given special emphasis in the Work Plan. From time to time, special investigative task forces are put together to deal with the complex air pollution problems of large facilities such as steel mills, chemical plants, and power plants. Additionally, special attention may be focused on particular pollutants across the board. For example, over the last several years, the Work Plan has emphasized reductions in total suspended particulate (TSP) and hydrocarbon (HC) emissions in the Chicago area. Since mid-1980 in southeast Cook County, there have been more than 1100 investigations at over 100 major TSP emitting facilities. During this time, TSP emissions in this area have been reduced approximately 40 percent. Correspondingly, throughout the Chicago area, there have also been more than 850 investigations at over 190 major HC emitting facilities designed to enhance compliance with applicable emission limitations. Overall HC emissions during this period have been reduced about 50 percent.

Table 6.9

**FY '84 Work Plan Investigative Priorities
in the Southeast Chicago Study Area**

Type	Actual No. of Facilities	Work Plan Frequency	Expected No. of Inspections for the Year
1. Task Force (Steel Mills)	4	12	48
2. Toxics/Hazard	1	4	4
3. Violators (Substantive)	5	4	20
4. NESHAPS	0	3	0
5. On Program	2	4	8
6. Multimedia Problems	7	3	21
7. NSPS	0	1	0
8. TSP Chicago		1	
9. HC Chicago	15	1	15
10. Random		1	
11. A-1 Facilities	17	1	17
12. A-2 Nonattainment	13	1	13
13. Service Station (incl. in B Facilities)		1	
14. Special Request (incl. in B Facilities)		1	
15. A-2 Attainment	0	1	0
16. B Facilities	<u>029</u>	1	<u>029</u>
TOTAL:	193		275

6.5.2.2 Incident Response

Every air pollution incident (e.g., major malfunctions of pollution control equipment, industrial spills, etc.) reported to FOS or a multimedia (more than one Agency Division) problem which may endanger the public health is investigated with the highest priority under the Work Plan.

6.5.2.3 Stack Testing

FOS routinely witnesses and evaluates stack tests. Usually, sampling is conducted by the facility to demonstrate compliance with existing rules and regulations. Tests may be requested by the Permit Section for development of operating permit conditions or, as a result of an enforcement or variance action, may be ordered by the Illinois Pollution Control Board, or may be conducted by a facility for obtaining design criteria data and for establishing operating rates for assuring compliance.

6.5.2.4 Continuous Monitoring

FOS maintains records of malfunctions of air pollution control equipment and/or processes. On an on-going basis, FOS evaluates and follows-up on reported malfunctions, issues Compliance Inquiry Letters, and assesses the need for the installation of continuous monitoring equipment. Compliance with permit conditions requiring the keeping of records regarding system malfunctions and preventive maintenance practices is routinely monitored and enforced.

6.5.2.5 Citizen Complaints

The handling of complaints is a very important aspect of FOS activities. Increasingly, many inspections which originate from a complaint are now conducted under the multimedia format where field personnel from more than one Agency Division conduct inspections together, to focus on complex problems related to more than one of the media. This is especially true in the Southeast Chicago study area where there is a concentration of landfill operations, heavy industry and hazardous waste treatment facilities.

The area covered by this study represents a little over one-half of one percent of the State's total geographic area, and less than one percent of the statewide population. About 3-1/2 work years per year of surveillance effort is allocated to the study area. This represents about 12 percent of the total for the State.

6.5.2.6. Compliance Status of Major and Significant Facilities in the Southeast Chicago Study Area

The latest air pollution emissions inventory lists about 193 facilities in the Southeast Chicago study area. Of the 193 facilities, 22 facilities are actual 100-ton per year emitters (designated A-1 Facilities under the Work Plan); 18 facilities have potential emissions after controls of less than 100 tons per year (A-2 Facilities under the Work Plan); 22 facilities are significant sources having actual and potential emissions below 100 tons per year, but falling under the categories of multimedia, toxic/hazardous, HC or fugitive dust emitters. The remaining 131 are minor facilities.

Minor Facilities

Minor facilities are given the lowest priority in the Agency's Work Plan. They are not inspected regularly, and many have been inspected for inventory purposes only. When problems are uncovered during these investigations, follow-up is handled under established Work Plan priorities. Where apparent violations are observed, an initial Compliance Inquiry Letter (CIL) is sent and usually an adequate facility response is sufficient compliance action.

Of the 131 minor facilities in the Southeast Chicago study area, 70 had been inspected as of September 1, 1983. Of the 70 investigated, 52 were determined to be in compliance, 12 were found to be in violation of substantive regulations, and 4 facilities were found to be deficient in not having IEPA permits. About 70 percent of the minor facilities uncovered with substantive problems have since corrected the violations, and the remaining 30 percent are being sent a second CIL.

Major and Significant Facilities

Even as early as September of 1983, all the major and significant facilities had been inspected at least once. Investigations of facilities with major and significant violations frequently surpass by many times the minimum frequency of inspection set out in the Work Plan.

Of the 62 major and significant facilities, 12 facilities have substantive violations, 12 facilities have permit violations only, and 38 facilities are in compliance. Seven of those facilities with substantive violations are now on approved compliance programs. The five facilities with no programs have violations that were uncovered after August of 1983. All of these, however, have responded indicating that they are formulating programs and formal submissions to the IEPA are under development. The 12 facilities with permit deficiencies are being sent follow-up Compliance Inquiry Letters.

6.6 Air Pollution Additional Studies (November 0973)

6.6.1 Introduction

An air toxic sampling program was initiated in the Lake Calumet area of Chicago in late November of 1983 for the purpose of determining the type and amount of selected toxic contaminants in the air. This program represented an innovative first effort by the State to measure air toxic contaminant levels. Severe time constraints necessitated that the program be carried out quickly and, thus, it should be noted that the study was not intended to be exhaustive. Resource limitations dictated the selection of only a few sampling days.

This sampling program consisted of two parts. The first part involved an on-site continuous sample collection and measurement program conducted by TRC Environmental Consultants, Inc. using their TAGA 6000 MS-MS mobile monitoring laboratory. The second part involved the laboratory analysis of samples collected during the summer months of 1983 at four routine sampling sites located in the Lake Calumet area and identified in Section 6.3 of this chapter. The mobile laboratory portion of the sampling program was aimed at identifying and quantifying volatile organic compounds from a list of 31 components. This list of target compounds is presented in Table 6.10. This list was compiled by the USEPA and is known as the "List of Potential Non-Criteria Air Pollutants". The samples collected during the summer of 1983 were analyzed for dioxin, arsenic, beryllium, nickel, cadmium, chromium, and polychlorinated biphenyls (as a group). The following paragraphs provide an overview of the sampling program and summarize the results.

6.6.2 Air Sampling Program

6.6.2.1 Mobile Toxic Monitoring

The Illinois EPA and Illinois Department of Energy and Natural Resources contracted with TRC Environmental Consultants, Inc. to sample for the period November 13-29, 1983 at 22 locations in the Lake Calumet area. These locations are listed in Table 6.11. The sampling strategy involved locating the mobile laboratory at one of the 22 locations and sampling for 2 to 4 hours during periods when the selected site would be downwind from a potential source of toxic contaminants. During the period the mobile laboratory was sampling, wind speed and direction measurements were also taken.

6.6.2.2 Airborne Dust Analysis

The Chicago Department of Consumer Services operates four airborne dust sampling sites near the Lake Calumet area. These sites are located at Washington High School, Old Carver High School, Addams School, and Anthony School. Nineteen samples were selected from the period February - July, 1983. These samples were analyzed for dioxin, arsenic,

Table 6.10

Air Quality Survey Target Compounds

a. acetaldehyde	q. hexachlorocyclopentadiene
b. acrolein	r. methyl chloroform
c. acrylonitrile	s. methylene chloride
d. alkyl chloride	t. nitrobenzene
e. benzyl chloride	u. nitrosomorpholine
f. carbon tetrachloride	v. perchloroethylene
g. chlorobenzene	w. phenol
h. chloroform	x. phosgene
i. chloroprene	y. propylene oxide
j. cresol (o,p,m)	z. toluene
k. p-dichlorobenzene	aa. trichloroethylene
l. dimethyl nitrosamine	bb. vinylidene chloride
m. epichlorohydrin	cc. xylenes (o,p,m)
n. ethylene dichloride	dd. benzene
o. ethylene oxide	ee. vinyl chloride
p. formaldehyde	

Table 6.11

Sites Monitored During Air Quality Survey

<u>Site Number</u>	<u>Name</u>	<u>Location</u>
1	O'Brien Lock and Dam	134th and Calumet River
2	Burnham	Croissant Road
3	Cottage Lake Grove	South Edge of Lake
4	Mann Park	130th Street/Exchange St.
5	Williams W. Powers Conservation Area	
6	G. Washington School	115th Street/Avenue L
7	Bright School	108th Street/Calhoun Street
8	Trumbull Park	103rd Street/Bensley Avenue
9	Burnham School	VanVlissinger Blvd./95th St.
10	Luella Park	100th Street/Oglesby
11	Arcade Park	111th Street/Lawrence
12	G.W. Carver School	130th Street
13	Sherwin Williams	113th Street/Corliss
14	Bright School	108th Street/Calhoun
15	Addams School	108th Street/Ewing
16	G. Washington School	115th Street/Avenue L
17	Dolton City Hall	Dolton Road
18	Dolton	Michigan Street/136th Street
19	SCA Incinerator	122nd Street
20	Anthony School	97th Street
21	Sherwin Williams	113th/Corliss Street
22	Mann Park	130th Street/Exchange Street

beryllium, nickel, polychlorinated biphenyls (as a group), cadmium, and chromium. The analyses of these 24-hour samples provide some measure of high air pollution impact at these four sites since the samples were taken when the predominant wind direction was from potential sources of toxic pollutants. That is, when the wind was blowing from the Lake Calumet or steel mill area and the TSP (total suspended particulates) readings were high.

6.6.3 Results and Conclusions

1. The mobile monitoring laboratory detected the presence of toluene, benzene, xylene, and acetone. Acetone was not one of the target compounds listed in Table 6.10 but was measured because its identity was distinguishable and daily tests with standards for acetone were successful in confirming its presence. The levels of the measured pollutants are shown in Table 6.12. The levels presented in Table 6.12 may be compared to the multimedia environmental goals (MEG) presented in Table 6.13. MEGs, as used in this report, describe levels of contaminants that are predicted by USEPA not to produce negative effects in the surrounding populations or ecosystems. MEGs are not regulations; rather, they are designed for use in ranking chemicals on the basis of predicted environmental acceptability. The average pollutant levels for the area should be compared to the MEG Ambient Level Goals while the maximum pollutant levels may be compared to the Minimum Acute Toxicity Concentrations for Air. The levels measured are all below these MEG values.

Table 6.14 compares the levels of toluene, xylene and benzene measured in the study to levels found by the USEPA in other cities and another location in Chicago. A statistical comparison of the pollutant levels found in these ten cities and southeast Chicago shows that the values measured in southeast Chicago were not significantly greater (p less than 0.05) than the levels found in the ten cities.

2. The results of the airborne dust chemical analysis showed that no detectable limits of polychlorinated biphenyls or dioxin were present. Levels of arsenic, beryllium, cadmium, chromium and nickel were all found above the minimum detectable level of the analytical technique. Although the concentrations of these contaminants varied considerably from sample to sample, none of the values were extremely high. The results of the filter analyses are shown in Table 6.15. This table also compares the ambient levels found for arsenic, beryllium, cadmium, chromium and nickel to both TLV/300 and TLV/420. The threshold limit value (TLV) are occupational exposure standards established by the American Conference of Governmental Industrial Hygienists for pollutants which have not had a NAAQS promulgated. They are designed to protect the worker from adverse health effects for an 8-hour workday and 40-hour workweek. The TLV/300 represents the level that has been used by some local, state, and federal agencies as a guideline for safe ambient levels in lieu of National Ambient Air Quality Standards. TLV/420 may be viewed as equivalent to a MEG. All levels measured were below both TLV/300 and TLV/420.
3. The nature of the emissions sources in the Lake Calumet area of Chicago is such that, even though this air monitoring study did not find harmful levels of air contaminants, it cannot be assumed that harmful levels never exist. To obtain a more substantial understanding of the air quality in this area, it will be necessary to locate longer-term sampling stations (such as those operated for airborne dust) to provide a larger data base from which more definite conclusions on the quality of the air can be derived.

Table 6.12

Quantitative Results for Air Quality Survey by Site

<u>Site</u>	<u>Date</u>	<u>Toluene (ppb)</u>	<u>Benzene (ppb)</u>	<u>Xylene (ppb)</u>	<u>Acetone (ppb)</u>	<u>Other (ppb)</u>
1	Nov. 14	11.7	ND	ND	81.0	-
2	Nov. 15	8.1	8.9	7.8	459.7	-
3A	Nov. 15	-	-	-	-	-
4	Nov. 16	6.8	4.1	4.6	313.3	-
5	Nov. 16	2.8	3.7	ND	673.3	-
6	Nov. 16	3.1	3.0	ND	498.3	-
7	Nov. 17	5.9	9.4	6.4	237.0	-
8	Nov. 17	2.6	6.1	ND	180.8	-
9	Nov. 17	ND	ND	ND	268.8	-
10	Nov. 17	5.6	9.8	ND	217.5	-
11	Nov. 18	16.7	ND	ND	158.8	-
12	Nov. 18	5.2	ND	ND	215.0	-
13	Nov. 18	7.8	5.9	ND	182.3	-
14	Nov. 19	6.1	ND	ND	302.6	-
15	Nov. 21	ND	ND	ND	245.0	-
16B	Nov. 21	21.7	ND	ND	236.6	-
		368.0	ND	ND	1543.5	-
17	Nov. 22	21.4	15.5	ND	305.0	-
18	Nov. 22	11.7	17.0	ND	193.0	-
19	Nov. 28	3.1	4.2	ND	222.0	-
20	Nov. 28	4.2	6.2	ND	485.8	-
21	Nov. 29	6.4	6.9	ND	123.5	-
22	Nov. 29	4.4	6.2	ND	98.4	-

A Monitoring stopped due to strong wind and rain.

B The arrival of a large number of automobiles with their engines running during the second half-hour of monitoring contributed to the significant increase in concentrations. For this reason, the two sets of values were not averaged.

Table 6.13

MEG Values for Air Quality Survey of Non-Criteria Pollutants
(ppb)

<u>Pollutant</u>	<u>Toluene</u>	<u>Benzene</u>	<u>Xylene</u>	<u>Acetone</u>
Natural background level (ppb)	2.6	0.02	1.2	0.01
Average pollutant concentration found in study area	7.4 A	5.1 A	0.9 A	271.3 A
Ambient level goal based on health effect - toxicity based estimated permissible concentration	240	24	240	600
Ambient level goal based on ecological effect - toxicity based estimated permissible concentration	120	25	-	-
Maximum pollutant concentration found in study area	21.7 (368.0)A	17.0	7.8	673.3 (1543.5)A
Minimum acute toxicity concentration for ambient air based upon health effects	100,000	925	100,000	250,000

AThe arrival of a large number of automobiles with their engines running during the second half hour of sampling at Washington H.S. on November 21, 1983 contributed to a significant increase in concentrations. For this reason, the values were separated into two data sets and were not used in computing averages.

Table 6.14

Weighted Average Concentrations in Different Cities

	<u>Toluene</u>	<u>Xylene</u>	<u>Benzene</u>
	S.E. Chicago/Lake Calumet		
Mean	5.1	0.9	5.1
Max.	21.7	7.8	17.0
Min.	ND	ND	ND
	Los Angeles		
Mean	11.7	6.5	6.0
Max.	53.4	62.7	27.9
Min.	1.1	0.6	0.7
	Phoenix		
Mean	8.6	6.0	4.7
Max.	38.7	36.2	59.9
Min.	0.5	0.3	0.4
	Oakland		
Mean	3.1	2.3	1.6
Max.	16.9	12.3	4.6
Min.	0.2	0.2	<0.1
	Houston		
Mean	10.3	5.1	5.8
Max.	65.7	33.6	37.7
Min.	1.0	0.4	0.8
	St. Louis		
Mean	1.5	0.5	1.4
Max.	6.4	2.7	5.8
Min.	0.1	0.1	0.1
	Denver		
Mean	6.2	4.1	4.4
Max.	24.6	26.8	23.9
Min.	0.3	0.2	0.1
	Riverside		
Mean	5.8	3.3	4.0
Max.	20.1	10.5	11.0
Min.	0.4	0.3	0.5
	Staten Island		
Mean	9.0	5.4	4.2
Max.	67.3	70.8	19.0
Min.	0.6	0.2	<0.1
	Pittsburgh		
Mean	3.9	2.1	5.0
Max.	46.3	14.6	64.6
Min.	0.4	0.2	0.4
	Chicago -- 79th and Lawrence		
Mean	4.6	2.3	2.6
Max.	14.8	9.9	8.8
Min.	0.8	0.2	0.6

CITATION:

Singh, H.B., et al. (January, 1983): Measurements of Hazardous Chemicals in the Ambient Atmosphere. SRI International EPA-600/3-83-002.

Table 6.15

Results for Air Quality Filter Analysis

Sample		Concentrations							
Location	Date	TSP ug/SCM ¹	As ng/SCM ²	Be ng/SCM	Cd ng/SCM	Cr ng/SCM	Ni ng/SCM	PCBs ng/SCM	Dioxin ng/SCM
Addams School	3/18/83	265	10.1	0.3	12.8	26.1	50.8	<1.5	<30.5
	5/24/83	121	2.8	<0.1	2.5	11.8	9.0	<1.5	<30.5
	7/11/83	167	3.2	<0.1	2.0	17.0	14.7	<1.5	<30.5
	7/17/83	120	3.6	<0.1	1.7	11.3	12.3	<1.5	<30.5
	7/29/83	120	3.9	<0.1	2.3	15.4	13.7	<1.5	<30.5
Anthony School	3/1/83	190	6.7	<0.1	6.2	23.2	30.5	<1.5	<30.5
	6/11/83	117	3.0	<0.1	1.0	7.6	4.0	<1.5	<30.5
	7/11/83	119	1.2	<0.1	1.1	6.5	5.1	<1.5	<30.5
	7/29/83	125	2.5	<0.1	2.8	18.0	10.3	<1.5	<30.5
Carver High School	2/23/83	173	5.5	0.3	2.9	26.2	17.3	<1.5	<30.5
	5/12/83	111	3.0	<0.1	1.4	11.3	7.9	<1.5	<30.5
	6/11/83	115	1.2	<0.1	0.9	11.3	2.6	<1.5	<30.5
	6/17/83	146	2.2	<0.1	1.4	11.9	9.0	<1.5	<30.5
	6/23/83	158	2.7	<0.1	2.5	15.6	8.9	<1.5	<30.5
Washington High School	3/1/83	317	12.0	0.2	6.6	41.4	58.0	<1.5	<30.5
	5/24/83	150	11.9	<0.1	2.3	38.0	30.9	<1.5	<30.5
	7/11/83	190	8.3	<0.1	1.3	41.5	27.2	<1.5	<30.5
	7/17/83	185	8.3	<0.1	1.0	22.9	47.0	<1.5	<30.5
	7/29/83	143	5.0	<0.1	1.4	32.9	22.7	<1.5	<30.5
Blank A		-	<0.9	<0.1	<0.1	<1.5	<1.8	<1.5	<30.5
Blank B		-	<0.9	<0.1	<0.1	<1.5	<1.8	<1.5	<30.5
Blank C		-	-	-	-	-	-	<1.5	<30.5
Average concentration			5.1	0.1	2.8	20.5	20.1		
TLV/300 (ng/m ³)			666	7	167	167	3,333		
TLV/420 (ng/m ³)			475	5	119	119	2,380		

¹ ug/SCM = micrograms per cubic meter² ng/SCM = nanograms per cubic meter

6.7 Supplemental Air Pollution Studies

6.7.1 Introduction

The draft Southeast Chicago study had several suggested follow-up activities for the Division of Air Pollution Control (DAPC) to consider. This section outlines the results of those activities to date (12-85). The follow-up studies that have been done are: (1) a nitrosamine sampling study; (2) PCB sampling in the study area; (3) emission inventory of both criteria and toxic air pollutants/PIPQUIC computer studies; and (4) an odor study of the area.

6.7.2 Nitrosamine Air Sampling

Because the air toxics monitoring performed in November of 1983 gave some indication that there were nitrogen bearing compounds (nitrosamines) possibly emitted near the large landfill sites in the study area, the DAPC subsequently monitored specifically for nitrosamines. This monitoring was done at the Thomas O'Brian Lock which is located to the East and between CID landfills 1 and 2. Monitoring was performed on six occasions: November 27-29, 1984; January 3-4, 1985; January 30-31, 1985; February 28-March 1, 1985; April 3-4, 1985; and April 18-19, 1985.

Sampling was done using a state-of-the-art proprietary sampling cartridge manufactured by the Thermo Electron Corporation. No sample showed any evidence of nitrosamine being present in the atmosphere.

6.7.3 Polychlorinated Biphenyls Air Sampling

The Division of Air Pollution Control initiated an air sampling program for polychlorinated biphenyls (PCBs) in the fall of 1984. Samples were taken at Grissom and Bright Schools using polyurethane foam sample trains. Samples were then taken to an off-site laboratory to be analyzed.

The air samples were collected on occasions when the SCA incinerator was burning wastes containing PCBs. Wind conditions and weather patterns varied each time a sample was taken. Although PCBs were found in 9 of 10 samples collected between November of 1984 and May of 1985, the exact amount of PCBs present could not be reliably determined.

The reason that precise amounts of PCBs present could not be determined was due to a defect in the analysis procedure which was found through detailed quality control checks which are not routinely used in measuring levels of PCBs in the air.

New procedures were developed and a special method validation program was conducted by the Radian Corporation of Austin, Texas which performed the original analysis under contract to IEPA. Test data collected in this validation program provided evidence that the new procedures will provide acceptable results.

The difficulties with the previous analysis for PCBs involved the extraction and concentration steps where a relatively large volume (16 ounces) of liquid containing the sample is reduced to seven one-thousandths of an ounce (4 drops) to provide for the detection of PCBs at extremely low levels. The steps used to concentrate the sample have been found to result in the loss of some of the PCBs. The new procedure limits this loss while specially formulated chemicals, added to the samples at the beginning of the procedure, are monitored in order to provide a reliable measure of the actual extraction and collection efficiency.

The first phase of the PCB air sampling program began in the fall of 1984 and was suspended upon discovery of the deficiency in the analysis procedure. At that time, 11 of the scheduled 16 samples had been collected from two locations in southeast Chicago.

The IEPA resumed the sampling program in mid-October of 1985 using the improved analysis procedures. A third sampling site is being implemented at Carver High School in the Altgeld Gardens area of southeast Chicago. The previous two PCB sampling locations, Bright Elementary School and Grissom Elementary School, will continue to be used in the next round of sampling.

6.7.4 Emissions Inventory of Toxic Air Pollutants

The Illinois Environmental Protection Agency and USEPA, in cooperation, are jointly developing an emissions inventory for the Southeast Chicago study area. When completed, this inventory will serve as the basis for assessing the viability of various emission control strategies.

In addition to the emissions inventory development, the IEPA is working with USEPA staff members involved with GEMS and PIPQUIC to develop the capability to factor risk management into environmental decisions concerning the Southeast Chicago study area. GEMS is a computerized system of models which can be used to determine environmental impacts (both media specific and multimedia). PIPQUIC is a multimedia relational data base for both pollutants and population. It contains assessment ranking packages and the capability to perform "what if" types of analyses.

6.7.5 Odor Study

The draft study of this area suggested that the IEPA undertake an analysis of the odor problems of the Southeast Chicago study area. At the time the draft study was written, the IEPA was not prepared to undertake such an analysis. Subsequent to the distribution of the draft document, the DAPC elected to undertake a study of the odor problems in the area. One basis for this decision was the large number of complaints received by the DAPC's field staff. The odor study program was begun in the summer of 1985.

6.7.5.1 Elements of the Southeast Chicago Odor Study

The study, which is designed to provide additional insight into the odor problems in the Southeast Chicago study area, is composed of three elements: (1) use of an odor log; (2) precise measurements of on-site meteorological data; and (3) correlation of the odor logs with the meteorological data.

6.7.5.1.1 Odor Log

Members of the general public in the study area have been provided with odor logs to use when reporting the occurrence of an odor episode. Each log sheet consists of an original and two carbon copies. One of the copies is retained as a record by the individual making the report. The other two copies are provided to the IEPA. The log includes the time and location of occurrence and describes the type of odor encountered.

6.7.5.1.2 Meteorological Data

The IEPA has installed an instrumented meteorological tower at Bright School within the study area. This tower measures both wind speed and direction that is specific to the study area. Alternate meteorological data is also available from the National Weather Service Station at O'Hare Airport and from other IEPA meteorological sites in and around Chicago.

6.7.5.1.3 Correlation of Data

Using both the odor logs and the wind data, odor pollution logs will be generated. Wind roses will be developed that describe the compass directions from which each odor is thought to have come. Once the source of odor has been identified and verified, the IEPA can pursue a program of mitigation.

7.0 Cancer Mortality in Selected Community Areas of Southeast Chicago, 1968-1982

A Detailed Analysis and Review of a Previous Study

In response to a request from the IEPA, the Illinois Department of Public Health (IDPH) conducted a review of selected mortality statistics from the southeast Chicago area.

7.1 Introduction

During the summer of 1984, a preliminary report by the Department of Public Health on cancer mortality was released as part of the IEPA's draft report on southeast Chicago (1). The study reported an excess rate of cancer for selected community areas of Chicago when compared with the rates for the entire city. The study area consisted of six community areas of Chicago: Pullman, South Deering, East Side, West Pullman, Riverdale and Hegewisch.

To follow up the preliminary report, the Division of Disease Control and the new Division of Epidemiologic Studies of the Illinois Department of Public Health performed a further detailed review of cancer mortality in the study area. The review involved four separate studies. The University of Illinois School of Public Health and the Illinois Cancer Council were involved in one of the subsequent studies.

First, a reanalysis of cancer mortality was performed which used methods similar to the preliminary study. Second, a time trend analysis of cancer mortality rates assisted in the interpretation of cancer rates within the six community areas of southeast Chicago. Third, a detailed analysis of cancer mortality by specific cancer types was done for each age, race and sex group of the community areas within the study area. The University of Illinois School of Public Health and the Illinois Cancer Council assisted the Illinois Department of Public Health in the third study. Lastly, a separate study of cancer mortality was performed for one census tract of South Deering on the northeast side of Lake Calumet; the analysis was requested by Mr. Edward Vrdolyak and Mr. Ed Hernandez.

Unlike the first preliminary study, these additional analyses have corrected for the major influences of age, race and sex on the occurrence of cancer in southeast Chicago. Not correcting for these influences will result in incorrect estimates of cancer rates. These additional studies have also taken a closer look at specific types of cancer. The previous analysis used a manual process to perform over 1,000 calculations; the additional analyses have used over 24,000 calculations using computer programs.

7.2 Methods

The cancer trend analysis derived age-adjusted mortality rates for each race, sex and community area for the time periods 1968-72, 1973-77 and

1978-82. The Chicago population was used as the standard. The following major cancer sites were used in the trend analysis: lung, colon, stomach, pancreas, bladder, leukemias and all cancers. The analysis was very limited due to the small number of cancers observed for each five year period. The average community area had fewer than 10 deaths from certain cancers (stomach, pancreas, bladder or leukemias) for each five year period. To stabilize the large variability in age-adjusted cancer mortality rates, all community areas were combined and then compared to the overall rates for the city of Chicago.

The reanalysis and detailed studies compared the observed and expected number of cancer deaths in each community. The expected number of cancer deaths was obtained by applying age, race and sex-specific cancer mortality rates for Chicago to the number of persons of similar age, race and sex within each community area, respectively. Expected numbers of deaths were calculated for each five year period for 1968-72, 1973-77 and 1978-82. Total expected cancer deaths were summed across age groups for each time period and across the 15 year period. The cancers included in these studies were: esophagus, stomach, large intestine, rectum, liver, pancreas, lung, connective tissue, breast, prostate, bladder, brain, non-Hodgkin's lymphoma, multiple myeloma, leukemias, other sites, oral cavity and pharynx sites, all digestive sites, all respiratory sites, all genitourinary sites, and all lymphatic and hematopoietic tissue sites.

The differences between the observed number of deaths and the expected numbers were tested using standard statistical techniques. When the expected number of deaths was fewer than five, a poisson distribution was used to determine the significance level (2). When the expected number of deaths was five or more, the Chi Square test with one degree of freedom was used (3). To limit the number of false positive findings from multiple comparisons, a higher significance cutoff level (p less than 0.01) was used. The reported findings from the detailed study also required significant differences in two five-year time periods or in one time period and the total 15 year period.

7.3 Results

The findings from the four additional studies are presented as separate sections. A summary is provided at the end of this report which draws on the findings of the four separate studies.

The demographics of the six community areas are different; these differences greatly influence the cancer mortality rates in each area. Table 7.1 shows the differences by race, age and population sizes. The community areas with larger populations will generally experience a higher number of cancer deaths than smaller populations. The community areas with higher proportions of elderly people or with larger black populations may also experience more cancer deaths. Pullman, West Pullman and South Deering have experienced a reduction in their white populations between 1970 and 1980. East Side and Hegewisch have fairly stable, elderly white populations. Table 7.2 shows the number of total cancer deaths for each time period for each community area in southeast Chicago. A total of 2,976 cancer deaths occurred over a 15 year period in residents of the six community areas under study.

Table 7.1

**Demographic Characteristics of
Selected Community Areas of Chicago**

<u>Community Area</u> <u>No. Name</u>	<u>Percent White</u>		<u>Percent Over 45 Yrs.</u>		<u>Population Size</u>	
	<u>0970</u>	<u>0980</u>	<u>0970</u>	<u>0980</u>	<u>0970</u>	<u>0980</u>
50 Pullman	51	19	28	27	10,893	10,341
51 S. Deering	83	31	29	24	19,271	19,400
52 East Side	99	94	36	40	24,649	21,331
53 W. Pullman	83	6	34	27	40,318	44,904
54 Riverdale	5	3	12	13	15,018	13,539
55 Hegewisch	99	97	38	38	11,346	11,572

Table 7.2

**Number of Cancer Deaths by Selected
Community Areas of Chicago, 1968-1982**

<u>Community Area</u> <u>No. Name</u>	<u>Cancer Deaths by Period</u>			<u>Total</u>
	<u>1968-72</u>	<u>1973-77</u>	<u>1978-82</u>	
50 Pullman	105	74	94	273
51 S. Deering	171	126	159	456
52 East Side	245	260	278	783
53 W. Pullman	384	305	264	953
54 Riverdale	47	55	54	156
55 Hegewisch	99	126	130	355
Total	1,051	946	979	2,976

Source: Illinois Department of Public Health

7.3.1 Reanalysis of the Preliminary Study

Several problems were found in the preliminary study. There had been little time to complete the study, which forced the analysis to be limited in scope. Errors in the calculations of age-standardized rates were noted; the rates were not adjusted for sex or race. The analysis of "urinary organs" also included reproductive and genital sites of cancer; the other broad site groupings included many types of cancer for which there are no known "associations with environmental factors". Presenting the findings as age-adjusted rates was somewhat artifactual. These rates did not truly represent the real cancer rate but were used for comparison purposes only.

To overcome these problems, the reanalysis took a different approach. The analysis presents the actual number of cancer deaths that occurred for each community area. The observed number of deaths are then compared to the number of expected cancer deaths which are derived from age, race and sex-specific cancer mortality rates for the city of Chicago. Thus, the comparison is to the number of expected cancer deaths if the community area had experienced the same rate of cancer deaths as Chicago.

Table 7.3 presents the findings of the reanalysis and contrasts these results to the preliminary study. The previously reported excess of cancer mortality rates for community area 53 -- West Pullman -- was no longer present. There was a large influx of non-whites (see Table 7.1) which explains the excess when racial differences of cancer rates are not taken into account. The previously reported excess of all cancer deaths for community area 54 -- Riverdale -- was no longer present, again from higher rates of cancer death in non-white populations (see Table 7.1). However, the reanalysis did find a significant excess of respiratory cancer deaths across all six community areas, an excess of genitourinary cancers in community area 55 (predominantly prostate cancers in men and bladder cancers in women), and an excess of all cancers deaths in community area 55 -- Hegewisch. These findings are further supported by the more detailed analyses in this report.

7.3.2 Trends in Cancer Mortality

Because of the instability of mortality rates with small numbers of deaths for each five year period, the analysis of cancer trends used all community areas combined (A) and compared them to Chicago (C). Figure 7.1 shows the trend in cancer mortality rates to be similar in both sexes, but males generally had higher rates than females. Figures 7.2 and 7.3 show that non-whites had higher cancer mortality rates than whites for both sexes. There were no significant differences between the study area and Chicago age-adjusted cancer mortality rates. Figure 7.4 shows the trends of lung cancer deaths, colon cancer deaths and other cancer deaths (stomach, pancreas, bladder and leukemia) for the study area. The trends were very similar to Chicago trends. These trends were not very different from national trends in cancer mortality. Figure 7.5 shows the variability in cancer mortality rates for each of the six community areas. The City of Chicago rates would be plotted right through the middle of the community area rates. The small chart on rank orders of community areas for each time period also showed the wide variability in rates with no consistent or significant trends.

Table 7.3

Comparison of Preliminary Report and Reanalysis

<u>Cancer Site</u>	<u>Community Area</u>	<u>Rate¹</u>	<u>Cancer Deaths²</u>	
			<u>Observed</u>	<u>Expected</u>
Digestive Organs	50	55.49	77	85.5
	51	53.20	124	133.5
	52	44.38	220	223.4
	53	83.11*	270	286.7
	54	47.48	41	45.0
	55	55.56	114	92.9
	50-55	-	846	867.0
Respiratory Organs	50	55.35	79	68.4
	51	53.17	126	108.9
	52	43.03	185	177.4
	53	72.36	254	233.3
	54	40.74	32	35.9
	55	37.39	84	78.2
	50-55	-	760*	702.1
Genital & Urinary Organs	50	29.47	45	44.5
	51	30.61	63	69.2
	52	28.66	132	113.4
	53	46.80*	144	147.4
	54	49.53	32	26.6
	55	32.08	67*	47.2
	50-55	-	483	448.3
All Cancers	50	151.0	273	279.1
	51	186.67	456	449.3
	52	173.09	780	740.5
	53	289.84*	953	953.1
	54	222.83*	146	155.8
	55	174.10	355*	316.5
	50-55	-	2963	2894.3


*Significant differences (p less than 0.05)

¹Preliminary report for the period 1969-1981 used age-adjusted cancer mortality rates and the Chicago 1970 population was the standard.

²The reanalysis used the actual number of cancer deaths. The expected number of cancer deaths was derived from using Chicago age, race and sex-specific rates applied to the Community Area population for time periods 1968-72, 1973-77 and 1978-82.

Source: Illinois Department of Public Health


FIGURE 7.1
TRENDS IN AGE-ADJUSTED CANCER MORTALITY RATES
BY SEX, STUDY AREA AND CHICAGO
1968-82



A = Study Area
C = Chicago

Source: Illinois Department of Public Health

FIGURE 7.2
TRENDS IN CANCER MORTALITY RATES* FOR MALES
BY RACE, STUDY AREA AND CHICAGO
1968-82




A = Study Area
C = Chicago

*Age Adjusted to Chicago 1970 Population

Source: Illinois Department of Public Health

FIGURE 7.3
TRENDS IN CANCER MORTALITY RATES* FOR FEMALES
BY RACE, STUDY AREA AND CHICAGO
1968-82




A = Study Area
C = Chicago

*Age Adjusted to Chicago 1970 Population

Source: Illinois Department of Public Health

FIGURE 7.4
TRENDS IN CANCER MORTALITY RATES* BY
SITE, STUDY AREA AND CHICAGO
1968-82




'Other' represents Stomach, Pancreas, Bladder and Leukemia

A = Study Area
C = Chicago

*Age Adjusted to Chicago 1970 Population

Source: Illinois Department of Public Health

FIGURE 7.5
TRENDS IN CANCER MORTALITY RATES*
BY CHICAGO COMMUNITY AREAS (50-55)
1968-82



Rank Order of Rates by Community Area for Each Time Period

Rank Order by Period			
Area	1968-72	1973-77	1978-82
50	2	6	4
51	3	5	3
52	5	4	5
53	4	3	1
54	6	2	2
55	1	1	6

*Age Adjusted to Chicago 1970 Population

Source: Illinois Department of Public Health

7.3.3 Detailed Analysis of Cancer Mortality

A detailed analysis was performed on the six community areas using seven age groups, race, sex, three time periods and 23 cancer sites or groupings. The level of significance had to be high (p less than 0.01) in order to reduce the chance of false positive findings. In addition, a significant finding had to be consistent over at least two time periods (five year periods or the 15 year period). Over 500 statistical tests were performed in the computer analysis.

Table 7.4 shows the community areas where significant excesses of cancer mortality occurred. Lung cancer mortality was significantly high for white males in the five combined community areas (50-53, 55) which had sizable white populations. The remaining community area (54) was principally a non-white population that had cancer mortality rates similar to non-white rates for Chicago. Bladder cancer mortality was significantly high for white females in the same combined five community areas. Prostate cancer deaths were significantly elevated for white males in community area 55 -- Hegewisch. There were no other community areas in which significant and consistent excesses in cancer deaths were identified from the detailed analysis.

7.3.4 Analysis of Cancer Mortality for One Census Tract

To evaluate a potential cluster of cancer deaths, census tract 5105 in South Deering was studied. A residential area of concern was located between 103rd and 109th Streets which lies within the boundaries of the census tract. The census tract boundaries are the C&NW Railway, 103rd Street, South Torrence, 104th Street, South Muskegon, 106th Street and South Torrence back to the railway tracks. An analysis of an area smaller than a census tract was not possible since the population census file and death certificates have data coded only to the census tract level. The years 1968 to 1982 were used for the analysis.

Table 7.5 shows the number of cancer deaths which occurred in residents of this census tract area. There were 64 male and 43 female cancer deaths over the 15 year period; three males and one female were non-white. Table 7.6 shows the number of observed and expected cancer deaths. There were no significant excesses of cancer deaths in males or females. The finding of six excess lung cancer deaths was in the same direction as the excess found in all five community areas combined.

7.4 Summary of Four Additional Studies

1. The combined findings of these four different analyses support the existence of excess cancer mortality in the study area of Southeast Chicago.

2. Lung cancer deaths were significantly greater for white males in the study area than would be expected for men of similar age in Chicago. Figure 7.4 showed a consistently higher lung cancer mortality rate for the study area when it was plotted against all of Chicago. This excess may be related to occupational exposures in the distant past or to a higher proportion of cigarette smoking history in this male population.
3. Bladder cancer deaths were found to be in excess for white females. This excess may be related to previous occupational exposures or some other factors as yet unknown.
4. An excess of prostate cancers was found in elderly white males in Hegewisch. There are no known environmental associations with this form of cancer, although some occupational associations have been reported in the medical literature.

These findings generally support an excess of lung cancer deaths in white males and bladder cancer deaths in white females. From other published research studies, these two types of cancer have been associated with environmental exposures to carcinogenic substances, primarily smoking tobacco and chemicals in the workplace. If another common environmental exposure (such as air or water) was associated with these excess cancers, we would have expected to find an excess in both males and females and in both whites and non-whites. The fact that the excess in lung cancer mortality occurred only in white males suggests that some factor unique to this subgroup, such as smoking tobacco or previous occupational exposures, might account for the excess. Similar risks might also explain the excess bladder cancer found in white females. However, since no excess lung cancer risk was found for white females, it is not likely that this group smoked more cigarettes on the average than other white females in Chicago. Some other factor, such as occupational exposures, may be more likely to account for the excess bladder cancer risk in white females.

There are several limitations to these studies. Each of the studies analyzed mortality data. There are many cancer patients who do not die from their disease and would not be included in these types of analyses. Cancer patients who die outside the study area after moving away are not included in the study. Since the length of residence is also unknown for those persons who died from cancer, they may have moved there recently or lived there all their lives. Cancer is a disease which takes many years to develop, usually 15 to 30 years. There are many potential risk factors which cannot be considered when studies use death certificates. A statewide cancer registry would offer better information to assess cancer risks. However, the registry is under development and may take several years before more precise studies can use newly diagnosed cancers.

Table 7.4

Community Areas of Southeast Chicago with
Statistically Significant Excesses of Cancer Mortality, 1968-1982

<u>Cancer Site</u>	<u>Area</u>	<u>Race/ Sex</u>	<u>Cancer Deaths</u>	
			<u>Observed</u>	<u>Expected</u>
Lung	50-53, 55	WM	440*	370.5
Prostate	55	WM	25*	12.6
Bladder	50-53, 55	WF	25*	13.8

*Significant differences (p less than 0.01)

Source: Illinois Department of Public Health

Table 7.5

Cancer Deaths in Census Tract 5105
of South Deering, Chicago, 1968-1982

Cancer Site	Male	Total	Female
Stomach	4		1
Large Intestine	4		5
Rectum	0		1
Liver	2		1
Pancreas	2		0
Lung	26		6
Breast	0		12
Prostate	4		0
Bladder	1		2
Leukemia	2		0
All Other	18		14
All Sites	64		43

Table 7.6

Observed and Expected Cancer Deaths in Census Tract 5105
South Deering, Chicago, 1968-1982

<u>Sex</u>	<u>Cancer Site</u>	<u>Observed</u>	<u>Expected</u>
Male	Lung	26	19.9
Male	All Sites	64	61.1
Female	All Sites	43	55.3

Source: Illinois Department of Public Health

7.5 Recommendations

Based on these findings, we cannot conclude that the excess cancers were due to environmental exposures in the air or water. However, more definitive studies are required before we can assess the nature of the relationship between cancer mortality in these community areas and occupational or environmental exposures. Such studies would require that we examine all cases of lung and bladder cancer in these communities, not just among those who died of these types of cancer. Detailed studies on newly diagnosed cancers would be expensive to conduct without data provided by the cancer registry. There are additional types of studies which will improve our understanding of the observed cancer excesses.

Several recommendations can be made:

1. Cancer mortality of all community areas of Chicago needs to be assessed. The University of Illinois School of Public Health is under contract for this study. The study has been completed and is now undergoing review by the Department of Public Health, prior to publication.
2. Further investigation of cancer and other causes of death within census tracts of the study area should be performed. The USEPA will be conducting such an analysis using selected cancer sites and non-cancer deaths such as acute respiratory infections, chronic renal disease and hypertensive renal disease.
3. The relationships of specific pollutants and health outcomes need to be assessed. The USEPA will create an inventory of air pollutants within the study area and from major sources outside the area. A number of potentially carcinogenic chemicals will be included in the detailed inventory. The analysis and correlation of air pollutants and health outcomes (No. 2 above) by census tract areas will be performed at a later date.
4. The occupational associations with the excess lung and bladder cancer deaths need to be evaluated. The Illinois Department of Public Health will assess the occupational information on the death certificates for these cancer sites and determine if there is any association with a particular occupation. The study has been completed and is now undergoing review by the Department of Public Health, prior to publication.
5. There should be another meeting of environmental officials, health department officials and public representatives after the conclusion of the above studies. The findings should then be presented to the community in a public meeting.

Citations

1. Illinois EPA, "Southeast Chicago, Draft Report", 1984.
2. Bailar, J.C. and Ederer, "Significance Factors for the Ratio of a Poisson Variable to its Expectation", Biometrics 20:639, 1964.
3. Colton, T., "Statistics in Medicine", Little Brown & Co., Boston, 1974.

8.0 References

Chapter 3

A. Documents

"Appendix D, Historical Dates" in the Facilities Plan of the Metropolitan Sanitary District of Greater Chicago, pages 119-139, May 1983.

Brosch, Robert Bulanda, and Kijewski. The Historical Development of Three Chicago Millgates: South Chicago, East Side, and South Deering, 1972.

Calumet Region Historical Guide. Board of Education, Chamber of Commerce, Gary, Indiana; Garman Printing Co., 1939.

Calumet Waterway Victory Celebration, various authors. Publishers, Calumet Federation for Promotion of Calumet Waterways. September 8, 1935, p. 17, 19, 24-25, 31.

Chicago Association of Commerce and Industry. The Chicago Story. CACI, Publishers. Chicago, Illinois, 1954.

Drury, John. Articles from "Old Chicago Neighborhoods" series in Landlords' Guide. "South Chicago", August 1947, p. 14; "East Side", p. 14, June 1950; "Roseland", p. 10-11, August 1949.

Duffy, Michael K. "Construction of 1969-71 Lifetables for the Chicago Standards Metropolitan Statistical Area", University of Chicago, Center for Urban Studies, February, 1975.

Ginsberg, Robert. "The Dirt Comes Out From Under The Carpet", CBE Environmental Review, March/April 1983, page 3.

Grimes, Ann. "The Autobiography of South Chicago" in Chicago magazine. March 1983, p. 160-164.

Illinois Department of Public Health, Health Statistics Bulletin, Bureau of Statistics Special Release No. 21. "The Aging of Illinois Populations," John H. Vineyard, Jr., August 1, 1955.

Illinois Department of Public Health, Annual Reports 1944-1958 and 1961-62 and 1964-65.

Illinois Department of Public Health, Springfield, Illinois Communicable Disease Records 1917-1982.

Illinois Department of Public Health, "Lifetables, Chicago, 1979-81," Nelson, Merwyn.

Illinois Department of Public Health, The Rise and Fall of Disease in Illinois, Vol. I & II, 1927, Rawlings, Issac D., M.S.M.D., et al.

Illinois Department of Public Health, State Center for Health Statistics, Chicago City 1974-76, Reported March, 1978.

Illinois Department of Public Health, Vital Statistics, Illinois, 1976-1980 Annual Reports.

Iron and Steel Industry of the Calumet Area. University of Illinois Studies in Social Sciences; John B. Appleton, Ph.D., University of Illinois, Urbana, 1927.

Piehl, Frank J. "Chicago Early Fight to Save Our Lake" in Chicago History, Vol. V, No. 4, Winter 1976-1977, p. 223-232.

Pointer, Norbert J. II. AIP, Urban and Regional Planner, DeLeuw, Cather, and Company, Chicago, Illinois. "Preservation Efforts In Historic Pullman." Submitted for presentation at conference, 1972.

Pointer, Norbert J. II. "Pullman - A New Town Takes Shape On The Illinois Prairie" in Historic Presentation, National Trust For Historic Preservation.

Ulreich, Michael. "River Trip Traces Area's Waterways" article in Clear Ridge Reporter. June 13, 1982.

U.S. Department of Health, Education and Welfare, "Illinois State Life Tables" Volume 2, No. 14 Data From National Center for Health Statistics, 1959-61 and 1969-71.

B. IEPA Files

<u>File Number</u>	<u>Name</u>
03160043	Envirotherm/Hyon, Inc.
03160031	Earth II/Alburn
03160034	Land and Lakes
03160002	Paxton I
03160033	Paxton II
03160011	MSD-103rd and Doty Avenues
03160003	Chirillo
03160030	Southeast Land Development Company

C. Interviews

Albert, Frank. Chicago Regional Port District, September 30, 1983.

Beck, Judy. League of Women Voters, (October 1983).

Borek, Paul. Department of Planning, City of Chicago, July 28, 1983.

Brace, Kenneth. Executive Director, Calumet Area Industrial Commission, October 3, 1983.

Forkel, Ed. Chicago Regional Port District, September 30, 1983.

Forshaw, Tee. Waste Management, Inc., October 3, 1983.

Gallay, Don. Department of Consumer Services, City of Chicago, July 22, 1983.

Ginsberg, Robert. Director of Research, Citizens For A Better Environment. August 31, September 15, 19 and 28, 1983.

Grigalauski, Charles. Waste Management, Inc., October 4 and 26, 1983.

Hankett, Dick. Department of Public Works, City of Chicago (October 1983).

Injerd, Dan. Division of Water Resources, Illinois Department of Transportation, October 11, 1983.

Johnson, Jim. Division of Water Resources, Illinois Department of Transportation, November 2, 1983.

Johnson, Mary Beth, Researcher. Department of Streets and Sanitation, City of Chicago (October 1983).

Krikow, Fred, Director of Environmental Affairs. Interlake Steel, Inc., September 26, 1983.

Koncza, Lou, Chief Engineer. Department of Public Works, City of Chicago, October 11, 1983.

Lindenbush, John, Archivist. Hotel Florence, Pullman Civic Organization, September 14, 1983.

Martin, Jim, and Pacyga Dominic. Southeast Chicago Historical Project. Columbia College.

Open Lands Project staff. October 12, 1983.

Paulson, Jerry. Lake Michigan Federation, October 12, 1983.

Petraitus, Paul, Historian. Chicago Historical Society, September 14, 1983.

Sullivan, Jerry. Writer. October 12, 1983.

Tomaszewski, Thomas. Chemical Waste Management, Inc., October 3 and 26, 1983.

Valentine, Norma. Chicago South Chamber of Commerce, September 14, 1983.

Vilcins, Ivar. Department of Planning, City of Chicago, August 9, 1983.

Willard, Dr. Dan. School of Public and Environmental Affairs, Indiana University, October 18, 1983.

Wos, Ronald. Chicago Planning Commission, October 11, 1983.

Chapter 4

Bretz, J. H., 1939, Geology of the Chicago Region. Part 1 - General: Illinois Geol. Survey Bull. 65.

Bretz, J. H., 1955, Geology of the Chicago Region. Part 2 - The Pleistocene: Illinois Geol. Survey Bull. 65.

Committee on Medical and Biologic Effects of Environmental Pollutants. 1977. Arsenic: Medical and Biological Effects of Environmental Pollutants. National Research Council, National Academy of Sciences. Natl. Acad. Pr.

Committee on Medical and Biologic Effects of Environmental Pollutants, 1979. Iron: Medical and Biological Effects of Environmental Pollutants. National Research Council, National Academy of Sciences. Natl. Acad. Pr.

Committee on Medical and Biologic Effects of Environmental Pollutants, 1973. Manganese: Medical and Biological Effects of Environmental Pollutants. National Research Council, National Academy of Sciences. Natl. Acad. Pr.

Committee on Medical and Biologic Effects of Environmental Pollutants, 1975. Nickel: Medical and Biological Effects of Environmental Pollutants. National Research Council, National Academy of Sciences, Natl. Acad. Pr.

Lindsay, W.L., 1979. Chemical Equilibria in Soils. John Wiley and Sons, Inc.

Suter, M., R. E. Bergstrom, H. F. Smith, G. H. Emrich, W. C. Walton, T. E. Larson, 1959, Preliminary Report on Ground-Water Resources of the Chicago Region, Illinois: Illinois Water Survey and Illinois Geol. Survey Cooperative Ground-Water Report 1.

U.S. Environmental Protection Agency. "Ambient Water Quality Criteria for Silver," EPA 440/5-80-081, 1980.

Willman, H. B., 1971, Summary of the Geology of the Chicago Area: Illinois Geol. Survey Circular 460.

Willman, H. B., and J. C. Frye, 1970, Pleistocene Stratigraphy of Illinois: Illinois Geol. Survey Bull. 94.

Chapter 6

"Air Quality Modeling", USEPA, OAQPS, RTP, NC, September 1980.

Annual Air Quality Reports," Illinois Environmental Protection Agency, Division of Air Pollution Control, 1974-1983.

"Local Climatological Data" -- 1982 Chicago Illinois, National Oceanic and Atmospheric Administration, National Climatic Data Center, Asheville, N.C.

"Report to Illinois Department of Energy and Natural Resource and Environmental Protection Agency on Air Quality Monitoring at the Lake Calumet Area," TRC Environmental Consultants, Inc., East Hartford, Connecticut, January 26, 1984.

Chapter 7

Illinois Department of Public Health, "Cancer Mortality in Selected Community Areas of Southeast Chicago, 1968-1982: A Detailed Analysis and Review of a Previous Study," 1985.

Illinois EPA, "Southeast Chicago, Draft Report," 1984.

Bailar, J.C., and Ederer, "Significance Factors for the Ratio of a Poisson Variable to its Expectation," Biometrics, 20:639, 1964.

Colton, T., "Statistics in Medicine," Little Brown & Co., Boston, 1974.

APPENDIX A

Arsenic (in ppm) in Soil

Grid No.	<u>0-6" depth</u>	<u>6"-2' depth</u>	<u>2'-00' depth</u>
1	16.0	6.0	8.5
2	6.1	6.5	5.4
3	8.5	0.7	8.3
4	15.0	2.9	2.4
5	7.7	-	1.5
6	13.0	3.7	7.7
8	4.5	1.1	2.3
9	12.0	4.7	17.0
10	9.6	19.0	1.7
12	*	*	*
14	8.7	*	*
15	4.9	*	*
16	7.3	8.7	6.4
17	5.4	6.8	6.5
18	6.7	6.7	6.8
19	14.0	9.6	2.7
20	2.4	2.5	2.4
21	6.5	3.7	8.3
22	5.6	30.0	5.9
23	6.5	7.0	4.0
24	7.8	80.0	1.7
25	6.0	2.5	2.0
Total	<u>174.2</u>	<u>202.1</u>	<u>101.6</u>
Mean	8.3	11.2	5.4
Highest	16.0	80.0	17.0
Lowest	2.4	0.7	1.5

*Slag, unable to retrieve sample

Barium (in ppm) in Soil

Grid No.	1	0-6" depth	6"-2' depth	2'-10' depth
		75.0	50.0	50.0
	2	75.0	75.0	462.5
	3	100.0	450.0	<25.0
	4	100.0	<25.0	<25.0
	5	75.0	-	<25.0
	6	250.0	175.0	25.0
	8	Interference	Interference	Interference
	9	75.0	<25.0	<25.0
	10	75.0	Interference	<25.0
	12	*	*	*
	14	100.0 (slag)	*	*
	15	Interference	*	*
	16	75.0	150.0	150.0
	17	25.0	<25.0	<25.0
	18	75.0	50.0	25.0
	19	125.0	100.0	<25.0
	20	<25.0	<2.5	<2.5
21		Interference	<2.5	25.0
	22	37.5	<2.5	Interference
	23	Interference	100.0	Interference
	24	100.0	62.5	<2.5
	25	75.0	<25.0	<25.0
Total		1,462.5	1,320.0	942.5
Mean		<86.0	<82.5	<58.9
Highest		250.0	450.0	462.0
Lowest		<25.0	<2.5	2.5

*Slag, unable to retrieve sample

Cadmium (in ppm) in Soil

Grid No.	<u>0-6" depth</u>	<u>6"-2' depth</u>	<u>2'-10' depth</u>
1	<2.5	<2.5	<2.5
2	<2.5	<2.5	<2.5
3	2.5	<2.5	<2.5
4	2.5	<2.5	<2.5
5	2.5	-	<2.5
6	2.5	<2.5	<2.5
8	<2.5	<2.5	<2.5
9	<2.5	<2.5	<2.5
10	<2.5	<2.5	<2.5
12	*	*	*
14	2.5	*	*
15	13.2	*	*
16	<2.5	<2.5	<2.5
17	<2.5	<2.5	<2.5
18	<2.5	<2.5	<2.5
19	<2.5	<2.5	<2.5
20	<2.5	<2.5	<2.5
21	<2.5	<2.5	<2.5
22	<2.5	<2.5	<2.5
23	<2.5	<2.5	<2.5
24	<2.5	<2.5	<2.5
<u>25</u>	<u><2.5</u>	<u><2.5</u>	<u><2.5</u>
Total	63.2	45.0	47.5
Mean	<3.0	<2.5	<2.5
Highest	13.2	-	-
Lowest	<2.5	-	-

*Slag, unable to retrieve sample

Chromium (total) (in ppm) in Soil

	<u>0-6" depth</u>	<u>6"-2' depth</u>	<u>2'-10' depth</u>
Grid No. 1	15.5	10.0	16.2
2	18.0	10.0	8.5
3	20.0	5.5	5.5
4	25.0	5.0	2.5
5	35.0	-	3.5
6	37.5	12.5	21.0
8	21.0	18.8	5.0
9	32.0	8.0	<2.5
10	30.0	77.5	3.8
12	*	*	*
14	2,500.0 (slag)	*	*
15	30.0	*	*
16	20.0	21.2	18.5
17	6.2	2.5	5.0
18	12.5	17.5	15.0
19	18.5	8.8	2.5
20	7.5	12.5	2.5
21	5.0	2.5	5.0
22	5.0	5.0	17.5
23	20.0	22.5	5.0
24	10.0	10.0	<2.5
25	22.0	<2.5	<2.5
Total	<u>2,890.7</u>	<u>252.3</u>	<u>144.5</u>
Mean	137.7	14.0	7.6
Highest	2,500.0	77.5	21.0
Lowest	5.0	<2.5	<2.5

(When the 2,500.0 ppm sample is not included in the calculation, the mean becomes 19.54 ppm for the 0-6" depth.)

*Slag, unable to retrieve sample

Copper (in ppm) in Soil

	<u>0-6" depth</u>	<u>6"-2' depth</u>	<u>2'-10' depth</u>
Grid No. 1	51.2	52.5	45.0
2	31.8	23.8	22.5
3	57.5	<2.5	5.0
4	50.0	8.8	3.8
5	38.8	-	7.5
6	77.5	27.5	27.5
8	26.2	<2.5	5.0
9	32.5	11.5	2.5
10	32.5	52.5	2.5
12	*	*	*
14	95.0 (slag)	*	*
15	42.5	*	*
16	22.5	43.8	27.5
17	12.5	12.5	10.0
18	20.0	20.0	20.0
19	31.2	15.0	3.5
20	3.8	5.0	3.0
21	12.5	4.0	10.0
22	9.5	7.0	20.0
23	22.5	27.5	5.0
24	25.0	18.8	<2.5
25	<u>28.8</u>	<u><2.5</u>	<u>2.5</u>
Total	723.8	337.7	225.3
Mean	34.5	18.8	11.9
Highest	95.0	52.5	45.0
Lowest	3.8	<2.5	<2.5

(When the 95.0 ppm sample is not included in the calculation, the mean becomes 31.44 ppm for the 0-6" depth.)

*Slag, unable to retrieve sample

Iron (in ppm) in Soil

	<u>0-6" depth</u>	<u>6"-2' depth</u>	<u>2'-10' depth</u>
Grid No. 1	21,525.0	31,284.0	31,685.0
2	19,486.0	13,837.0	12,251.0
3	25,335.0	9,325.0	8,864.0
4	28,033.0	7,171.1	4,782.9
5	20,572.0	-	6,257.0
6	24,984.0	17,812.0	23,090.0
8	16,645.0	8,309.0	5,120.0
9	20,656.0	13,336.0	4,328.0
10	42,116.0	83,699.0	4,526.0
12	*	*	*
14	174,518.0 (slag)	*	*
15	19,477.0	. *	*
16	24,092.0	18,487.0	18,938.0
17	7,860.8	9,147.5	13,027.0
18	13,697.0	17,098.0	16,491.0
19	26,319.0	14,180.0	5,452.0
20	6,193.0	7,606.0	5,565.0
21	6,088.0	3,919.0	9,196.0
22	6,192.0	14,553.0	20,478.0
23	19,075.0	22,150.0	8,786.0
24	14,891.0	21,723.0	4,095.0
25	14,807.7	4,740.8	4,607.0
Total	552,562.5	318,377.4	207,538.9
Means	26,312.5	17,687.7	10,923.1
Highest	174,518.0	83,699.0	31,685.0
Lowest	6,088.0	3,919.0	4,095.0

(When the 174,518.0 ppm sample is not included in the calculation, the mean becomes 18,902.2 for the 0-6" depth.)

*Slag, unable to retrieve sample

Lead (in ppm) in Soil

Grid No.	<u>0-6" depth</u>	<u>6"-2' depth</u>	<u>2'-10' depth</u>
1	220.00	88.50	32.25
2	131.50	133.25	576.00
3	355.98	<7.50	<7.50
4	152.57	15.04	<7.50
5	137.75	-	<7.50
6	278.55	82.39	11.31
8	163.25	10.00	<7.50
9	89.50	33.75	<7.50
10	103.25	110.50	<7.50
12	*	*	*
14	657.00 (slag)	*	*
15	121.25	*	*
16	34.75	294.15	54.75
17	56.78	<7.50	<7.50
18	33.01	26.05	18.73
19	53.25	28.00	<7.50
20	<7.50	16.50	10.00
21	111.25	<12.50	28.50
22	44.75	18.25	<12.50
23	67.00	20.25	<12.50
24	69.25	27.00	<12.50
25	55.84	<7.50	<7.50
Total	2,943.98	938.63	836.54
Mean	140.19	52.15	44.03
Highest	657.00	294.15	576.00
Lowest	33.01	<7.50	<7.50

(When the 657.0 ppm sample is not included in the calculation, the mean becomes 114.35 ppm for the 0-6" depth.)

*Slag, unable to retrieve sample

Manganese (in ppm) in Soil

	<u>0-6" depth</u>	<u>6"-2' depth</u>	<u>2'-00' depth</u>
Grid No. 1	420.0	145.0	490.0
2	580.0	445.0	475.0
3	870.0	2,247.5	305.3
4	942.0	241.3	216.8
5	480.0	-	182.5
6	462.5	1,215.0	257.3
8	730.0	6,600.0	465.0
9	600.0	405.0	205.0
10	3,425.0	9,250.0	280.0
12	*	*	*
14	32,600.0 (slag)	*	*
15	1,100.0	*	*
16	190.8	395.0	493.8
17	311.5	266.8	321.5
18	453.5	440.8	403.8
19	445.0	640.0	232.5
20	347.5	450.0	302.5
21	315.0	42.5	295.0
22	135.0	52.5	445.0
23	590.0	480.0	2,325.0
24	390.0	355.0	175.0
25	352.0	045.5	092.0
Total	45,739.8	23,816.9	8,063.0
Mean	2,178.1	1,323.2	424.4
Highest	32,600.0	9,250.0	2,325.0
Lowest	135.0	42.5	175.0

(When the 32,600.0 ppm sample is not included in the calculation, the mean becomes 657.0 ppm for the 0-6" depth.)

*Slag, unable to retrieve sample

Mercury (in ppm) in Soil

	<u>0-6" depth</u>	<u>6"-2' depth</u>	<u>2'-00' depth</u>
Grid No. 1	0.10	0.06	0.03
2	0.14	0.08	0.05
3	0.20	0.01	0.02
4	0.07	0.03	0.01
5	0.14	-	0.01
6	0.11	0.29	0.03
8	0.07	0.01	0.01
9	0.08	0.02	0.01
10	0.06	0.03	0.01
12	*	*	*
14	0.02 (slag)	*	*
15	0.27	*	*
16	0.04	0.20	0.02
17	0.02	0.01	0.02
18	0.03	0.05	0.05
19	0.07	0.03	0.01
20	0.01	0.02	0.01
21	0.09	0.02	0.24
22	0.04	0.02	0.02
23	0.05	0.29	0.02
24	0.10	0.09	0.01
25	<u>0.06</u>	<u>0.00</u>	<u>0.00</u>
Total	1.77	1.27	0.59
Means	0.08	0.07	0.03
Highest	0.27	0.29	0.24
Lowest	0.01	0.01	0.01

*Slag, unable to retrieve sample

Nickel (in ppm) in Soil

Grid No.	<u>0-6" depth</u>	<u>6"-2' depth</u>	<u>2'-10' depth</u>
1	<25.0	<25.0	42.5
2	<25.0	<25.0	<25.0
3	<25.0	<25.0	<25.0
4	25.0	<25.0	<25.0
5	<25.0	-	<25.0
6	30.0	<25.0	30.0
8	<25.0	<25.0	<25.0
9	<25.0	<25.0	<25.0
10	30.0	75.0	<25.0
12	*	*	*
14	162.5 (slag)	*	*
15	27.5	*	*
16	<25.0	45.0	25.0
17	<25.0	<25.0	<25.0
18	25.0	25.0	25.0
19	25.0	<25.0	<25.0
20	<25.0	<25.0	<25.0
21	<25.0	<25.0	<25.0
22	<25.0	<25.0	<25.0
23	<25.0	25.0	25.0
24	<25.0	<25.0	<25.0
25	25.0	<25.0	<25.0
Total	675.0	520.0	497.5
Mean	32.1	28.9	26.2
Highest	162.5		
Lowest	25.0		

(When the 162.5 ppm sample is not included in the calculation, the mean becomes 25.6 ppm for the 0-6" depth.)

*Slag, unable to retrieve sample

Selenium (in ppm) in Soil

Grid No.	<u>0-6" depth</u>	<u>6"-2' depth</u>	<u>2'-10' depth</u>
1	0.6	0.6	0.5
2	0.5	0.2	0.3
3	0.7	0.4	5.2
4	1.3	0.3	<0.1
5	0.5	-	0.1
6	0.5	1.3	0.5
8	0.5	4.0	0.2
9	0.7	0.4	<0.1
10	0.6	2.3	0.2
12	*	*	*
14	2.1 (slag)	*	*
15	0.8	*	*
16	0.6	0.5	0.2
17	0.2	0.1	0.2
18	0.6	0.6	0.5
19	0.7	0.4	0.1
20	0.3	0.1	<0.1
21	0.5	0.1	0.2
22	0.4	0.2	0.1
23	0.3	0.2	0.2
24	0.6	0.6	0.1
25	0.6	<0.1	<0.1
Total	13.6	12.4	9.0
Mean	0.65	0.55	0.47
Highest	2.10	4.00	5.20
Lowest	0.20	0.10	<0.10

(When the 2.1 ppm sample is not included in the calculation, the mean becomes 0.58 ppm for the 0-6" depth.)

*Slag, unable to retrieve sample

Silver (in ppm) in Soil

Grid No.	<u>0-6" depth</u>	<u>6"-2' depth</u>	<u>2'-10' depth</u>
1	<2.5	<2.5	<2.5
2	<2.5	<2.5	<2.5
3	<2.5	5.0	<2.5
4	<2.5	<2.5	<2.5
5	<2.5	-	<2.5
6	<2.5	<2.5	<2.5
8	<2.5	3.8	<2.5
9	<2.5	<2.5	<2.5
10	<2.5	<2.5	<2.5
12	*	*	*
14	3.8 (slag)	*	*
15	<2.5	*	*
16	<2.5	<2.5	<2.5
17	<2.5	<2.5	<2.5
18	<2.5	<2.5	<2.5
19	<2.5	<2.5	<2.5
20	<2.5	<2.5	<2.5
21	<2.5	<2.5	<2.5
22	<2.5	<2.5	<2.5
23	<2.5	<2.5	<2.5
24	<2.5	<2.5	<2.5
25	<2.5	<2.5	<2.5
Total	53.8	48.8	47.5
Mean	<2.56	<2.71	<2.5
Highest	3.8	5.0	-
Lowest	<2.5	<2.5	-

(When the 3.8 ppm sample is not included in the calculation, the mean becomes <2.5 ppm for the 0-6" depth.)

*Slag, unable to retrieve sample

Zinc (in ppm) in Soil

Grid No.	<u>0-6" depth</u>	<u>6"-2' depth</u>	<u>2'-00' depth</u>
1	190.0	167.5	105.0
2	132.5	92.5	340.0
3	265.0	2.5	35.0
4	390.0	45.0	17.5
5	202.5	-	27.5
6	212.5	65.0	67.5
8	275.0	15.0	25.0
9	255.0	95.0	17.5
10	177.5	220.0	17.5
12	*	*	*
14	412.5 (slag)	*	*
15	550.0	*	*
16	70.0	125.0	90.0
17	95.0	42.5	65.0
18	105.0	110.0	80.0
19	132.5	52.5	20.0
20	32.5	50.0	20.0
21	200.0	25.0	30.0
22	62.5	35.0	55.0
23	92.5	82.5	32.5
24	167.5	70.0	17.5
25	005.0	20.0	05.0
Total	<u>4,135.0</u>	<u>1,315.0</u>	<u>1,077.5</u>
Mean	196.9	73.1	56.7
Highest	550.0	220.0	340.0
Lowest	32.5	2.5	17.5

(When the 412.5 ppm sample is not included in the calculation, the mean becomes 186.1 ppm for the 0-6" depth.)

*Slag, unable to retrieve sample

APPENDIX B

Time Collected:

Lab #

30775

Date Collected:

9/27/83

SPECIAL ANALYSIS FORM

Date Received

9/30/83

ILLINOIS ENVIRONMENTAL PROTECTION AGENCY
DIVISION OF LAND/NOISE POLLUTION CONTROL

COUNTY:

Cook

FILE HEADING:

FILE NUMBER:

SOURCE OF SAMPLE: (Exact Location)

Republic Steel

Grail #14

PHYSICAL OBSERVATIONS, REMARKS:

Soil 5' - 6' indentation

on OVA

30774 - 6025ed

↓ 75 3 THM

TESTS REQUESTED:

Organic soil

COLLECTED BY:

Sherry O'Brien

TRANSPORTED BY:

Dan Tolson

LABORATORY

RECEIVED BY: Rne

DATE

COMPLETED:

12/12/83

DATE

FORWARDED:

12/12/83

Chlorinated hydrocarbon pesticides not detected

PCBs not detected (<0.1ug/g)

Volatile organic compounds not detected (<0.06ug/g)

Base-Neutral and Acid extractables not detected (<5.ug/g)

DO 30775 (501)

[illegible]

Time Collected: _____

Lab # _____

0030572

Date Collected: 9-14-83

SPECIAL ANALYSIS FORM

Date Received SEP 16 1983

0030572

SEP 16 1983

ILLINOIS ENVIRONMENTAL PROTECTION AGENCY
DIVISION OF LAND/NOISE POLLUTION CONTROL

COUNTY: _____

FILE HEADING: _____

FILE NUMBER: _____

Cook

SOURCE OF SAMPLE: (Exact Location)

Grid # 15 15-50 ft depth

Wolf Lake

PHYSICAL OBSERVATIONS, REMARKS: soil sample - looks like boundary sand

30571 - 2 THM VIALS

30572 - 2 CLEAR 602 SED JARS

TESTS REQUESTED: mg. scan

COLLECTED BY: Doug Talan

TRANSPORTED BY: Sherry D+Ta

LABORATORY

RECEIVED BY: Rmc/ms

DATE COMPLETED: 11/18/83

DATE FORWARDED: 11/18/83

DO 30571 Volatile organic compounds not detected

DO 30572 PCBs Not detected ($< 10 \mu\text{g/g}$ PPB $\approx < 0.01 \mu\text{g/g}$ PPM)

Chlorinated hydrocarbon pesticides not detected

Aliphatic hydrocarbons $\text{C}_{12}-\text{C}_{26} = 10 \mu\text{g/g}$ (PPM)

0030573

0030574

SEP 16 1983

Time Collected: _____

Lab # _____

Date Collected: 9-14-83

SPECIAL ANALYSIS FORM

Date Received _____

ILLINOIS ENVIRONMENTAL PROTECTION AGENCY
DIVISION OF LAND/NOISE POLLUTION CONTROL

COUNTY: _____

FILE HEADING: _____

FILE NUMBER: _____

Cook

SOURCE OF SAMPLE: (Exact Location)

Grid #15 0° - 0.5 ft depth

Wolf Lake

PHYSICAL OBSERVATIONS, REMARKS: soil sample - looks like boundary sand

30573 - 2 each THM Vials

30574 - 2 each 602 SED (CLEAR) JARS

TESTS REQUESTED: _____

COLLECTED BY: Doug Tolan

TRANSPORTED BY: Sherry Otto

LABORATORY

RECEIVED BY: Rmc/ms

DATE COMPLETED: 11/18/83

DATE FORWARDED: 11/18/83

D030573 Volatile organic compounds not detected *Sherry*

D030574 PCBs Not detected

Chlorinated hydrocarbon pesticides Not detected

Aliphatic hydrocarbons C₁₂-C₂₆ = 1 ug/g (ppm)

Naphthalene = 0.2 ug/g

Phenanthrene/Anthracene = 1 ug/g

Time Collected: _____

Date Collected: 9-14-83

SPECIAL ANALYSIS FORM

Date Received _____

ILLINOIS ENVIRONMENTAL PROTECTION AGENCY
DIVISION OF LAND/NOISE POLLUTION CONTROL

COUNTY: _____

Cock

FILE HEADING: _____

FILE NUMBER: _____

SOURCE OF SAMPLE: (Exact Location)

Grid #23 0²-0⁵ ft depth

Hoxie Tot Lot

PHYSICAL OBSERVATIONS, REMARKS: soil samples no odor detected

30579 - 3 EACH THM VIALS

30580 - 2 EACH 602 CLEAR SEALS

TESTS REQUESTED: _____

COLLECTED BY: Doug Tolan

TRANSPORTED BY: Sherry Otto

LABORATORY

RECEIVED BY: Rmc/ms

DATE

COMPLETED: 11/15/83

DATE

FORWARDED: 11/15/83

D030579 - Volatile organic compounds not detected

D030580 PCBs not detected

Chlorinated hydrocarbon pesticides not detected

Aliphatic hydrocarbons C₁₂-C₂₆ = 3 ug/g

Phenanthrene / Anthracene = 0.2 ug/g

30580 Rm-

Time Collected: _____

Lab # _____

30581
SEP 16 1983

Date Collected: 9-14-83

SPECIAL ANALYSIS FORM

Date Received _____

ILLINOIS ENVIRONMENTAL PROTECTION AGENCY
DIVISION OF LAND/NOISE POLLUTION CONTROL

30582

COUNTY: _____

FILE HEADING: _____

FILE NUMBER: _____

Cook

SOURCE OF SAMPLE: (Exact Location)

Grid # 23 05-2° ft.

Horie Tot Lot

PHYSICAL OBSERVATIONS, REMARKS: 301 samples

30581 - 3 each THM VIALS
30582 - 2 602 CLEAR SED JARS

TESTS REQUESTED: _____

COLLECTED BY: Drug Tolan

TRANSPORTED BY: Sherry Otto

LABORATORY

RECEIVED BY: Bmc/ms

DATE
COMPLETED:

11/18/83

DATE
FORWARDED: 11/18/83

D030581 Volatile organic compounds not detected

Sherry

D030582 - PCBs not detected

Chlorinated hydrocarbon pesticides not detected

Aliphatic hydrocarbons C₁₂-C₂₆ = 5µg/g

Time Collected:

Lab #

11/18/83 Hmc

11/18/83 Hmc

Date Collected: 9-14-83

SPECIAL ANALYSIS FORM

Date Received

SEP 16 1983

ILLINOIS ENVIRONMENTAL PROTECTION AGENCY
DIVISION OF LAND/NOISE POLLUTION CONTROL

COUNTY:

FILE HEADING:

FILE NUMBER:

Cook

SOURCE OF SAMPLE: (Exact Location)

Grid # 24 05-2° ft depth

Burnham Park

PHYSICAL OBSERVATIONS, REMARKS: soil sample

30583 - 3 each THM vials

30584 - 2 each lead clean
seal jar

TESTS REQUESTED:

COLLECTED BY: Doug Tolan

TRANSPORTED BY: Sherry Otto

LABORATORY

RECEIVED BY: Rmc/ms

DATE
COMPLETED:

11/18/83

DATE
FORWARDED: 11/18/83

DO 30583 Volatile organic compounds not detected

DO 30584 PCBs not detected

Chlorinated hydrocarbon pesticides not detected

Base-Neutral and Acid extractable compounds not detected

Time Collected: _____

Lab # _____

Date Collected: 9-14-83

SPECIAL ANALYSIS FORM

Date Received _____

D030585 Rmc
D030586 Rmc
SEP 16 1983

ILLINOIS ENVIRONMENTAL PROTECTION AGENCY
DIVISION OF LAND/NOISE POLLUTION CONTROL

COUNTY: _____

FILE HEADING: _____

FILE NUMBER: _____

Cook

SOURCE OF SAMPLE: (Exact Location)

Grid #24 0^s - 0^s ft. depth

Burnham Park

PHYSICAL OBSERVATIONS, REMARKS: soil sample

TESTS REQUESTED: _____

COLLECTED BY: Doug Tolan

TRANSPORTED BY: Sherry Cotto

LABORATORY

RECEIVED BY: Rmc/ms

DATE
COMPLETED: 11/18/83

DATE
FORWARDED: 11/18/83
D. H. Hargis

D030585 Volatile organic compounds not detected

D030586 PCBs not detected

Chlorinated hydrocarbon pesticides not detected

Base-Neutral and Acid extractable compounds not detected

Detection limits for pesticides & PCBs in water

Parameter	$\mu\text{g/l}$ <i>PPb</i>	Parameter	$\mu\text{g/l}$
Lindane	<0.01	o,p' -DDE	<0.01
Heptachlor	<0.01	p,p' -DDE	<0.01
Aldrin	<0.01	o,p' -DDD	<0.01
Heptachlor Epoxide	<0.01	p,p' -DDD	<0.01
Alpha Chlordane	<0.01	o,p' -DDT	<0.01
Gamma Chlordane	<0.01	p,p' -DDT	<0.01
Dieldrin	<0.01	Toxaphene	<0.5
Endrin	<0.01	Silvex	
Methoxychlor	<0.05	2,4-D	
		<i>PCBs</i>	<0.1

Laboratory Number

- EPA Use Only -

Test by:

Date:

30756

Time Collected:

Lab #

SPECIAL ANALYSIS FORM

30757

Date Collected:

9/28/83

Date Received

ILLINOIS ENVIRONMENTAL PROTECTION AGENCY
DIVISION OF LAND/NOISE POLLUTION CONTROL

COUNTY:

Cook

FILE HEADING:

FILE NUMBER:

SOURCE OF SAMPLE: (Exact Location)

Olive Harvey College

Grid # 2

PHYSICAL OBSERVATIONS, REMARKS:

30756 1-gal H₂O

↓ 57.3 each THM

TESTS REQUESTED:

Organic Scan

COLLECTED BY:

Sherry O'S

TRANSPORTED BY:

Dany Tolm

LABORATORY

RECEIVED BY:

Rmc

DATE

COMPLETED:

12/12/83

DATE

FORWARDED:

12/12/83

Chlorinated hydrocarbon pesticides not detected

PCBs not detected (<0.1 ug/l)

Base-Neutral and Acid extractable compounds not detected (K₁)
except for Dibutyl phthalate = 63 ug/l

DO 30757

	ug/l (ppb)		
methylene chloride	<1		
1,1-dichloroethane	<1		
dichloroethylene	<1		
chloroform	<1		
1,2-dichloroethane	<1		
1,1,1-trichloroethane	<1		
carbon tetrachloride	<1		
dichlorobromomethane	<1		
trichloroethylene	<1		
dibromochloromethane	<1		
bromoform	<1		
tetrachloroethylene	<1		
benzene	5	possible but could not be positively identified	
toluene	<5		
xylene	<5		
ethyl benzene	<5		

0630758

0630759

SEP 30 1983

Time Collected: _____

Lab #

Date Collected: 9/28/83

SPECIAL ANALYSIS FORM

Date Received _____

ILLINOIS ENVIRONMENTAL PROTECTION AGENCY
DIVISION OF LAND/NOISE POLLUTION CONTROL

COUNTY: _____

FILE HEADING: _____

FILE NUMBER: _____

SOURCE OF SAMPLE: (Exact Location)

Cook
Grid #3Luella Playground

PHYSICAL OBSERVATIONS, REMARKS:

30758 - 1 gal #20↓ 59 - 3 each THMTESTS REQUESTED: Organic ScreenCOLLECTED BY: Shirley O. RossTRANSPORTED BY: Pam Tolan

LABORATORY

RECEIVED BY: Rmc

DATE

COMPLETED: 12/12/83

DATE

FORWARDED: 12/12/83

Chlorinated hydrocarbon pesticides not detected
PCBs not detected (<0.1 ug/l)
Volatile organic compounds not detected (<5 ug/l)
Base Neutral and Acid extractable compounds not detected (<5 ug/l)
except Dibutyl phthalate = 6.9 ug/l

D030759

	ug/l (ppb)		
methylene chloride	<1		
1,1-dichloroethane	<1		
dichloroethylene	<1		
chloroform	<1		
1,2-dichloroethane	<1		
1,1,1-trichloroethane	<1		
carbon tetrachloride	<1		
dichlorobromomethane	<1		
trichloroethylene	<1		
dibromochloromethane	<1		
bromoform	<1		
tetrachloroethylene	<1		
Benzene	<5		
Toluene	<5		
Xylenes	<5		
Ethylbenzene	<5		

Time Collected:

Lab #

030750

030751

SEP 30 1983

Date Collected:

9/28/83

SPECIAL ANALYSIS FORM

Date Received

ILLINOIS ENVIRONMENTAL PROTECTION AGENCY
DIVISION OF LAND/NOISE POLLUTION CONTROL

COUNTY:

Cook

FILE HEADING:

FILE NUMBER:

SOURCE OF SAMPLE: (Exact Location)

Veterans Mem. Park

Grid # 4

PHYSICAL OBSERVATIONS, REMARKS:

30760 - 1 gal

✓ 61 - 3 1/4 m

TESTS REQUESTED:

organic scan

COLLECTED BY:

Sherry Otto

TRANSPORTED BY:

Dave Tolson

LABORATORY

RECEIVED BY: lmr

DATE

COMPLETED:

12/12/83

DATE

FORWARDED:

12/12/83

Chlorinated hydrocarbon pesticides not detected Sherry

PCBs not detected (< 0.1 µg/l)

Volatile organic compounds not detected (< 5 µg/l)

Base-Neutral and Acid extractable compounds not detected
except for Dibutyl phthalate 7.5 µg/l < 5 µg/l

DO 30761

	ug/l (ppb)		
methylene chloride	<1		
1,1-dichloroethane	<1		
dichloroethylene	<1		
chloroform	<1		
1,2-dichloroethane	<1		
1,1,1-trichloroethane	<1		
carbon tetrachloride	<1		
dichlorobromomethane	<1		
trichloroethylene	<1		
dibromochloromethane	<1		
bromoform	<1		
tetrachloroethylene	<1		
Benzene	<5		
Toluene	<5		
Xylenes	<5		
Ethylbenzene	<5		

LP 41

Time Collected:

Lab #

D030691

Date Collected:

9-21-83

SPECIAL ANALYSIS FORM

Date Received

SEP 22 1983

ILLINOIS ENVIRONMENTAL PROTECTION AGENCY
DIVISION OF LAND/NOISE POLLUTION CONTROL

COUNTY:

COOK

FILE HEADING:

FILE NUMBER:

SOURCE OF SAMPLE: (Exact Location)

CALUMET PARK

GRID # 5

PHYSICAL OBSERVATIONS, REMARKS:

N/O ODOR; REMOVED SEVERAL
VOLUMES

TESTS REQUESTED:

ORGANICS SCAN

COLLECTED BY:

SHERRY OTTO

LPC

TRANSPORTED BY:

KEN BOSIE

DOUG TOLAN

LPC

LABORATORY

RECEIVED BY:

LM

DATE

COMPLETED:

11/18/83

DATE

FORWARDED:

11/18/83

Volatile organic compounds not detected

PCBs not detected

Chlorinated hydrocarbon pesticides not detected

Base-Neutral and Acid extractable compounds not detected

LP41

Time Collected:

Lab #

DO 30693

Date Collected:

9-21-83

SPECIAL ANALYSIS FORM

Date Received

SEP 22 1983

ILLINOIS ENVIRONMENTAL PROTECTION AGENCY
DIVISION OF LAND/NOISE POLLUTION CONTROL

COUNTY:

COOK

FILE HEADING:

FILE NUMBER:

SOURCE OF SAMPLE: (Exact Location)

BRIGHT SCHOOL

GRID #8

PHYSICAL OBSERVATIONS, REMARKS:

NO ODOR ; REMOVED
SEVERAL VOLUMES

TESTS REQUESTED:

ORGANICS SCAN

COLLECTED BY:

SHERRY OTTO

LPC

TRANSPORTED BY:

KEN BOJIE

DOUG TOLAN

LPC

LABORATORY

RECEIVED BY:

RN

DATE

COMPLETED:

11/18/83

DATE

FORWARDED:

11/18/83

Volatile organic compounds not detected

PCBs - not detected

Chlorinated hydrocarbon pesticides not detected

Base-Neutral and Acid extractable compounds not detected

LP 41

Time Collected:

Lab # D030695

Date Collected:

9-21-83

SPECIAL ANALYSIS FORM

Date Received

SEP 27 1983

ILLINOIS ENVIRONMENTAL PROTECTION AGENCY
DIVISION OF LAND/NOISE POLLUTION CONTROL

COUNTY:

COOK

FILE HEADING:

FILE NUMBER:

SOURCE OF SAMPLE: (Exact Location)

WOLFE PLAYGROUND PARK
GRID # 9

PHYSICAL OBSERVATIONS, REMARKS:

NO ODOR; REMOVED
SEVERAL VOLUMES

TESTS REQUESTED:

ORGANICS SCAN

COLLECTED BY:

SHERY OTTO

TRANSPORTED BY:

KEN BOJWA
DOUG TOLAN LPC

LABORATORY

RECEIVED BY:

PM

DATE

COMPLETED:

11/18/83

DATE

FORWARDED:

11/18/83

Volatile organic compounds not detected

OTM

PCBs not detected

Chlorinated hydrocarbon pesticides - not detected

Base-Neutral and Acid extractable compounds not detected.

LP 41

Time Collected:

Lab #

D030690

Date Collected:

9-21-83

SPECIAL ANALYSIS FORM

Date Received SEP 22 1983

ILLINOIS ENVIRONMENTAL PROTECTION AGENCY
DIVISION OF LAND/NOISE POLLUTION CONTROL

COUNTY:

COOK

FILE HEADING:

FILE NUMBER:

SOURCE OF SAMPLE: (Exact Location) ADAMS ELEMENTARY PLAYGROUND
GRID # 10

PHYSICAL OBSERVATIONS, REMARKS:

NO ODOR; REMOVED
SEVERAL VOLUMES

TESTS REQUESTED:

ORGANICS SCAN

COLLECTED BY:

SHERY OTTO LPE

TRANSPORTED BY:

Ken Bosic {
DOWG TOLAN LPE

LABORATORY

RECEIVED BY:

RA

DATE

COMPLETED:

11/18/83

DATE

FORWARDED:

11/18/83

Volatile organic compounds not detected (< 5. ug/l - PPH₂)

PCBs - not detected (< 0.1 ug/l)

Chlorinated hydrocarbon pesticides not detected

Base-Neutral Acid extractable compounds not detected (< 5. ug/l)

LPH

0030752

0030753

SEP 30 1983

Time Collected:

Lab #

SPECIAL ANALYSIS FORM

Date Collected:

9/27/83

Date Received

ILLINOIS ENVIRONMENTAL PROTECTION AGENCY
DIVISION OF LAND/NOISE POLLUTION CONTROL

COUNTY:

Cook

FILE HEADING:

FILE NUMBER:

SOURCE OF SAMPLE: (Exact Location)

Chicago Port Dist.

Grid #12

PHYSICAL OBSERVATIONS, REMARKS:

OVA indicated some organics present

30762 - 1 gal

↓ 63 - 3 THM

TESTS REQUESTED:

organic scan

COLLECTED BY:

Sherry O. etc

TRANSPORTED BY:

Dany Tolm

LABORATORY

RECEIVED BY: fne

DATE

COMPLETED:

12/12/83

DATE

FORWARDED:

12/12/83

Chlorinated hydrocarbon pesticides not detected

PCBs not detected

Benzene = 580 ug/l

Indene = 40 ug/l

Toluene = 1700 ug/l

Phenylethanone = 110 ug/l

Xylenes = 560 ug/l

Dimethyl pyridine = 140. ug/l

Ethyl benzene = 30 ug/l

Benzothiophene = 20 ug/l

Pyridine = 10 ug/l

Acenaphthalene = 20 ug/l

Methylpyridine = 5 ug/l

Dibutyl phthalate = 1.3 ug/l

C₃-Substituted benzenes = 40 ug/l

Unidentified compounds estimated to be approximately 35. ug/l Total

Naphthalene = 970 ug/l

Methyl naphthalene = 60 ug/l

LPC-8A 4/77

(NOT FOR DATA PROCESSING)

0030753

0030752

D030763

	ug/l (ppb)		
methylene chloride	<1		
1,1-dichloroethane	<1		
dichloroethylene	<1		
chloroform	<1		
1,2-dichloroethane	<1		
1,1,1-trichloroethane	<1		
carbon tetrachloride	<1		
dichlorobromomethane	<1		
trichloroethylene	<1		
dibromochloromethane	<1		
bromoform	<1		
tetrachloroethylene	<1		
Benzene	580		
Toluene	1700		
Xylenes	560		
Ethylbenzene	30		
pyridine	10		
Methylpyridine	5		

LP41

030754
030755
SEP 30 1983

Time Collected: _____
Date Collected: 9/27/83

Lab # _____
SPECIAL ANALYSIS FORM
Date Received _____

ILLINOIS ENVIRONMENTAL PROTECTION AGENCY
DIVISION OF LAND/NOISE POLLUTION CONTROL

COUNTY: Cook FILE HEADING: _____ FILE NUMBER: _____

SOURCE OF SAMPLE: (Exact Location) Republic Steel
Grind #14

PHYSICAL OBSERVATIONS, REMARKS: OVA indicated organics
no color

30764 - 1 gal
↓ 65 3 THM

TESTS REQUESTED: Organic Sam

COLLECTED BY: Sherry Oth TRANSPORTED BY: Dan Tolson
LABORATORY

RECEIVED BY: Rmc DATE COMPLETED: 12/12/83 DATE FORWARDED: 12/12/83

Chlorinated hydrocarbon pesticides not detected Q. Kureny
PCBs not detected (<0.1 ug/l)
pyridine = 20 ug/l
Methyl pyridine = 15 ug/l
Dibutyl phthalate = 3.9 ug/l

030754
030755

D030765

	ug/l (ppb)		
methylene chloride	<1		
1,1-dichloroethane	<1		
dichloroethylene	<1		
chloroform	<1		
1,2-dichloroethane	<1		
1,1,1-trichloroethane	<1		
carbon tetrachloride	<1		
dichlorobromomethane	<1		
trichloroethylene	<1		
dibromochloromethane	<1		
bromoform	<1		
tetrachloroethylene	<1		
Benzene	5	Possible but could not be positively identified 94 identified	
Toluene	<5		
xylene s	<5		
ethyl benzene	<5		

LP#1

030756
030757

Time Collected: _____

Lab #

Date Collected: 9/27/83

SPECIAL ANALYSIS FORM

Date Received _____

SEP 30 1983

ILLINOIS ENVIRONMENTAL PROTECTION AGENCY
DIVISION OF LAND/NOISE POLLUTION CONTROL

COUNTY:

FILE HEADING:

FILE NUMBER:

Cook

SOURCE OF SAMPLE: (Exact Location)

New Comer High School

Grind #16

PHYSICAL OBSERVATIONS, REMARKS:

OVA indicated organics present

No odor

30756 - 1 gal

✓ 67 - 3 T.M.

TESTS REQUESTED:

organic scan

COLLECTED BY:

S. L. O. O. O.

TRANSPORTED BY:

D. L. O. O. O.

LABORATORY

RECEIVED BY:

Rmc

DATE
COMPLETED:

12/12/8

DATE
FORWARDED:

12/12/8

Chlorinated hydrocarbon pesticides Not detected

PCBs Not detected (< 0.1 ug/l)

Volatile organic compounds not detected

Dibutylphthalate = 76 ug/l

Aliphatic hydrocarbons = 10 ug/l

D030767

	ug/l (ppb)		
methylene chloride	<1		
1,1-dichloroethane	<1		
dichloroethylene	<1		
chloroform	<1		
1,2-dichloroethane	<1		
1,1,1-trichloroethane	<1		
carbon tetrachloride	<1		
dichlorobromomethane	<1		
trichloroethylene	<1		
dibromochloromethane	<1		
bromoform	<1		
tetrachloroethylene	<1		
Benzene	<5		
Toluene	<5		
Xylenes	<5		
Ethylbenzene	<5		

11241

30758

30759

SEP 30 1983

Time Collected:

Lab #

SPECIAL ANALYSIS FORM

Date Collected:

9/26/83

Date Received

ILLINOIS ENVIRONMENTAL PROTECTION AGENCY
DIVISION OF LAND/NOISE POLLUTION CONTROL

COUNTY:

Cook

FILE HEADING:

FILE NUMBER:

SOURCE OF SAMPLE: (Exact Location)

Beaubien Forest Preserve

Grid # 17

PHYSICAL OBSERVATIONS, REMARKS:

30768 - 1 gal
↓ 69 - 374m

TESTS REQUESTED:

Organic scan

COLLECTED BY:

Sherry D. H.

TRANSPORTED BY:

Dany Tolan

LABORATORY

RECEIVED BY:

P. M.

DATE

COMPLETED:

12/12/83

DATE

FORWARDED:

12/12/83

Chlorinated hydrocarbon pesticides not detected

PCBs not detected (0.1 ug/l)

Possible trace of pyridine & methyl pyridine < 5 ug/l

Dibutyl phthalate = 15 ug/l

DO30769

	ug/l (ppb)		
methylene chloride	<1		
1,1-dichloroethane	<1		
dichloroethylene	<1		
chloroform	<1		
1,2-dichloroethane	<1		
1,1,1-trichloroethane	<1		
carbon tetrachloride	<1		
dichlorobromomethane	<1		
trichloroethylene	<1		
dibromochloromethane	<1		
bromoform	<1		
tetrachloroethylene	<1		
Benzene	<5		
Toluene	<5		
Xylenes	<5		
Ethylbenzene	<5		

LP#

Time Collected: _____

Lab #

30770
30771
SEP 30 1983

Date Collected: 7/27/83

SPECIAL ANALYSIS FORM

Date Received _____

ILLINOIS ENVIRONMENTAL PROTECTION AGENCY
DIVISION OF LAND/NOISE POLLUTION CONTROL

COUNTY:

Cook

FILE HEADING:

FILE NUMBER:

SOURCE OF SAMPLE: (Exact Location) Thomas O'Brien Lock + Dam

Grail #18

PHYSICAL OBSERVATIONS, REMARKS:

O.V.A. indicated organics present

30770 - 1 grail

↓ 71 - 3 T4m

TESTS REQUESTED:

organic screen

COLLECTED BY: Sam C. Ellis

TRANSPORTED BY: Dave Tolan

LABORATORY

RECEIVED BY: Rme

DATE COMPLETED:

12/12/83

DATE

FORWARDED: 12/12/83

Chlorinated hydrocarbon pesticides Not detected

PCBs Not detected (<0.1 ug/l)

Volatile organic compounds Not detected (<5. ug/l)

Base-Neutral and Acid extractables Not detected (<5. ug/l)

except for Dibutyl phthalate = 5. ug/l

D030771

	ug/l (ppb)		
methylene chloride	<1		
1,1-dichloroethane	<1		
dichloroethylene	<1		
chloroform	<1		
1,2-dichloroethane	<1		
1,1,1-trichloroethane	<1		
carbon tetrachloride	<1		
dichlorobromomethane	<1		
trichloroethylene	<1		
dibromochloromethane	<1		
bromoform	<1		
tetrachloroethylene	<1		
Benzene	<5		
Toluene	<5		
Xylenes	<5		
ethylbenzene	<5		

LP 41

Time Collected: _____

Lab #

D030694

Date Collected: 9-20-83

SPECIAL ANALYSIS FORM

Date Received

SEP 27 1983

ILLINOIS ENVIRONMENTAL PROTECTION AGENCY
DIVISION OF LAND/NOISE POLLUTION CONTROL

COUNTY:

COOK

FILE HEADING:

FILE NUMBER:

SOURCE OF SAMPLE: (Exact Location)

MANN PARK

GRID #19

PHYSICAL OBSERVATIONS, REMARKS:

No ODOR; REMOVED SEVERAL
VOLUMES

TESTS REQUESTED:

ORGANICS SCAN

KEN BELLIS

COLLECTED BY:

SHERRY OTTO LPC

TRANSPORTED BY:

DOUG TOLAN LPC

LABORATORY

RECEIVED BY:

RM

DATE
COMPLETED:

11/15/83

DATE
FORWARDED:

11/15/83

Volatile organic compounds not detected
PCBs - not detected
Chlorinated hydrocarbon pesticides not detected
Base-Neutral and Acid extractable compounds not detected

LP 41

Time Collected:

Lab #

DO30692

Date Collected:

9-20-83

SPECIAL ANALYSIS FORM

Date Received

SEP 27 1983

ILLINOIS ENVIRONMENTAL PROTECTION AGENCY
DIVISION OF LAND/NOISE POLLUTION CONTROL

COUNTY:

COOK

FILE HEADING:

FILE NUMBER:

SOURCE OF SAMPLE: (Exact Location)

SOUTH PORTION OF WOLFE LAKE
GRID # 20

PHYSICAL OBSERVATIONS, REMARKS:

No Odor; SEVERAL VOLUMES
REMOVED

TESTS REQUESTED:

ORGANICS SCAN

COLLECTED BY:

SHERY OTTO LPC

TRANSPORTED BY:

KEN BORIE }
DOUG TOLAN LPC

LABORATORY

RECEIVED BY:

RM

DATE

COMPLETED:

11/15/83

DATE

FORWARDED:

11/15/83

Volatile organic compounds not detected

PCBs - not detected

Chlorinated hydrocarbon pesticides not detected

Base-Neutral and Acid extractable compounds not detected

30575

Time Collected: _____

Lab #

30576

Date Collected: 9-14-83

SPECIAL ANALYSIS FORM

SEP 16 1983

Date Received _____

ILLINOIS ENVIRONMENTAL PROTECTION AGENCY
DIVISION OF LAND/NOISE POLLUTION CONTROL

COUNTY:

Cook

FILE HEADING:

FILE NUMBER:

SOURCE OF SAMPLE: (Exact Location)

Grid # 22 H₂O sampleJohn W. Needles ParkPHYSICAL OBSERVATIONS, REMARKS: slow recharge, removed 1 volume
on 9-13-8330575 - 3 EACH THM VIALS30576 - 1 GAL. WATER

TESTS REQUESTED:

COLLECTED BY: Sherry OttoTRANSPORTED BY: Sherry Otto

LABORATORY

RECEIVED BY: Rmc/msDATE COMPLETED: 11/18/83DATE FORWARDED: 11/18/83DO 30575 Volatile organic compounds not detected
($< 5. \mu\text{g/l}$ PPB)DO 30576 PCBs not detected
($< 0.1 \mu\text{g/l}$)Chlorinated hydrocarbon pesticides not detectedBase-Neutral and Acid extractable compounds not detected
($< 0.2 \mu\text{g/l}$)
($< 5. \mu\text{g/l}$ PPB)

Time Collected: _____

Lab # _____

Date Collected: 9-14-83

SPECIAL ANALYSIS FORM

Date Received _____

0030577

0030578

SEP 16 1983

ILLINOIS ENVIRONMENTAL PROTECTION AGENCY
DIVISION OF LAND/NOISE POLLUTION CONTROL

COUNTY: _____

FILE HEADING: _____

FILE NUMBER: _____

Cook

SOURCE OF SAMPLE: (Exact Location)

Grid # 24 H₂O sample

PHYSICAL OBSERVATIONS, REMARKS: removed several volumes before
sampling, no odor

30577 - 3 each THM vials

30578 - 1 gal water

TESTS REQUESTED: _____

COLLECTED BY: Sherry Otto

TRANSPORTED BY: Sherry Otto

LABORATORY

RECEIVED BY: Rmc/ms

DATE COMPLETED: 11/18/83

DATE FORWARDED: 11/18/83

D030577 Volatile organic compounds not detected 2 lines
($< 5 \text{ mg/l}$ PPS)

D030578 PCBs not detected $< 0.1 \text{ mg/l}$

Chlorinated hydrocarbon pesticides not detected

Base-Neutral and acid extractable compounds not detected
($< 5 \text{ mg/l}$)

1P11

Time Collected: _____

Lab # _____

030772

030773

SEP 30 1983

Date Collected: 9/28/83

SPECIAL ANALYSIS FORM

Date Received _____

ILLINOIS ENVIRONMENTAL PROTECTION AGENCY
DIVISION OF LAND/NOISE POLLUTION CONTROL

COUNTY: _____

FILE HEADING: _____

FILE NUMBER: _____

Cook

SOURCE OF SAMPLE: (Exact Location) _____

Burnham Woods Golf Course

Grid # 25

PHYSICAL OBSERVATIONS, REMARKS: _____

30772 - 1 gal

↓ 73 - 3 THM

TESTS REQUESTED: organic scan

COLLECTED BY: S. J. O. O. O.

TRANSPORTED BY: D. J. T. T. T.

LABORATORY

RECEIVED BY: R. M. C.

DATE

COMPLETED: 12/12/83

DATE

FORWARDED: 12/12/83

Chlorinated hydrocarbon pesticides not detected

PCBs not detected (<0.1 ug/l)

Volatile organic compounds not detected (<5. ug/l)

Base-Neutral and Acid extractable compounds not detected

(<5. ug/l)

D030.773

	ug/l (ppb)		
methylene chloride	<1		
1,1-dichloroethane	<1		
dichloroethylene	<1		
chloroform	<1		
1,2-dichloroethane	<1		
1,1,1-trichloroethane	<1		
carbon tetrachloride	<1		
dichlorobromomethane	<1		
trichloroethylene	<1		
dibromochloromethane	<1		
bromoform	<1		
tetrachloroethylene	<1		
Benzene	<5		
Toluene	<5		
Xylenes	<5		
Ethylbenzene	<5		

DO 30776

Blank

	ug/l (ppb)		
methylene chloride	<1		
1,1-dichloroethane	<1		
dichloroethylene	<1		
chloroform	<1		
1,2-dichloroethane	<1		
1,1,1-trichloroethane	<1		
carbon tetrachloride	<1		
dichlorobromomethane	<1		
trichloroethylene	<1		
dibromochloromethane	<1		
bromoform	<1		
tetrachloroethylene	<1		
Benzene	<5		
Toluene	<5		
Xylenes	<5		
Ethylbenzene	<5		

APPENDIX C

INTRODUCTION TO BORING LOGS




The IEPA borings show a good representation of the Recent and Wisconsin age deposits of this area. Recent man made deposits, described on the logs as fill material, were found in ten of the twenty two holes drilled and ranged from one to eleven feet thick. The thickest and major deposit of this type was slag found in the area around the steel factories and Lake Calumet. Other types of fill found included concrete, cinders, bricks and soil fill.

Sediment deposited during the various stages of Lake Chicago is indicated by the sand, silt, and clay deposits on the boring logs. Many of the logs also show a till, which is the material deposited by the Wisconsin age glaciers prior to Lake Chicago.

It is difficult to say what the elevation of the water table was at the time these holes were drilled due to the fact that ground elevations were not surveyed. However, the depth to water encountered in the borings varied from two to ten feet with two holes dry at ten foot completion depth, one at 15 and another at 25. Water depth is indicated on the logs by this ▼ sign.

Samples were obtained with a five foot continuous sampler indicated on the logs by the initials CS. At grid #14 the nature of the material required a change in sampler and at this hole a split spoon sampler was used. This is shown on the boring logs by the initials SS. The samples were removed from the sampler at the site and split lengthwise. A composite sample was then taken from the center of the core. Sampling intervals are indicated on the logs by S_1 , S_2 and S_3 . Sample recovery is the amount of sample actually retained in the sampler.

S0:mks:16/71



Percent grain size	Adjective modifiers for minor grain sizes ^a
>15%	Included in major textural class
10-15%	Some
5-10%	Little
< 5%	Trace

^aOnly applicable to wells bored by the IEPA

Textural triangles (adopted from Shepard, 1954) and terminology used for classification of unconsolidated deposits.



Illinois Environmental Protection Agency

BORING NO. <i>Grid #1</i>		WELL NO. <i>-</i>	GROUNDLEVEL ELEV. <i>-</i>		PAGE <i>1</i> OF <i>2</i>			
COUNTY <i>Cook</i>		SITE NO. <i>-</i>	DATE <i>9/22/83</i>		ANNULUS FILL MATERIAL			
SITE <i>Chicago State University</i>		START TIME <i>10:10A.</i>		FINISH TIME <i>11:30A.</i>				
BORING LOCATION <i>See site sketch</i>		SCREEN		PACKING				
DRILLING EQUIPMENT <i>CME 55 3 1/4 inch I.D. hollow stem auger</i>		SCREEN		PACKING				
COMPLETION DEPTH <i>25 feet</i>		BEDROCK DEPTH <i>-</i>		TOP OF CASING <i>-</i>				
WELL CASING <i>No well installed; backfill with cuttings at completion</i>		TYPE AND QUANTITY		PERSONNEL				
SCREEN INTERVAL		TYPE AND QUANTITY		PERSONNEL				
ELEV	DESCRIPTION	DEPTH	Sample No	Sample Type	Sample Recovery %	Penetration (Strength)	N Value (blows)	REMARKS
	0.0-1.0 Black <u>Silt</u> roots abundant, dry	0	S ₁					No odor and no indication on OVA (organic vapor analyzer).
	1.0-3.0 Black <u>Fill Material</u> cinders, dry	1	S ₂					
		2						
		3						
	3.0-5.0 Brown gray <u>silty Clay</u> till little pebbles (5%) dry	4						No odor and no indication on OVA.
		5						
	5.0-10.0 Gray-brown <u>silty Clay</u> till mottled, trace of pebbles and roots, more gray from 8.0-10.0ft. dry	6	S ₃					
		7						
		8						No odor
		9						
	10.0-15.0 Gray-brown <u>silty Clay</u> till mottled, trace of pebbles, dry	10						
		11						
		12						
		13						
		14						

Illinois Environmental Protection Agency

Boring No.		Well No.	Ground Level Elev.		Page		Of	
County		Site No.	Start	Date	Finish	Annulus Fill Material		
Site			Start	Time	Finish	Above Packing		
Boring Location			Start	Time	Finish	Packing		
Drilling Equipment		Size	Type			Screen		
Completion Depth		Bedrock Depth	Top of Casing					
Well Casing		Type and Quantity		Personnel				
Screen Interval		Type and Quantity		Remarks				
Elev.	Description	Depth	Sample No.	Sample Type	Sample Recovery %	Penetration	Strength	N Value (blows)
		14						
	150-20.0 Gray <u>silty Clay</u> till, dry	15						
		16						
		17						
		18						
		19						
	20.0-25.0 Same as above, dry	20						
		21						
		22						
		23						
		24						
	Boring complete	25						
	Dry hole at completion							
	Samples S ₁ , S ₂ , and S ₃ taken for metals only							



Illinois Environmental Protection Agency

Boring No. <u>Grid #2</u>		Well No. <u>-</u>	Ground Level Elev. <u>-</u>	Page <u>1</u> of <u>2</u>				
County <u>Cook</u>	Site No. <u>-</u>	Start Date <u>9/22/83</u>	Finish Date <u>9/22/83</u>	Above Packing				
Boring Location <u>Olive Harvey College</u>	Drilling Equipment <u>CME 55 3 1/4 inch I.D. hollow stem auger</u>	Start Time <u>8:00 A.</u>	Finish Time <u>9:35 A.</u>	Packing	Screen			
Completion Depth <u>20 feet</u>	Bedrock Depth <u>-</u>	Top of Casing <u>-</u>	Well Casing <u>No well installed; backfilled with cuttings</u>	Personnel				
Screen Interval <u>9-28-83</u>	Type and Quantity <u>-</u>	Samples			Remarks			
Elev.	Description	Depth	Sample No.	Sample Type	Sample Recovery %	Penetration Strength	N Value	Blow Count
	0.0 - 0.9 Black clayey Silt, many roots	0	S ₁					
	0.9 - 4.2 Dark brown silty sandy Fill Material, some pebbles, sand ranging from very fine to fine grain, dry	1	S ₂					
		2			CS 5.0			
		3						
	4.2 - 4.6 Dark gray silty clayey Fill Material trace of pebbles, dry	4						
	4.6 - 5.0 Dark brown silty sand Fill Material, some pebbles, very fine to fine grained sand, dry	5						
	5.0 - 8.8 Sandy silty Fill Material, some pebbles	6	S ₃					
		7			CS 5.0			
		8						
	8.8 - 9.5 Black sandy Silt organic, trace of roots, moist	9						
	9.5 - 10.0 Brown Sand Fine to medium grain, wet	10						
	10.0 - 15.0 Brown-gray clayey Silt till, little pebbles (5%), moist	11						
		12			CS			
		13						
		14						



Boring No.		Well No.		Ground Level Elev.		Page	
County		Site No.		Date		Annulus Fill Material	
Boring Location		Drilling Equipment		Start Time		Above Packing	
Completion Depth		Bedrock Depth		Finish Time		Packing	
Well Casing		Type and Quantity		Screen		Personnel	
Screen Interval		Type and Quantity		Samples		Remarks	
Elev.	Description	Depth	Sample No.	Sample Type	Sample Recovery Ft.	Penetration (lb/ft)	N Value (blows)
		14					
	15.0-20.0 Dark gray silty Clay till, very hard, moist	15					
		16					
		17	CS				
		18					
		19					
	Boring complete	20					
	9-28-83 Groundwater level measured 10.0 feet from surface						
	Water samples for metals and organics taken						
	Samples S ₁ , S ₂ and S ₃ taken for metals only						



Illinois Environmental Protection Agency

BORING NO. <u>Grid #3</u>		WELL NO. <u>-</u>		GROUNDLEVEL ELEV. <u>-</u>		PAGE <u>1</u> OF <u>1</u>	
COUNTY <u>Cook</u>		SITE NO. <u>-</u>		DATE <u>9/28/83</u>		ANNULUS FILL MATERIAL <u>ABOVE PACKING</u>	
SITE <u>Luella Playground School</u>		START TIME <u>9:00A</u>		FINISH TIME <u>10:00A</u>		PACKING	
BORING LOCATION <u>See site sketch</u>		COMPLETION DEPTH <u>15 feet</u>		BEDROCK DEPTH <u>-</u>		SCREEN	
DRILLING EQUIPMENT <u>CME 55 3 1/4 inch I.D. hollow stem augers</u>		WELL CASING <u>No well installed; backfilled with cuttings after sampling.</u>		SAMPLES		PERSONNEL	
SCREEN INTERVAL <u>-</u>		TYPE AND QUANTITY <u>-</u>		Sample No.		Sherry Otto Doug Tolan Ken Bosie	
ELEV.		DESCRIPTION		DEPTH		REMARKS	
			0.0-0.6 Black <u>sandy Silt</u> , roots, dry		0	S ₁	No indication on OVA at bole hole or sample.
			0.6-2.0 Blue <u>Fill Material</u> crystalline, very hard, dry		1	S ₂	
			2.0-3.8 Light brown <u>Sand</u> fine to medium grain, moist		2	CS 38	
					3		
					4		
			5.0-5.7 Same as above		5		No indication on OVA at bore hole or sample.
			5.7-6.4 Gray <u>Sand</u> , medium grain, black streaks along bedding planes		6	S ₃	
			6.4-7.1 Dark gray <u>Clay</u> trace of pebbles		7	CS 30	
			7.1-8.0 Dark gray <u>sandy Silt</u>		8		
					9		
			10.0-15.0 Gray <u>Clay</u> till		10	CS	
					11		
					12		
					13		
					14		
					15		

Boring complete
Groundwater level at completion was 9.7 feet from surface.
Bailed well dry.
Water samples taken for metals and organics.
Samples S₁, S₂, and S₃ Taken for metals only.



Illinois Environmental Protection Agency

BORING NO. <u>Grid #4</u>		WELL NO. <u>-</u>	GROUND LEVEL ELEV. <u>-</u>		PAGE <u>1</u> OF <u>1</u>			
COUNTY <u>Cook</u>	SITE NO. <u>-</u>	DATE <u>9/28/83</u>	FINISH <u>9/28/83</u>	ABOVE PACKING				
SITE <u>Veterans Memorial Park</u>		START <u>10:30A</u>	FINISH <u>11:00A</u>	PACKING				
BORING LOCATION <u>See site sketch</u>		TIME		SCREEN				
DRILLING EQUIPMENT <u>CME 55 3 1/4 inch I.D. hollow stem auger</u>	SIZE <u>10 feet</u>	TYPE <u>-</u>		SCREEN				
COMPLETION DEPTH <u>10 feet</u>	BEDROCK DEPTH <u>-</u>	TOP OF CASING <u>-</u>		SCREEN				
WELL CASING <u>No well installed; backfilled hole with cuttings at completion</u>		TYPE AND QUANTITY		PERSONNEL				
SCREEN INTERVAL <u>-</u>		TYPE AND QUANTITY		PERSONNEL				
ELEV	DESCRIPTION	DEPTH	Sample No	Sample Type	Sample Recovery %	Penetration (Strength)	N Value (Blow)	REMARKS
	0.0-0.5 Black sandy <u>Silt</u> roots	0	S ₁					No indication on OVA at bore hole or sample
	0.5-1.2 Brown with black mottling, <u>Sand</u> , medium grained	1	S ₂					
	1.2-1.5 Black <u>clayey Silt</u>	2						
	1.5-1.7 Gray <u>sandy Clay</u> trace of pebbles	2						
	1.7-2.4 Brown <u>Sand</u> medium grained	3						
	2.4-2.6 Brown <u>Sand</u> coarse to very coarse grained	3						No indication on OVA at bore hole or sample
	2.6-4.0 Brown <u>Sand</u> fine grained, wet	4						
	5.0-6.3 Same as above	5						
	6.3-7.8 Gray <u>Sand</u> fine grained, very wet	6	S ₃					
		7						
		8						
		9						
		10						
	Boring complete							
	Groundwater level was 3.3 feet from surface at completion.							
	Bailed several volumes prior to sampling.							
	Took water samples for metals and organics.							
	Samples S ₁ , S ₂ and S ₃ taken for metals only.							



Illinois Environmental Protection Agency

BORING NO.		WELL NO.		GROUNDLEVEL ELEV.		PAGE		CF	
COUNTY		SITE NO.		DATE		ABOVE PACKING		PACKING	
SITE		COMPLETION DEPTH		START		FINISH		SCREEN	
BORING LOCATION		BEDROCK DEPTH		START		FINISH		SCREEN	
DRILLING EQUIPMENT		TYPE AND QUANTITY		SAMPLE NO.		SAMPLE TYPE		SAMPLE RECOVERY (%)	
WELL CASING		TYPE AND QUANTITY		SAMPLE NO.		SAMPLE TYPE		SAMPLE RECOVERY (%)	
SCREEN INTERVAL		TYPE AND QUANTITY		SAMPLE NO.		SAMPLE TYPE		SAMPLE RECOVERY (%)	
ELEV		DESCRIPTION		DEPTH		SAMPLE NO.		SAMPLE TYPE	
		0.0-0.9 Black <u>Silt</u> roots abundant		0	S ₁				
		0.9-2.7 Light to medium brown <u>Sand</u> medium grained, some orange staining, trace roots		1	S ₂				
				2		CS2.7			
				3					
				4					
		5.0-8.0 Light brown <u>Sand</u> coarse to very coarse, wet		5	S ₃				
				6					
				7		CS5.0			
		8.0-10.0 Gray <u>Sand</u> fine to medium grained, wet		8					
				9					
				10					
		Boring complete							
		Groundwater level was 5.0 from surface at completion.							
		Removed several volumes prior to sampling.							
		Water samples taken for metals and organics.							
		Samples S ₁ , S ₂ , S ₃ taken for metals							



Illinois Environmental Protection Agency

BORING NO. <u>Grid #6</u>		WELL NO. <u>-</u>		GROUNDLEVEL ELEV. <u>-</u>		PAGE <u>1</u> OF <u>1</u>		
COUNTY <u>Cook</u>		SITE NO. <u>-</u>		DATE <u>9/29/83</u> <u>9/29/83</u>		ABOVE PACKING		
SITE <u>Pullman Park</u>		START DATE <u>9/29/83</u>		FINISH DATE <u>9/29/83</u>		PACKING		
BORING LOCATION <u>See site sketch</u>		START TIME <u>7:30 A.</u>		FINISH TIME <u>8:30 A.</u>		SCREEN		
DRILLING EQUIPMENT <u>CME 55</u>		SIZE <u>3 1/4 inch I.D. hollow stem auger</u>		TYPE <u>-</u>		SCREEN		
COMPLETION DEPTH <u>15 ft.</u>		BEDROCK DEPTH <u>-</u>		TOP OF CASING <u>-</u>		SCREEN		
WELL CASING <u>No well installed; backfilled hole with cuttings at completion.</u>		TYPE AND QUANTITY <u>-</u>		SAMPLES		PERSONNEL		
SCREEN INTERVAL <u>-</u>		TYPE AND QUANTITY <u>-</u>		SAMPLES		PERSONNEL		
ELEV.	DESCRIPTION	DEPTH	Sample No.	Sampler Type	Sample Recovery %	Penetration (Strength)	N Value (blows)	REMARKS
	0.0-0.7 Black <u>Silt</u> roots	0	S ₁					No odor and no indication on OVA
	0.7-2.4 <u>Gravelly Fill Material</u> , blue cinders	1	S ₂					
	2.4-2.7 Brown gray <u>Clay</u> , dry	2						
		3						
		4						No odor and no indication on OVA
	5.0-8.6 Brown gray <u>Clay</u> mottled with trace of pebbles, dry	5	S ₃					
		6						
		7						
		8						
	10.0-15.0 Gray <u>Clay</u> , dry	10						
		11						
		12						
		13						Boring complete Dry hole at completion. Samples S ₁ , S ₂ , and S ₃ taken for metals only.
		14						
		15						



Illinois Environmental Protection Agency

BORING NO.		WELL NO.	GROUNDLEVEL ELEV.		PAGE		OF	
COUNTY		SITE NO.	DATE	FINISH	ANNUOUS FILL MATERIAL			
SITE		DATE	FINISH	ABOVE PACKING				
BORING LOCATION		DATE	FINISH	PACKING				
DRILLING EQUIPMENT		DATE	FINISH	SCREEN				
COMPLETION DEPTH		BEDROCK DEPTH	TOP OF CASING	SCREEN				
WELL CASING		TYPE AND QUANTITY		PERSONNEL				
SCREEN INTERVAL		TYPE AND QUANTITY		PERSONNEL				
ELEV.	DESCRIPTION	DEPTH	Sample No	Sample Type	Sample Recovery (%)	Penetration (lb/ft)	N Value (blows)	REMARKS
	0.0 - 0.7 Black <u>sandy Silt</u> trace of pebbles, many roots	0	S ₁					No odor and no indication on OVA at bore hole or sample.
	0.7 - 3.1 Light brown <u>Sand</u> coarse to very coarse grained	1	S ₂					
	3.1 - 3.2 Black <u>silty Sand</u>	2						
	3.2 - 4.0 Light brown <u>Sand</u> medium grain, moist	3	CS4.0					
	5.0 - 10.0 Brown <u>Sand</u> medium grain, some orange staining, some back streaks along bedding planes, moist, wet at 9.0 feet	4						No odor and no indication on OVA at bore hole or sample.
		5	S ₃					
		6						
		7	CS					
		8						
		9						
		10	CS					
		11						
	Boring complete	15						
	Groundwater level was 4.7 feet from surface							
	Bailed several volumes and took water samples for metals and organics.							
	Samples S ₁ , S ₂ and S ₃ were taken for metals only.							



Illinois Environmental Protection Agency

BORING NO. <u>Grid #9</u>		WELL NO. <u>-</u>		GROUNDLEVEL ELEV. <u>-</u>		PAGE <u>1</u> OF <u>1</u>	
COUNTY <u>Cook</u>		SITE NO. <u>-</u>		DATE <u>9/21/83</u>		ABOVE PACKING <u>9/21/83</u>	
SITE <u>Wolfe Playground Park</u>				START TIME <u>8:00A.</u>		FINISH TIME <u>9:00A.</u>	
BORING LOCATION <u>See site sketch</u>				SCREEN		PACKING	
DRILLING EQUIPMENT <u>CME 55 3 1/4 inch I.D. hollow stem auger</u>				SCREEN		PACKING	
COMPLETION DEPTH <u>10 feet</u>		BEDROCK DEPTH <u>-</u>		TOP OF CASING <u>-</u>		SCREEN	
WELL CASING <u>No well installed; backfilled with cuttings after sampling</u>				PERSONNEL <u>Sherry Otto</u> <u>Ken Bosie</u> <u>Erique Gonzalez</u>			
SCREEN INTERVAL <u>sampling</u>				REMARKS			
TYPE AND QUANTITY				REMARKS			
ELEV.				DEPTH			
DESCRIPTION				REMARKS			
0.0 - 0.6 Black <u>Silt</u> roots				S ₁			
0.6 - 1.0 Light brown <u>Sand</u> very fine to fine grain, trace orange staining, trace roots				S ₂			
1.0 - 1.5 Black <u>sandy Silt</u> some roots, moist				CS 2.8			
1.5 - 2.8 Light brown <u>Sand</u> medium to coarse grain (1.7 - 1.9 coarse to very coarse grain) wet				CS 1.0			
5.0 - 7.5 Light brown <u>Sand</u> medium grain				CS 2.0			
7.5 - 10.0 Same as above				Same as above			
Boring complete				Same as above			
Groundwater level was 2.5 feet from surface.				Same as above			
Bailed several volumes and retrieved water samples for metals and organics				Same as above			
Samples S ₁ , S ₂ , and S ₃ taken for metals only.				Same as above			



Illinois Environmental Protection Agency

BORING NO. <u>Grid #10</u>		WELL NO. <u>-</u>	GROUNDLEVEL ELEV. <u>-</u>		PAGE <u>1</u> OF <u>1</u>		
COUNTY <u>Cook</u>		SITE NO. <u>-</u>	DATE <u>9/21/83</u>	FINISH <u>9/21/83</u>	ABOVE PACKING		
SITE <u>Adams Elementary School Playground</u>			START <u>10:00 A.</u>	TIME <u>11:00 A.</u>	FINISH		
BORING LOCATION <u>See site sketch</u>			PACKING				
DRILLING EQUIPMENT <u>CME 55 3 1/4 inch I.D. hollow stem auger</u>			SCREEN				
COMPLETION DEPTH <u>15 feet</u>			SCREEN				
WELL CASING <u>No well installed; backfilled with cuttings after sampling</u>			PERSONNEL				
SCREEN INTERVAL <u>-</u>			REMARKS				
ELEV	DESCRIPTION	DEPTH	Sample No.	Sample Type	Sample Recovery (%)	Penetration (lb/inch)	N Value (blows/ft)
	0.0-0.4 <u>Black clayey Silt, roots abundant</u>	0	S ₁				
	0.4-2.5 <u>Sandy gravelly Fill Material with chunk of concrete @ 2.5 feet</u>	1	S ₂	CS 2.5			
	2.5-5.0 <u>Fill Material</u>	2					
		3		CS 0.5			
	5.0-6.0 <u>Fill Material</u>	4					
	6.0-10.0 <u>Light brown Sand medium to coarse grain, some pebbles, wet</u>	5	S ₃				
		6		CS 3.2			
		7					
		8					
		9					
	10.0-15.0 <u>Augered through for water sampling.</u>	10					
		11					
		12					
		13					
		14					
		15					
	<u>Boring complete</u> <u>Groundwater level at completion was 6.5 feet from surface.</u> <u>Removed several volumes prior to sampling.</u> <u>Water samples taken for metals and organics.</u> <u>Samples S₁, S₂, and S₃ Taken for metals only.</u>						



Illinois Environmental Protection Agency

BORING NO. <i>Grid #12</i>		WELL NO. <i>-</i>	GROUNDLEVEL ELEV. <i>-</i>		PAGE <i>1</i> OF <i>1</i>			
COUNTY <i>Cook</i>	SITE NO. <i>-</i>	START DATE <i>9/27/83</i>	FINISH DATE <i>9/27/83</i>	ANNULUS FILL MATERIAL				
SITE <i>Chicago Port District</i>		TIME <i>10:10 A. 12:00</i>		ABOVE PACKING				
BORING LOCATION <i>See site sketch</i>		SCREEN		PACKING				
DRILLING EQUIPMENT <i>CME 55 3 1/4 inch I.D. hollow stem auger</i>		SCREEN		SCREEN				
COMPLETION DEPTH <i>10.5 Feet</i>	BEDROCK DEPTH <i>-</i>	TOP OF CASING <i>-</i>		SCREEN				
WELL CASING <i>No well installed; backfilled hole with cuttings after sampling.</i>		TYPE AND QUANTITY		PERSONNEL				
SCREEN INTERVAL		TYPE AND QUANTITY		PERSONNEL				
ELEV	DESCRIPTION	DEPTH	Sample No	Sample Type	Sample Recovery %	Penetration (lb/ft)	N Value (blows)	REMARKS
	0.0-5.0 <i>Slag Fill Material (very difficult to drill)</i>	0						OVA at bore hole 80-90 ppm.
		1						
		2						
		3						Could not use SS or CS because of the type of fill material.
		4						
	5.0-10.5 <i>Same as above</i>	5						No sediment samples taken.
		6						
		7						
		8						
		9						
		10						
	<i>Boring complete</i>							
	<i>Groundwater level at completion was 8.5 Feet from surface.</i>							
	<i>Bailed well dry; later that day took water samples for metals and organics.</i>							



BORING NO.	WELL NO.	GROUNDELEV. ELEV.	PAGE	OF
Grid #14	-	-	1	1
COUNTY Cook	SITE NO. -	DATE START FINISH	ABOVE PACKING	
SITE Republic Steel		9/27/83 9/27/83		
BOHNG LOCATION See site sketch		START TIME FINISH	PACKING	
DILLING EQUIPMENT CME 55 3 1/4 inch I.D. hollow stem auger		8:00A. 9:30A.		
COMPLETION DEPTH 9.5	BEDROCK DEPTH -	TOP OF CASING -	SCREEN	
WELL CASING No well installed; backfilled with cuttings after sampling.	TYPE AND QUANTITY	SAMPLES		
SCREEN INTERVAL	TYPE AND QUANTITY	Sample No	Sample Type	Sample Recovery %
ELEV.	DESCRIPTION	DEPTH	Penetration Strained	N Value (Blow)
				REMARKS
	0.0-2.5 Black Slag Fill Material	0	S ₁	OVA reading at bore hole was 40-60ppm No reading on the sample.
	2.5-5.0 Augered through slag	1	CS 20	
		2		
		3		OVA reading at bore hole was 100 ppm.
		4		
	5.0-5.2 Black Sand medium to coarse grain, wet	5		
	5.2-6.5 Light gray Sand medium grain, wet	6	S ₂ SS 1.5	11/15 OVA reading of 10 ppm of sand sample.
	6.5-8.0 Light gray to brown Sand medium grain, wet	7	SS 1.5	10/13 5ppm. OVA reading at bore hole. (S ₃ For metals only)
	8.0-8.8 Light gray Sand medium to coarse grain	8	S ₃	
	8.8-9.5 Light gray Sand fine to medium grain	9	SS 1.5	8/10 No reading on OVA (S ₃ For metals only)
	Boring complete	10		
	Groundwater level upon completion was 1.5 feet from surface.			
	Removed several volumes prior to sampling.			
	Water samples taken for metals and organics.			
	Samples S ₁ , S ₂ , S ₃ taken for metals			
	S ₂ taken for organics			



Illinois Environmental Protection Agency

BORING NO. <u>Grid #15</u>		WELL NO. <u>-</u>	GROUNDLEVEL ELEV. <u>-</u>		PAGE <u>1</u> OF <u>1</u>			
COUNTY <u>Cook</u>	SITE NO. <u>-</u>	START DATE <u>9/14/83</u>	FINISH DATE <u>9/14/83</u>	ANNUOUS FILL MATERIAL ABOVE PACKING				
SITE <u>Wolf Lake Conservation Area</u>		START TIME <u>2:30P.</u>	FINISH TIME <u>3:30P.</u>	PACKING				
BORING LOCATION <u>See site sketch</u>				SCREEN				
DRILLING EQUIPMENT <u>CME 55</u>	SIZE <u>3 1/4 inch I.D. hollow stem auger</u>							
COMPLETION DEPTH <u>10 feet</u>	BEDROCK DEPTH <u>-</u>	TOP OF CASING <u>-</u>						
WELL CASING <u>No well installed; backfilled with cuttings at completion.</u>		TYPE AND QUANTITY		PERSONNEL				
SCREEN INTERVAL <u>-</u>		TYPE AND QUANTITY						
ELEV	DESCRIPTION	DEPTH	Sample No	Sample Type	Sample Recovery Ft	Penetration (lb/ft)	in Value (lb/ft)	REMARKS
	0.0-0.4 Black <u>Silt</u> , some roots, dry	0	S ₁	CS				No odor; OVA not operative
	0.4-1.5 Augered through, no sample	1						
	1.5-3.8 Fill Material black foundary sand and gravel, dry	2						No odor
		3	S ₂	CS	23			
		4						
	5.0-8.5 Same as above	5						No odor
		6	S ₃	CS				
		7						
		8						
	8.5-10.0 Augered through; no sample	9						
		10						
	Boring complete Dry hole at completion. No water samples taken. Samples S ₁ and S ₂ taken for metals and organics. Sample S ₃ taken for metals only.							



Illinois Environmental Protection Agency

BORING NO.		WELL NO.		GROUND LEVEL ELEV.		PAGE		
COUNTY		SITE NO.		DATE		ANNUAL FILL MATERIAL		
SITE		START		FINISH		ABOVE PACKING		
BORING LOCATION		START		FINISH		PACKING		
DRILLING EQUIPMENT		START		FINISH		SCREEN		
COMPLETION DEPTH		BEDROCK DEPTH		TOP OF CASING		PERSONNEL		
WELL CASING		TYPE AND QUANTITY		SAMPLES		PERSONNEL		
SCREEN INTERVAL		TYPE AND QUANTITY		SAMPLES		PERSONNEL		
ELEV.	DESCRIPTION	DEPTH	Sample No.	Sample Type	Sample Recovery (%)	Sample Orientation (S/N)	N Value (Blow)	REMARKS
	0.0-0.6 Black <u>clayey Silt</u>	0	S ₁					OVA reading at bore hole is 30-40 ppm No indication on sample.
	0.6-5.0 <u>Fill Material</u> , <u>dema</u> , bricks, glass from 3.0ft. to 5.0ft. with clay mixed through-out, dry	1	S ₂					
		2						
		3						
	5.0-7.7 Dark brown gray <u>silty Sand</u> Fine to medium grain, shell fragments, trace roots, moist	5						No indication with OVA
		6	S ₃					
		7						
	7.7-9.2 Light gray <u>Clay</u> with orange yellow staining, trace roots, moist	8						Encountered water at 20feet.
		9						
	10.0-27.5 Gray <u>Clay</u> hard	10						Encountered water at 20feet.
		11						
	Boring complete	12						Encountered water at 20feet.
	Groundwater level at completion was 20feet from surface.	13						
	9-28-83 groundwater level was 4.5feet from surface.	14						Encountered water at 20feet.
	Water samples taken for metals and organics.	15						
	Samples S ₁ , S ₂ and S ₃ taken for metals.	16						Encountered water at 20feet.
		17						
		18						Encountered water at 20feet.
		19						
		20						Encountered water at 20feet.
		21						
		22						Encountered water at 20feet.
		23						
		24						Encountered water at 20feet.
		25						
		26						Encountered water at 20feet.
		27						
		28						Encountered water at 20feet.
		29						
		30						Encountered water at 20feet.
		31						
		32						Encountered water at 20feet.
		33						
		34						Encountered water at 20feet.
		35						
		36						Encountered water at 20feet.
		37						
		38						Encountered water at 20feet.
		39						
		40						Encountered water at 20feet.
		41						
		42						Encountered water at 20feet.
		43						
		44						Encountered water at 20feet.
		45						
		46						Encountered water at 20feet.
		47						
		48						Encountered water at 20feet.
		49						
		50						Encountered water at 20feet.
		51						
		52						Encountered water at 20feet.
		53						
		54						Encountered water at 20feet.
		55						
		56						Encountered water at 20feet.
		57						
		58						Encountered water at 20feet.
		59						
		60						Encountered water at 20feet.
		61						
		62						Encountered water at 20feet.
		63						
		64						Encountered water at 20feet.
		65						
		66						Encountered water at 20feet.
		67						
		68						Encountered water at 20feet.
		69						
		70						Encountered water at 20feet.
		71						
		72						Encountered water at 20feet.
		73						
		74						Encountered water at 20feet.
		75						
		76						Encountered water at 20feet.
		77						
		78						Encountered water at 20feet.
		79						
		80						Encountered water at 20feet.
		81						
		82						Encountered water at 20feet.
		83						
		84						Encountered water at 20feet.
		85						
		86						Encountered water at 20feet.
		87						
		88						Encountered water at 20feet.
		89						
		90						Encountered water at 20feet.
		91						
		92						Encountered water at 20feet.
		93						
		94						Encountered water at 20feet.
		95						
		96						Encountered water at 20feet.
		97						
		98						Encountered water at 20feet.
		99						
		100						Encountered water at 20feet.
		101						
		102						Encountered water at 20feet.
		103						
		104						Encountered water at 20feet.
		105						
		106						Encountered water at 20feet.
		107						
		108						Encountered water at 20feet.
		109						
		110						Encountered water at 20feet.
		111						
		112						Encountered water at 20feet.
		113						
		114						Encountered water at 20feet.
		115						
		116						Encountered water at 20feet.
		117						
		118						Encountered water at 20feet.
		119						
		120						Encountered water at 20feet.
		121						
		122						Encountered water at 20feet.
		123						
		124						Encountered water at 20feet.
		125						
		126						Encountered water at 20feet.
		127						
		128						Encountered water at 20feet.
		129						
		130						Encountered water at 20feet.
		131						
		132						Encountered water at 20feet.
		133						
		134						Encountered water at 20feet.
		135						
		136						Encountered water at 20feet.
		137						
		138						Encountered water at 20feet.
		139						
		140						Encountered water at 20feet.
		141						
		142						Encountered water at 20feet.
		143						
		144						Encountered water at 20feet.
		145						
		146						Encountered water at 20feet.
		147						
		148						Encountered water at 20feet.
		149						
		150						Encountered water at 20feet.
		151						
		152						Encountered water at 20feet.
		153						
		154						Encountered water at 20feet.
		155						
		156						Encountered water at 20feet.
		157						
		158						Encountered water at 20feet.
		159						
		160						Encountered water at 20feet.
		161						
		162						Encountered water at 20feet.
		163						
		164						Encountered water at 20feet.
		165						
		166						Encountered water at 20feet.
		167						
		168						Encountered water at 20feet.
		169						
		170						Encountered water at 20feet.
		171						
		172						Encountered water at 20feet.
		173						
		174						Encountered water at 20feet.
		175						
		176						Encountered water at 20feet.
		177						
		178						Encountered water at 20feet.
		179						
		180						Encountered water at 20feet.
		181						
		182						Encountered water at 20feet.
		183						
		184						Encountered water at 20feet.
		185						
		186						Encountered water at 20feet.
		187						
		188						Encountered water at 20feet.
		189						
		190						Encountered water at 20feet.
		191						
		192						Encountered water at 20feet.
		193						
		194						Encountered water at 20feet.
		195						
		196						Encountered water at 20feet.
		197						
		198						Encountered water at 20feet.
		199						
		200						Encountered water at 20feet.
		201						
		202						Encountered water at 20feet.
		203						
		204						Encountered water at 20feet.
		205						
		206						Encountered water at 20feet.
		207						
		208						Encountered water at 20feet.
		209						
		210						Encountered water at 20feet.
		211						
		212						Encountered water at 20feet.
		213						
		214						Encountered water at 20feet.
		215						
		216						Encountered water at 20feet.
		217						
		218						Encountered water at 20feet.
		219						
		220						Encountered water at 20feet.
		221						
		222						Encountered water at 20feet.
		223						
		224						Encountered water at 20feet.
		225						
		226						Encountered water at 20feet.
		227						
		228						Encountered water at 20feet.
		229						
		230						Encountered water at 20feet.
		231						
		232						Encountered water at 20feet.
		233						
		234						Encountered water at 20feet.
		235						
		236						Encountered water at 20feet.
		237						
		238						Encountered water at 20feet.
		239						
	</							



Illinois Environmental Protection Agency

BORING NO. <u>Grid #17</u>		WELL NO. <u>-</u>		GROUNDLEVEL ELEV. <u>-</u>		PAGE <u>1</u> OF <u>1</u>	
COUNTY <u>Cook</u>		SITE NO. <u>-</u>		DATE <u>9/26/83</u>		FRESH <u>9/26/83</u>	
SITE <u>Beaubien Forest Preserve</u>				START		ABOVE PACKING	
BORING LOCATION <u>See site sketch</u>				TIME <u>3:30P.</u>		FRESH <u>5:00P.</u>	
DRILLING EQUIPMENT <u>CME 55 3/4 inch T.D. hollow stem auger</u>				SCREEN		PACKING	
COMPLETION DEPTH <u>10 feet</u>				BEDROCK DEPTH <u>-</u>		TOP OF CASING <u>-</u>	
WELL CASING <u>No well installed; backfilled well with cuttings after sampling.</u>				PERSONNEL			
SCREEN INTERVAL <u>-</u>				REMARKS			
ELEV	DESCRIPTION	DEPTH	Sample No	Sample Type	Sample Recovery %	Penetration (Strength)	N Value (blows)
	0.0-0.6 Black <u>silty Sand</u> , roots abundant	0	S ₁				
	0.6-1.5 Brown <u>Sand</u> medium to very coarse grain, some roots	1	S ₂				
	1.5-2.8 Brown <u>gravelly Sand</u> medium to coarse grain sand, pebbles range in size from 5-40 mm., subangular to angular, trace roots	2					
		3					
		4					
	5.0-6.0 Brown <u>Sand</u> medium to very coarse grain, gravelly zone at 5.4 5.5 pebbles range in size of 5 to 20 mm, wet	5					
	6.0-7.0 Brown <u>sandy Gravel</u> , 0 to 5 mm in size, trace shell fragments, angular, wet	6	S ₃				
	7.0-7.2 Brown <u>Sand</u> very fine to fine grain shells unbroken), wet	7					
	7.2-8.3 Gray <u>silty Sand</u> very fine grain, trace roots, trace shell fragments	8					
		9					
		10					
	Boring complete Groundwater level at completion was 6.8 feet from surface. Bailed well dry even though good recharge. Water samples taken for metals and organics. Samples S ₁ , S ₂ , and S ₃ taken for metals.						



Illinois Environmental Protection Agency

BORING NO. <u>Grid #18</u>		WELL NO. <u>-</u>	GROUND LEVEL ELEV. <u>-</u>		PAGE <u>1</u> OF <u>1</u>			
COUNTY <u>Cook</u>		SITE NO. <u>-</u>	DATE <u>9/27/83</u>	FINISH <u>9/27/83</u>	ANNUAL FILL MATERIAL			
SITE <u>Thomas J. O'Brien Lock and Dam</u>			START <u>4:30P.</u>	FINISH <u>5:45P.</u>	ABOVE PACKING			
BORING LOCATION <u>See site sketch</u>					PACKING			
DRILLING EQUIPMENT <u>CME 55 3 1/4 inch I.D. hollow stem auger</u>					SCREEN			
COMPLETION DEPTH <u>15 feet</u>								
WELL CASING <u>No well installed; backfilled hole with cuttings after sampling.</u>			SAMPLES			PERSONNEL		
SCREEN INTERVAL <u>-</u>						<u>Sherry Otto</u> <u>Ken Bosie</u> <u>Enrique Gonzalez</u>		
ELEV.	DESCRIPTION	DEPTH	Sample No	Sample Type	Sample Recovery %	Penetration (Strength)	N Value (Blow)	REMARKS
	0.0-1.5 Black <u>gravelly silty Fill Material</u>	0	S ₁					No indication on OVA at bore hole or sample
	1.5-4.8 Gray <u>silty Clay</u> , trace pebbles, trace roots, brown sand (medium grain) Filling Fractures	1	S ₂					
		2			CS 50			
	4.8-5.0 Black <u>silty Sand</u> Fine to medium grain, Trace roots, moist	5						Same as above
	5.0-5.8 Same as above	6	S ₃					
	5.8-7.7 Black <u>Silt</u> some roots, moist	7			CS 4.2			
	7.7-8.0 Dark gray <u>Clay</u> , wet	8						
	8.0-10.0 Light gray <u>Sand</u> medium grain, trace roots, trace yellow staining, wet	9						
	10.0-15.0 Gray brown <u>Sand</u> medium grain, wet	10			CS			
	Boring complete Groundwater level at completion was 5.4 feet from surface Bailed several volumes prior to sampling. Water samples Taken for metals and organics. Samples S ₁ , S ₂ , and S ₃ Taken for metals.	15						





Illinois Environmental Protection Agency

BORING NO. <u>Grid #20</u>		WELL NO. <u>-</u>		GROUNDLEVEL ELEV. <u>-</u>		PAGE <u>1</u> OF <u>1</u>			
COUNTY <u>Cook</u>		SITE NO. <u>-</u>		DATE <u>9/20/83</u> <u>9/20/83</u>		ANNULUS FILL MATERIAL <u>ABOVE PACKING</u>			
SITE <u>South portion of Wolfe Lake Conservation Area</u>				START TIME <u>11:00A.</u> <u>12:00A.</u>		PACKING <u>---</u>			
BORING LOCATION <u>See site sketch</u>				FINISH TIME <u>---</u>		SCREEN <u>---</u>			
DRILLING EQUIPMENT <u>CME 55 3 1/4 inch I.D. hollow stem auger</u>		SIZE <u>---</u> TYPE <u>---</u>		START TIME <u>---</u>		FINISH TIME <u>---</u>			
COMPLETION DEPTH <u>10 feet</u>		BEDROCK DEPTH <u>---</u>		TOP OF CASING <u>---</u>		SCREEN <u>---</u>			
WELL CASING <u>No well installed; backfilled with cuttings after sampling.</u>				PERSONNEL <u>Sherry Otto</u> <u>Ken Basie</u> <u>Enrique Gonzalez</u>					
SCREEN INTERVAL <u>---</u> TYPE AND QUANTITY <u>---</u>				SAMPLES					
				Sample No.	Sample Type	Sample Recovery (%)	Penetration (lb/ft)	N Value (blows)	
ELEV.				DEPTH				REMARKS	
0.0-0.7 Dark brown <u>Sand</u> medium grain, some pebbles, trace orange staining, roots				0	S ₁				Raining, OVA not used; no odor
0.7-0.8 Black <u>Organic Material</u> , wood chips and roots				1	S ₂				
0.8-3.9 Dark gray <u>Sand</u> fine to medium grain, trace black staining, moist				2		CS 3.9			
				3					
				4					
5.0-5.7 Black <u>Organic Material</u>				5					Same as above
5.7-6.8 Gray <u>Sand</u> fine to medium grain, some roots, wet				6	S ₃	CS 1.8			
				7					
7.5-10.0 Gray <u>Sand</u> fine to medium grain, wet				8					Same as above
				9		CS 2.5			
				10					
Boring complete Groundwater level at completion was 1.9 feet from surface. Bailed several volumes. Water samples were taken for metals and organics. Samples S ₁ , S ₂ , and S ₃ were take for metals.									



Illinois Environmental Protection Agency

BORING NO. <u>Grid #21</u>		WELL NO. <u>-</u>		GROUNDLEVEL ELEV. <u>-</u>		PAGE <u>1</u> OF <u>1</u>	
COUNTY <u>Cook</u>		SITE NO. <u>-</u>		DATE <u>9/13/83</u>		FRESH <u>9/13/83</u>	
SITE <u>Lincoln Avenue Grade School</u>		START <u>2:00P</u>		FINISH <u>3:30P</u>		ABOVE PACKING	
BORING LOCATION <u>See site sketch</u>		TIME <u>2:00P</u>		FINISH <u>3:30P</u>		PACKING	
DRILLING EQUIPMENT <u>CME 55 3 1/4 inch I.D. hollow stem auger</u>		START <u>2:00P</u>		FINISH <u>3:30P</u>		SCREEN	
COMPLETION DEPTH <u>10 feet</u>		BEDROCK DEPTH <u>-</u>		TOP OF CASING <u>-</u>		SCREEN	
WELL CASING <u>No well installed; backfilled hole with cuttings at completion.</u>		TYPE AND QUANTITY <u>-</u>		SAMPLES		PERSONNEL	
SCREEN INTERVAL <u>-</u>		TYPE AND QUANTITY <u>-</u>		SAMPLE NO.		PERSONNEL	
ELEV.		DESCRIPTION		DEPTH		REMARKS	
		0.0-0.4 Black <u>silty Gravel</u> , many roots		0		No odor detected, OVA not operative	
		0.4-2.0 Light brown <u>Sand</u> very fine to fine grain, trace roots, red orange staining at 1.6 ft. - 1.7 ft., dry		1			
				2			
				3			
				4			
		5.0-5.3 Light brown <u>Sand</u> very fine to fine grain, dry		5		Same as above	
		5.3-6.5 Dark brown to black <u>Sand</u> , fine to medium grain, some pebbles, some roots, dry		6			
		6.5-6.7 large tree root		7			
		6.7-7.5 Light brown <u>Sand</u> fine to medium grain, red orange staining, some roots, moist		8			
				9			
				10			
		Boring complete					
		Dry hole at completion.					
		No water samples taken.					
		Samples S ₁ , S ₂ , and S ₃ taken for metals only.					



Illinois Environmental Protection Agency

BORING NO. <u>Grid #22</u>		WELL NO. <u>-</u>	GROUNDLEVEL ELEV. <u>-</u>		PAGE <u>1</u> OF <u>1</u>	
COUNTY <u>Cook</u>		SITE NO. <u>-</u>	DATE <u>9/13/83</u>		FRESH <u>9/13/83</u>	
SITE <u>John W. Needles Park</u>		START <u>9/13/83</u>		ABOVE PACKING		
BORING LOCATION <u>See site sketch</u>		TIME <u>9:00A. 10:30A.</u>		PACKING		
DRILLING EQUIPMENT <u>CME 55 3 1/4 inch I.D. hollow stem auger</u>		START <u>9:00A.</u>		FRESH <u>10:30A.</u>		
COMPLETION DEPTH <u>10 feet</u>		BEDROCK DEPTH <u>-</u>		SCREEN		
WELL CASING <u>No well installed; backfilled hole with cuttings after sampling</u>		TYPE AND QUANTITY		PERSONNEL		
SCREEN INTERVAL		TYPE AND QUANTITY		PERSONNEL		
ELEV.	DESCRIPTION	DEPTH	Sample No	Sample Type	Sample Recovery %	Remarks
	0.0-0.8 Black silt <u>Sand</u> , roots, fine to medium grain	0	S ₁			No odor and no indication on OVA
	0.8-1.7 Brown <u>Sand</u> red orange stains throughout, fine to medium grain, dry	1	S ₂			
	1.7-3.2 Gray light brown <u>Sand</u> , fine to medium grain, from 2.5 ft. - 2.6 ft. a coarse to very coarse sand, dry	2				
	3.2-3.4 Orange stained <u>Sand</u> fine to medium grain, dry	3				
	3.4-3.9 Gray <u>Sand</u> fine to coarse grain with trace pebbles, dry	4				
	5.0-5.4 Gray <u>Clay</u> , dry	5				Same as above
	5.4-5.6 Gray <u>Sand</u> very fine grain, dry	6	S ₃			
	5.6-10.0 Gray <u>Clay</u> thin bedded, varied with beds of light and dark gray clay, moist	7				
		8				
		9				
		10				
	Boring complete					
	Groundwater level at completion was 8.6 feet from surface.					
	Bailed well dry.					
	9-14-83 groundwater level was 8.6 feet from surface.					
	Water samples were taken for metals and organics.					
	Samples S ₁ , S ₂ , and S ₃ were taken for metals.					



BORING NO.		WELL NO.		GROUNDLEVEL ELEV.		PAGE	
COUNTY		SITE NO.		DATE		APPROX. FILL MATERIAL	
SITE		START		FINISH		ABOVE PACKING	
BORING LOCATION		START		FINISH		PACKING	
DRILLING EQUIPMENT		START		FINISH		SCREEN	
COMPLETION DEPTH		BEDROCK DEPTH		TOP OF CASING			
WELL CASING		TYPE AND QUANTITY		SAMPLES		PERSONNEL	
SCREEN INTERVAL		TYPE AND QUANTITY					
ELEV.	DESCRIPTION	DEPTH	Sample No.	Sample Type	Sample Recovery (%)	Penetration (Blows)	W Value (Blows)
		0	S ₁				
		1	S ₂				
		2		CS50			
		3					
		4					
		5					
		6	S ₃				
		7		CS50			
		8					
		9					
		10					
Boring complete							
Groundwater level at completion was 8.9 feet from surface.							
Unable to obtain enough water for samples.							
Samples S ₁ and S ₂ taken for metals and organics.							
Sample S ₃ taken for metals only.							



Illinois Environmental Protection Agency

BORING NO. <u>Grid #24</u>		WELL NO. <u>-</u>		GROUNDLEVEL ELEV. <u>-</u>		PAGE <u>1</u> OF <u>1</u>	
COUNTY <u>Cook</u>		SITE NO. <u>-</u>		DATE <u>9/14/83</u>		FRESH <u>9/14/83</u>	
SITE <u>Burnham Park</u>				ABOVE PACKING			
BORING LOCATION <u>See site sketch</u>				PACKING			
DRILLING EQUIPMENT <u>CME 55 3 1/4 inch I.D. hollow stem auger</u>				START TIME <u>10:00A.</u>		FRESH <u>11:00A.</u>	
COMPLETION DEPTH <u>10 feet</u>		BEDROCK DEPTH <u>-</u>		TOP OF CASING <u>-</u>		SCREEN	
WELL CASING <u>No well installed; backfilled with cuttings after sampling</u>		TYPE AND QUANTITY		SAMPLES			
SCREEN INTERVAL <u>-</u>		TYPE AND QUANTITY		PERSONNEL			
ELEV		DESCRIPTION		DEPTH			
				Sample No. Sample Type Sample Recovery Ft. Penetration (lb/ft) N Value (lb/ft) Blows			
				REMARKS			
		0.0-0.2 Asphalt and roots		0 S ₁			
		0.2-2.0 Black silty Sand, trace roots, moist		1 S ₂			
		2.0-4.0 Light brown Sand Fine to coarse grain, wet		2 CS4.0			
				3			
				4			
		5.0-6.8 Same as above		5			
				6 S ₃			
				7 CS1.8			
				8			
				9			
				10			
		Boring complete					
		Groundwater level at completion was 4.1 Feet from surface.					
		Water samples taken for metals and organics.					
		Samples S ₁ and S ₂ taken for metals and organics.					
		Sample S ₃ taken for metals only.					



Illinois Environmental Protection Agency

BIRING NO. <u>Grid # 25</u>		WELL NO. <u>-</u>		GROUNDLEVEL ELEV. <u>-</u>		PAGE <u>1</u> OF <u>1</u>	
SITE <u>Cook</u>		DATE <u>9/28/83</u>		FINISH <u>9/28/83</u>		ABOVE PACKING	
BORING LOCATION <u>Bulliam Woods Golf Course</u>		START TIME <u>1:30P.</u>		FINISH TIME <u>3:00P.</u>		PACKING	
DRILLING EQUIPMENT <u>See site sketch</u>		SIZE <u>55 3/4 inch</u>		TYPE <u>I.D. hollow stem auger</u>		SCREEN	
COMPLETION DEPTH <u>15</u>		BEDROCK DEPTH <u>-</u>		TOP OF CASING <u>-</u>			
WELL CASING <u>No well installed; backfilled hole with cuttings after sampling.</u>		TYPE AND QUANTITY		SAMPLES		PERSONNEL	
SCREEN INTERVAL <u>-</u>		TYPE AND QUANTITY				PERSONNEL	
ELEV	DESCRIPTION	DEPTH	Sample No	Sample Type	Sample Recovery Ft	Penetration (lb/inch)	Remarks
	0.0 - 0.4 Black <u>clayey Silt</u> , roots	0	S ₁				No indication on OVA at bore hole or sample.
	0.4 - 2.7 Brown <u>Sand</u> medium grain, dry	1	S ₂				
		2			CS27		
		3					
	5.0 - 7.5 Same as above	5					No detection on OVA.
		6	S ₃	CS25			
	7.5 - 10.0 Same as above	8					No detection on OVA.
		9		CS20			
	10.0 - 15.0 Same as above	10					Lost shoe of continuous sampler down hole on last sample.
		11		CS			
	Boring complete	15					
	Groundwater level at completion was 6.2 feet from surface.						
	Water samples were taken for metals and organics.						
	Samples S ₁ , S ₂ , and S ₃ were taken for metals only.						

APPENDIX D

ATTACHMENT 3

DATE	DIS- CHARGE (CPS)			SULFATE (500) (MG/L)	RDAS (MG/L)	TU-810- ITI UNITS
671002						91
670927						55
670912						7
670907	20.0	7.5	0.004	9.10		18
670829	21.1	7.4	0.002	6.23		10
670801	22.2	7.4		2.00		10
670727	21.7	7.5		1.43		5
670710	20.6	7.4	0.003	5.40		3
670628	18.9	7.3	0.004	3.50		45
670623	20.6	7.2	0.005	12.00		16
670613	21.1	7.3	0.000	5.50		65
670606	17.8	7.4	0.001	7.33		18
670602	16.7	7.4	0.002	6.00		8
670525	15.6	7.3	0.004	6.00		20
670516	13.3	7.4	0.002	0.73		2
670509	15.6	8.5	0.000	0.30		30
670502	11.1	7.5	0.002	3.13		12
670425	11.1	7.4	0.002	0.40		16
670418	11.1	7.7	0.003	0.40		25
670411	7.8	7.6	0.004	3.50		25
670403	12.2	7.6	0.001	6.50		24
670328	11.7	7.5	0.003	2.23		9
670321	6.7	7.5	0.001	2.70		18
670314	8.9	7.6	0.003	6.00		32
670307	3.3	7.5	0.007	7.00		37
670227	3.3	7.5	0.005	5.00		63
670221	4.4	7.5	0.008	5.30		31
670214	10.0	7.4	0.008	10.40		55
670128	12.2	6.9	0.007	7.00		8
670117	3.3	7.2	0.009	5.00		42
670110	10.0	7.3	0.020	9.60		137

MA 03 GRAND CALUMET RIVER
FOURTH AVENUE --CONTINUED

DATE	UOW (%L)	S DAT (%L)	COD (%L)	SOL- SOLIDS	CADRIUM	HLX CHROM- IUM	TRI CHROM- IUM	LOPPER (%L)	CYANIDE (%L)	TOTAL	LEAD (%L)	ZINC (%L)	FLOW- IUE	NARO- HESS (CACO3)	ALFA- LILITY (CACU3)
				(%L)	(%L)	(%L)	(%L)			(%L)			(%L)	(%L)	(%L)
710105									0.060						
690427					0.000					0.0	3.30		3.3		
690419					0.000					0.0	0.30		0.0		
690411					0.000					0.0	0.00		0.0		
690806					0.000					0.0	3.39		3.3		
690730					0.330					0.0	0.00		0.0		
690725					0.000					0.0	0.00		3.3		
690716					0.000					0.0	0.00		0.0		
690711					0.000					0.0	0.00		0.0		
690325									3.230						

AAA 01 CALUMET RIVER
113TH STREET BRIDGE SOUTH OF LAKE CALUMET
LAB: CHICAGO

DATE	DIS-CHARGE (CPS)	TEMP-ERA-TURE DEG C	DIS-SOLVED OILS (MG/L)	PH UNITS	TOTAL PHOS-PHOBUS (MG/L)	PHENOLS (MG/L)	FORMAL-DEHYDRAL (MG/L)	AMMONIA-NITRO-GEN (MG/L)	NITRATE-NITRITE (MG/L)	SPEC-IFIC COND UMHOS	CHLOR-IDE (MG/L)	SULFATE (SO4) (MG/L)	ANAS (MG/L)	TDSID-ITY UNITS
740426		14.4	7.1	8.2	0.040	0.000	100	0.07	1.2	450				0.20
740715		26.1	6.4	7.4	0.203	2.133	1133	3.44	1.3	447				3.10
740627		22.2	7.1	7.9	0.100	0.000	103	0.60	1.8	617	75	70		0.46
740524		19.4	6.2	8.3	0.260	0.000	100	0.75	1.7	750				0.20
740419		15.0	6.5	7.8	0.363	2.300	133	3.33	1.9	413	122	120		0.50
740315		8.3	4.8	7.9	0.070	0.000	100	1.80	1.7	950				0.40
740219		7.2	13.7	7.9	3.023	3.333	33	1.53	1.4	833				3.43
740116		0.0	10.7	7.7	0.063	0.005	10	1.20	2.0		120	105		0.50

WAS 01 CALUMET RIVER
130TH STREET BRIDGE SOUTH OF LAKE CALUMET - CONTINUED

DATE	DIS- CHARGE (CFS)	TEMP- FAR- TUBE (F)	DIS- SOLVED OXYGEN (MG/L)	PH	TOTAL PHOS- PHORUS (MG/L)	AMMONIA NITRO- GEN (MG/L)	AMMONIA NITRATE (MG/L)	SPECI- FIC CONC (MG/L)	CHLOR- IDE (MG/L)	SULFATE (MG/L)	HAZ- ARDS (MG/L)	TURBID- ITY UNITS
711121	20.0	6.9	6.1	7.9	3.110	3.331	200	0.14	1.7	663		3.41
711017	20.0	6.9	7.0	8.0	0.000	0.000	100	0.12	1.6	567		3.20
710919	20.0	6.9	6.2	8.0	0.000	0.000	100	0.12	1.2	500	95	0.70
710823	25.6	5.7	6.2	8.2	3.361	3.331	213	3.28	1.3	667		0.70
710709	25.6	5.6	6.1	8.1	0.000	0.000	200	0.51	0.5	431		3.60
710626	22.2	6.2	7.4	7.7	3.333	3.333	273	0.63	3.8	667	61	0.80
710510	20.0	6.3	7.0	8.0	0.000	0.000	100	0.60	3.5	650	33	0.60
710509	17.8	7.0	7.2	8.2	0.000	0.000	100	3.52	0.6	430		3.70
710433	15.6	7.5	8.1	8.3	3.333	3.333	550	0.75	0.6	661		3.50
710205	7.2	7.5	7.7	8.0	0.000	0.000	40	1.00	1.5	650		0.60
710129	3.3	7.5	7.5	8.3	3.333	3.333	50	3.70	0.9	400		3.30
710020	21.1	6.5	7.4	8.0	0.000	0.000	100	0.50	0.8	333		3.25
710025	11.1	6.5	8.1	8.1	0.000	0.000	100	1.30	3.0	663	50	3.15
710016	6.4	11.5	7.7	8.0	0.000	0.000	10	1.60	0.9	610		0.60
710008	1.1	8.0	8.0	8.0	0.000	0.000	100	1.05	1.0	500	73	0.60
710112	3.3	13.0	8.3	8.3	3.333	3.333	100	1.10	0.9	550	60	0.15
711202	6.7	10.5	8.1	8.0	0.000	0.000	100	0.60	3.0	23	13	0.20
711116	19.6	8.0	8.0	8.0	0.000	0.000	62	3.53	3.2	55	32	3.20
711323	19.6	8.0	8.1	8.1	0.000	0.000	113	0.30	0.0	19	29	0.20
710919	22.8	6.0	8.1	8.0	0.000	0.000	100	0.60	0.0	22	33	0.20
710715	25.6	6.0	8.1	8.1	0.000	0.000	200	0.0	0.0	32	32	0.10
710623	26.1	4.5	8.1	8.1	0.000	0.000	1100	0.60	0.2	32	37	0.20
710512	17.8	7.0	8.2	8.2	0.000	0.000	133	1.43	1.5	62	66	3.30
710415	13.3	7.0	8.2	8.2	0.000	0.000	20	2.40	3.5	96	102	0.60
710317			8.0	8.0	0.000	0.000	10	2.70	3.2	84	94	0.30
710223	2.2	10.0	8.1	8.1	0.000	0.000	60	0.00	3.2	55	86	0.30
710113	3.9	8.0	7.5	8.3	0.000	0.000	100	0.50	0.2	72	106	0.60
710202	5.6	13.3	8.2	8.2	3.333	3.333	73	0.83	3.2	93	63	3.20
710118	10.4	8.0	7.9	8.1	0.000	0.000	350	0.70	0.2	30	85	3.20
710021	18.9	8.0	7.8	8.0	0.000	0.000	120	0.2	0.2	30	36	0.20
710917	21.1	6.0	8.0	8.0	0.000	0.000	900	0.00	0.0	25	34	0.20
710811	24.8	5.0	8.1	8.1	0.000	0.000	1000	0.0	0.0	25	31	0.10
710715	22.8	5.9	7.7	7.7	3.333	3.333	163	3.73	3.2	23	35	0.20
710617	25.0	7.0	7.7	8.0	0.000	0.000	60	0.00	0.0	38	50	0.10
710512	20.6	5.5	7.8	8.0	0.000	0.000	40	0.00	0.2	74	86	3.30
710416	15.0	7.0	7.7	8.0	0.000	0.000	90	2.20	0.2	97	85	0.20
710325	8.9	9.0	7.8	8.0	0.000	0.000	100	2.60	0.2	63	57	0.30
710315	1.7	13.6	7.4	8.2	3.333	3.333	530	1.00	0.2	80	57	0.50
691204	6.7	10.0	7.8	8.0	0.000	0.000	30	0.10	0.2	75	62	0.40
691120			8.0	8.0	0.000	0.000	100	1.30	3.2	63	52	3.20
691022	15.6	7.0	7.8	8.1	0.163	0.000	120	0.80	0.2	38	44	0.30
691001	19.4	6.9	8.1	8.1	0.000	0.000	100	0.20	0.0	23	35	3.30
690924	21.1	6.8	7.7	8.0	0.000	0.000	60	0.40	0.0	26	35	0.00
690827		4.7	7.5	8.0	0.000	0.000	2000	0.50	0.0	26	35	0.30
690716	26.1	4.8	7.5	8.0	0.000	0.000	133	3.43	3.3	24	36	1.3
690610	20.0	6.7	7.7	8.0	0.000	0.000	40	1.50	0.2	21	66	0.30
690514	18.3	6.8	7.7	8.1	0.131	0.000	60	3.2	3.2	58	76	3.23
690416		7.6	7.8	8.0	0.000	0.000	30	0.00	1.1	100	135	0.30
690319	10.0	7.9	7.8	8.0	0.000	0.000	10	2.20	1.6	82	100	3.60
690219	7.8	8.1	7.9	8.3	3.333	3.333	133	3.5	3.5	84	106	0.50
681209	5.6	8.1	8.2	8.2	0.163	0.000	110	1.40	0.5	27	30	0.30
681112	12.7	8.8	8.3	8.3	3.333	3.333	133	0.73	3.2	19	46	3.33
681017	20.6		7.8	8.0	0.000	0.000	160	1.20	1.1	31	42	0.60
680904	23.9		7.8	8.0	0.000	0.000	90	0.7	0.7	50	68	0.30
680831	25.6	6.3	8.1	8.3	3.333	3.333	233	1.20	0.7	33	48	0.30
680724	27.8		7.7	8.0	0.000	0.000	403	0.7	0.7	33	48	0.20
680718		5.6	7.9	8.3	3.333	3.333	233	3.7	3.7	42	44	0.30
680520			7.8	8.0	0.000	0.000	100	0.7	0.7	27	42	0.30
670913	21.1	5.1	7.4	8.1	0.163	0.000		1.40	3.2	28	53	3.13
670815	22.2	4.4	7.7	8.1	0.131	0.000		0.70	0.7	41	66	0.10

WAS 01 CALUMET RIVER
130TH STREET BRIDGE SOUTH OF LAKE CALUMET --CONTINUED

DATE	5 DAY COD (MG/L)	SUR- FACED SOLIDS (MG/L)	HEX- CHLOR- IDE (MG/L)	TEL- CHLOR- IDE (MG/L)	COPPER (MG/L)	TOTAL CHLOR- IDE (MG/L)	LEAD (MG/L)	ZINC (MG/L)	FLUOR- IDE (MG/L)	HAZ- ARDS (MG/L)	ALKA- LITY (MG/L)
710627			3.33	3.33	3.33	3.33	0.5	0.31	3.3	3.6	

[illegible]

MAA 01 CALUMET RIVER
130TH STREET BRIDGE SOUTH OF LAKE CALUMET --CON' 100LD

DATE	DIS-												
	AMZNIC	BARION	BUNCH	ION	IRON	ANES.	PERCUIT	NICKEL	ARION	SILVER	GIL	NOZ	VSS
	(MG/L)	(MG/L)	(MG/L)	(MG/L)	(MG/L)	(MG/L)	(MG/L)	(MG/L)	(MG/L)	(MG/L)	(MG/L)	(MG/L)	(MG/L)
711202	0.000				0.12			3.3					
711116	0.000				0.10			0.0					
711020	0.000				0.00			0.0					
710915	3.333				3.12			3.3					
710715	0.000				0.10			0.0					
710623	3.333				3.12			3.3					
710512	0.000				0.00			0.0					
710415	0.000							0.0					
710317	3.333				3.33			3.3					
710203	0.000							0.0					
710113	3.333				3.50								
701118	0.000				0.20			0.0					
700917		0.0						0.0					
700817		3.3			3.10			0.0					
700512		0.0			0.10								
700416		3.0			0.30			3.3					
700325	0.000	0.0			0.20			0.0					
700115	0.000	0.0			3.30			0.0					
691022	3.333	3.3						0.0					
690928	0.000	0.0			0.20			0.0					
690716	3.025	0.0						0.0					
690610	0.000	0.0			0.10			0.0					
690518	0.000	0.0						0.0					
690416	3.333	3.3			3.20			0.0					
681112	0.000	0.0			0.10			0.0					

MAA 02 CALUMET RIVER
US 41-ELING AVENUE BRIDGE NEAR SOUTH AT LAKE
LAB: CHICAGO

DATE	TEMP-	DIS-	TOTAL		PH	PHOS-	PHENOLS	FECAL	AMMONIA	NITRATE	SPAL	COLOR-	SULFATE	NO3S	TURBID-
	CHARGE	TEMP	CHARGE	PHOS-											
	(CPS)	(CPS)	(MG/L)	(MG/L)	UNITS	(MG/L)	(MG/L)	(NO./L)	(MG/L)	(MG/L)	UNITS	(MG/L)	(MG/L)	(MG/L)	UNITS
700923		23.3			7.9	3.333	3.333	100	3.23	3.3	333				0.10
700717		26.8	7.0	0.2	0.050	0.000	100	0.37	0.5	333		18	28		0.10
700627		17.0	7.6	7.6	0.550	0.000	100	0.38	1.8	350					3.23
700527		17.8	13.2	8.3	3.333	3.333	110	3.80	0.7	433					3.20
700422		13.3	9.0	7.9	0.040	0.000	100	0.60	0.2	400					0.20
700315		13.0	9.0	7.6	3.350	0.000	100	0.73	0.8	450					3.20
700219		6.7	11.0	8.0	0.120	0.000	10	0.90	0.3	400		20	34		0.20
700116		5.6	11.1	7.4	0.040	0.000	33	1.33	3.5						3.43
700129		11.1	8.5	8.5	0.050	0.000	100	0.40	0.7	410					0.20
700626		20.0	8.6	8.0	0.060	0.000	130	0.37	3.5	317					0.80
700539		18.4		8.0	0.150	0.000	100	0.70	0.8	300					0.20
700430		13.3		8.1	0.020	0.000	60	0.89	0.3	317					0.20
700305		7.2	8.0	7.8	0.333	0.333	13	3.93	3.6	350					3.37
700124		0.0	7.5	7.8	0.330	0.000	20	0.60	0.7	367					0.10
700628		21.1	8.5	7.9	0.000	0.000	100	0.20	0.2	243		11	23		3.25
700425		11.1	10.0	8.0	0.012	0.300	100	1.30	3.8	400					0.35
700316		18.4	9.5	7.6	0.025	0.000	10	1.00	0.6	430					3.40
700204		8.4	11.0	8.0	0.353	0.300	133	3.80	3.5	360		25	38		3.43
700112		7.8	9.0	8.0	0.060	0.000	40	1.20	0.6	450		50	83		0.30
711207				7.5	1.664	0.000	20000	22.60	3.0			115	123		2.40
711202		6.7	11.5	8.0	0.065	0.000	70	0.30	3.0			20	33		0.10
711116		13.9	9.0	8.1	0.030	0.000	100	0.30	3.0			26	27		0.20
711023		17.0	9.0	8.1	0.333	3.333	23	3.23	3.3			13	24		0.10
710915		19.4	9.0	8.2	0.030	0.000	100	0.30	0.0			11	21		3.38
710715		22.0	7.0	8.0	0.000	0.000	100	3.80	0.0			15	22		0.13
710623		21.7	8.3	8.2	0.065	0.000	30	0.50	0.0			14	25		0.20
710512		13.9	8.5	8.2	0.033	0.000	100	0.70	0.0			23	28		0.20
710415		13.3	8.0	8.1	0.333	3.333	13	3.83	0.2			24	36		0.20
710317			8.0	8.0	0.030	0.000	40	0.40	3.2			38	45		3.10
710203		4.4	8.0	8.1	0.196	0.000	10	0.93	3.0			23	37		3.13
710113		3.1	13.0	7.4	0.033	0.000	1400	0.98	3.0			10	17		0.20
701202		8.3	8.0	7.9	0.131	0.000	180	0.80	0.0			60	34		3.23
701118		11.1	9.3	7.8	3.359	0.000	100	0.00	0.0			19	29		0.20
701021		15.0	10.0	7.6	0.033	0.000	40	0.13	0.0			14	26		0.20
700917		17.8	8.5	8.4		0.000	223	0.03	3.3			11	23		3.13

HAA 02 CALUMET RIVER
US 41-BUILDING AVENUE BRIDGE NEAR MOUTH AT LAKE --CONTINUED

DATE	TEMP- DIS- CHARGE (CFS)	DIS- SOLVED OIL/GAL DEG C	TOTAL PHOS- PHOSPHORUS (MG/L)	PERAL COLIFORM (NO./L)	AMMONIA NITRO- GEN (MG/L)	NITRATE (MG/L)	SPEC COND UMHOS	CHLOR- IDE (MG/L)	SULFATE (MG/L)	HAAS (MG/L)	TURBID- ITY UNITS
700611	22.2	7.0	0.000	0.000	200	0.00	0.0	41	26	0.10	4
700715	19.4	8.8	0.005	0.000	173	0.10	0.0	10	23	0.10	4
700617	20.0	9.5	0.005	0.000	20	0.00	0.0	11	23	0.10	4
700512	15.0	8.0	0.013	0.000	20	1.00	0.2	12	28	0.13	15
700416	12.4	9.3	0.013	0.010	60	1.00	0.2	22	26	0.00	11
700325	7.2	9.0	0.013	0.025	100	1.00	0.0	25	31	0.13	13
700218	2.4	13.1	0.013	0.000	233	0.10	0.0	4	26	0.20	13
700115	1.1	12.6	0.000	0.000	10	0.40	0.0	11	26	0.20	11
691209	11.7	9.1	0.065	0.000	33	0.60	0.2	37	36	0.23	15
691120			0.065	0.000	105	0.80	0.0	26	31	0.20	22
691022	18.4	8.5	0.005	0.000	130	0.00	0.0	27	26	0.13	17
690924	17.8	7.7	0.005	0.000	70	0.20	0.0	13	25	0.00	13
690824	19.4	8.3	0.005	0.000	400	0.30	0.0	11	25	0.20	12
690727		6.6	0.065	0.000	133	0.30	0.0	11	21	0.20	4
690716	23.3	6.2	0.065	0.000	100	0.20	0.0	13	24		5
690610	17.8	7.8	0.000	0.000	33	0.30	0.0	14	22	0.20	4
690514	18.4	8.8	0.131		80		0.0	18	24	0.20	13
690416		9.0	0.000	0.000	20	0.10	0.5	26	35	0.20	13
690315	8.9	12.2	0.2	0.000	13	0.40	0.7	22	29	0.20	15
690219	9.4	8.9	0.000	0.000	100	1.20	0.5	39	56	0.50	11
690106	1.1		0.065	0.010	133	0.30	0.0	23	29	0.10	33
681209	3.3	8.4	0.163	0.000	10	0.20	0.2	10	30	0.10	13
681112	9.4	10.5	0.131	0.000	1000	0.10	0.0	15	26	0.20	11
681017	18.4	8.1	0.065	0.000	533	0.30	0.5	14	23	0.03	17
680904	22.2		0.000		80		0.5	14	24	0.00	4
680724	22.8		0.000		430		0.5	13	32	0.13	11
680716			0.000		2000		0.2	15	24	0.20	6
680528			0.013		100		0.0	11	24	0.20	3
680528		8.2	0.131		23000		0.5	13	38	0.20	11
680116	2.2	11.7	0.013		100		0.0	20			6
671120	4.4	9.4	0.000	0.000	133	1.20	0.2	16	31	0.10	15
670913	20.0	7.1	0.522			0.60	0.2	18	28	0.10	8
670417	28.4	7.0				1.50					

HAA 02 CALUMET RIVER
US 41-BUILDING AVENUE BRIDGE NEAR MOUTH AT LAKE --CONTINUED

DATE	800 5 DAY (MG/L)	COB (MG/L)	SUS- PENDED SOLIDS (MG/L)	CADMIUM (MG/L)	HEZ CHROM- IUM (MG/L)	TRI CHROM- IUM (MG/L)	COPPER (MG/L)	CYANIDE (MG/L)	TOTAL IRON (MG/L)	LEAD (MG/L)	ZINC (MG/L)	FLUOR- IDE (MG/L)	HARD- NESS (CALCO)	ALKAL- LITY (CALCO)
740717				0.000	0.00	0.00	0.04	0.000	0.2	0.13	0.0	0.3		
740219				0.000	0.00	0.00	0.23	0.000	0.2	0.45	0.1	0.5		
720628				0.000	0.00	0.00	0.00	0.000	0.2	0.00	0.0	0.4		
720208	12			0.000	0.00	0.00	0.00	0.100	0.1	0.00	0.1	0.7	150	120
721112	15			0.000	0.00	0.00	0.00	0.370	0.1	0.00	0.1	0.7		112
711207	7		18					0.000				1.1		
711202		7		0.000	0.00	0.00	0.01	0.000	0.1	0.00	0.0	0.3	130	138
711116	4			0.000	0.00	0.00	0.01	0.000	0.1	0.00	0.0	0.3	130	104
711020	11			0.000	0.00	0.00	0.01	0.070	0.1	0.00	0.1	0.3	130	133
710915	13			0.000	0.00	0.00	0.00	0.000	0.1	0.00	0.0		120	104
710715	7			0.000	0.00	0.00	0.02	0.080	0.1	0.00	0.1	0.3	130	104
710623	16			0.000	0.00	0.00	0.01	0.160	0.1	0.00	0.0		160	112
710512	8			0.000	0.00	0.00	0.00	0.100	0.0	0.00	0.0	0.4	150	112
710415	12			0.000	0.00	0.00	0.00	0.000	0.0	0.10	0.3	0.5	150	116
710317	12			0.000	0.00	0.00	0.00	0.000	0.5	0.06	0.1		160	120
710203	15			0.000	0.00	0.00	0.00	0.240	1.7	0.00	0.1		160	128
710113	12			0.000	0.00	0.00	0.00	0.080	0.4	0.00	0.1		170	112
701202	5							0.000				0.4	150	114
701118	6			0.000	0.00	0.00	0.00	0.030		0.00	0.1		130	124
701021	4			0.000	0.00	0.00	0.00	0.000		0.00	0.0		140	104
700917	5			0.000	0.00	0.00	0.00	0.130		0.13	0.3	0.2	140	134
700811	10			0.000	0.00	0.00	0.00	0.280	0.4	0.00	0.1		140	145
700715	11							0.000	0.1			0.2	140	115
700617	7			0.000	0.00	0.00	0.00	0.360	0.2	0.30	0.1	0.2	140	134
700512	8			0.000	0.00	0.00	0.00	0.000	0.0	0.00	0.3	0.2	140	134
700416	6			0.000	0.00	0.00	0.00	0.360	0.4	0.30	0.3		150	112
700325	14			0.000	0.00	0.00	0.00	0.000	0.9	0.00	0.4	0.4	160	120

88A 02 CALUMET RIVER
US 41-BUILDING AVENUE BRIDGE NEAR MOUTH AT LAW --CONTINUED

DATE	NO. DAY	COD	SUS- PENDED SOLIDS (MG/L)	CAUMIUM (MG/L)	CHROM- IUM (MG/L)	CHROM- IUM (MG/L)	COPPER (MG/L)	CYANIDE (MG/L)	TOTAL IRON (MG/L)	LEAD (MG/L)	ZINC (MG/L)	FECHUR- IDE (MG/L)	HAZU- NISE (MG/L)	ALAA- LIMIT (MG/L)
700218		12		0.000	3.30	3.30	3.33	0.333	3.1	3.30	3.1	3.2	153	123
700315		8		0.000	0.00	0.00	0.00	0.000	0.4	0.10	1.0		156	116
691203		17		0.000	0.00	0.00	0.00	0.000	0.7	0.00	0.7	0.7	160	106
691123		13						3.333					150	112
691022		5		0.000	0.00	0.00	0.03	0.000	0.4	0.00	0.1	0.2	140	106
691001		6						3.333					143	106
690924		4		0.000	0.00	0.00	0.03	0.000	0.0	0.00	0.0	0.2	130	100
690827		8		0.000				3.100	0.1	0.00		0.2	140	100
693716		5		3.333	3.33	3.30	3.00	3.333	3.0	0.00	0.0	0.0	130	115
690610		3		0.000	0.00	0.00	0.00	0.000	0.2	0.00	0.0		140	116
693514		5		3.333	3.33	3.33	3.30			3.33	3.3		143	112
690416		5		0.000	0.00	0.00	0.00		0.6	0.00	0.1		150	112
690319		5						0.000	0.9			0.0	140	116
690219		5						0.000					170	106
690106		0						0.000	1.2			0.2	150	116
681209		8						3.333	0.6			0.2	140	106
681112		8		0.030	0.00	0.00	0.00	0.000	0.5	0.00	0.0		136	116
681017		2		0.000	0.00	0.00	0.00	0.000		0.00	0.0		136	138
683928		0						0.000					140	106
680728		8											156	106
680718		5											136	138
683528		5											132	138
680508		5											122	112
680116	2												152	116
671128		10											146	138
670913		50											156	108
670817		7												

88A J2 CALUMET RIVER
US 41-BUILDING AVENUE BRIDGE NEAR MOUTH AT LAW --CONTINUED

DATE	ARSENIC (MG/L)	BARIUM (MG/L)	BORON (MG/L)	CHROM- IUM (MG/L)	DIS- SOLVED IRON (MG/L)	HAZU- NISE (MG/L)	MERCURY (MG/L)	NICKEL (MG/L)	SELE- NIUM (MG/L)	SILVER (MG/L)	OIL (MG/L)	DOE (MG/L)	VSS (MG/L)
740717	0.000	0.0	0.1		0.06	0.3	0.0	0.00	0.000				
740219	0.000	0.0	0.1		0.10	0.3	0.0	0.00	0.000				
720628					3.36	3.3							
720204	0.000				0.10								
720112	0.000				0.08								
711202	0.000				0.00								
711116	0.000				0.10								
711323	3.333				3.33	3.3							
710915	0.000				0.10								
710715	0.000				0.00								
710623	0.000				0.10								
710512	0.000				0.00								
710415	3.331					3.0							
710317	0.000				0.30	0.0							
710203	0.000					0.0							
710113	0.000				0.10								
701118	0.000				0.20	0.0							
721021	3.330				3.33	3.3							
700917		0.0				0.0							
700811		0.0			0.00	0.0							
700617		0.0			0.00	0.0							
700512		0.2			0.30	0.0							
700416		3.3			3.23	3.0							
700325	0.000	0.0			0.10	0.0							
700218	0.004	0.0				0.0							
700115	0.000	0.0			0.10	0.0							
691209	0.000	0.0				3.0							
691322	3.333	3.3				0.0							
690924	0.000	0.0			0.00	0.0							
690716	0.000	0.0				0.0							
690410	0.000	0.0			0.00	0.0							
690514	0.000	0.0				0.0							
690416	0.303	3.3			3.10	0.0							
681112	0.000	0.0			0.00	0.0							

HA 01 GRAND CALUMET RIVER
TORRENCE AVENUE BRIDGE AT BURNHAM --CONTINUED

DATE	TEMP- CHARGE (C/F)	DIS- SOLVED OXYGEN (MG/L)	DIS- SOLVED OXYGEN (MG/L)	TOTAL PHOS- PHOSPHORUS (MG/L)	PHOS- PHOSPHORUS (MG/L)	FECAL COLIFORMS (100/.1L)	AMMONIA NITRO- GEN (MG/L)	NO3+NO2 NITRO- GEN (MG/L)	SPEC COND (MG/L)	LEAD (MG/L)	FLOUR- IDE (MG/L)	CHLOR- IDE (MG/L)	SULFATE (500) (MG/L)
751024	21.5	0.5	0.2	2.000		200	10.00	0.4	1200				
750915	18.5	1.0	0.2	0.600		700	1.80	2.7	883				
750912	18.5	0.7	7.9	1.400	0.005	6500	4.80	0.2	933	0.03	0.9	95	110
750808	22.0	2.0	7.0	1.100		1700	7.00	0.3	1150				
750610	21.5	0.6	7.0	1.100		300	29.00	0.8	1250				
750617	16.5	0.0	7.0	0.750		9200	21.00	0.7	1400				
750227	5.5	5.9	8.5	0.750		1800	5.40	0.9	1067				
750116	6.0	5.5	8.0	0.620		2300	4.00	1.0	1017				
750103	6.0	5.7	8.6	0.650	0.008	500	5.10	1.5	1017	0.07	0.8	100	145
741204	8.5	3.2	8.3	1.000	0.102	14000	19.00	0.7	1200				

HA 01 GRAND CALUMET RIVER
TORRENCE AVENUE BRIDGE AT BURNHAM --CONTINUED

DATE	ARSENIC (MG/L)	BARIUM (MG/L)	BORON (MG/L)	CADMIUM (MG/L)	CHROM- IUM (MG/L)	CHROM- IUM (MG/L)	COPPER (MG/L)	IRON (MG/L)	NICKEL (MG/L)	SELE- NIUM (MG/L)	SILVER (MG/L)	ZINC (MG/L)	URAN (MG/L)	DOB (MG/L)
770309	0.000	3.0	0.6	0.020	0.00	0.33	0.16	0.6	0.00	0.000				
760323	0.000	0.1	0.7	0.000	0.00	0.00	0.08	2.3	0.0	0.00	0.000	0.2	0.90	
751119	0.002	0.0	0.8	0.000	0.00	0.00	0.11	0.8	0.0	0.00	0.000	0.0	0.80	
751103	0.000	0.0	0.6	0.000	0.00	0.00	0.07	0.5	0.0	0.00	0.000	0.0	1.20	
750912	0.005	0.0	0.8	0.000	0.00	0.01	0.04	0.7	0.0	0.00	0.000	0.0	0.60	
750103	0.000	1.3	0.6	0.000	0.00	0.00	0.10	0.5	0.0	0.00	0.000	0.1	1.00	
741204													2.00	

HA 01 GRAND CALUMET RIVER
TORRENCE AVENUE BRIDGE AT BURNHAM --CONTINUED

DATE	SUS- PENDED SOLIDS (MG/L)	CHLOR- IDE (MG/L)	AMMONIA NITRO- GEN (MG/L)	CHROM- IUM (MG/L)	ALKA- LINIT (MG/L)
770309	0.030			1.0	320
760323	0.010	0.89		0.3	260
751119	0.010	0.20			
751103	0.330	0.12		0.0	
750912	0.020	0.21		0.0	
750103	0.010	0.15		0.2	

HA 01 CALUMET RIVER
110TH STREET BRIDGE SOUTH OF LAKE CALUMET
LAB: CHICAGO

DATE	TEMP- CHARGE (C/F)	DIS- SOLVED OXYGEN (MG/L)	DIS- SOLVED OXYGEN (MG/L)	TOTAL PHOS- PHOSPHORUS (MG/L)	PHOS- PHOSPHORUS (MG/L)	FECAL COLIFORMS (100/.1L)	AMMONIA NITRO- GEN (MG/L)	NO3+NO2 NITRO- GEN (MG/L)	SPEC COND (MG/L)	LEAD (MG/L)	FLOUR- IDE (MG/L)	CHLOR- IDE (MG/L)	SULFATE (500) (MG/L)
770309	2.0	11.9	0.4	0.090	0.000	210	0.50	0.4	392	0.02	0.2	26	33
770126	0.0	13.3	0.4	0.000	0.000	600	0.32	0.2	343	0.01	0.3		26
761110	11.0	0.3	0.5	0.090		400	1.10	0.4	533				
761005	18.5	6.6	0.3	0.000	0.000	700	0.84	0.8	450	0.07	0.5	52	81
760803		5.9	0.3	0.080		100	0.11	1.3	483				
760614	24.0		0.4	0.030		100	1.00	0.5	467				
760428	15.5	6.5	0.2	0.050	0.000	100	0.58	0.5	517	0.01	0.5	55	52
760323	10.0	10.6	0.4	0.040		100	1.40	0.8	467				
760212	5.5	12.9	0.5	0.070		100	0.27	0.6	350				
760112	3.0	11.2	0.2	0.170	0.000	100	2.20	1.0	733	0.08	0.6	100	84
751119	12.0	0.1	0.3	0.110		100	0.43	1.0	450				
751103	15.5	7.7	7.9	0.060		100	0.26	1.2	600				
751024	17.0	6.1	8.5	0.090		100	0.30	1.2	617				
751016	20.0	7.4	0.3	0.050		100	0.26	1.4	567				
750912	20.0	5.9	0.3	0.090		900	0.20	1.3	533				

BA 01 CALUMET RIVER
130TH STREET BRIDGE SOUTH OF LAKE CALUMET --CONTINUED

DATE	DIS- CHARGE (CFS)	TEMP- FRA- TUBE DEG/C	DIS- SOLVED OXYGEN (MG/L)	PH UNITS	TOTAL PHOS- PHOSPHORUS (MG/L)	PHOS- PHOSPHORUS (MG/L)	FECAL COLIFORM (100/L)	AMMONIA NITRO- GEN (MG/L)	NITRO- NITRO- GEN (MG/L)	SPFC COND UMHOS	LEAD (MG/L)	FLUOR- IDE (MG/L)	CHLOR- IDE (MG/L)	SULFATE (50%) (MG/L)
750805		24.0	5.3	8.3	0.040		200	0.12	1.0	443				
750610		21.5	5.8	7.9	0.050	0.000	100	0.78	1.1	600	0.01	0.6	75	55
750417		11.5	10.0	8.1	0.080		100	1.80	1.2	717				
750227		3.0	12.5	8.8	0.080	0.000	100	1.60	0.5	533	0.13	0.4	60	50
750116		1.5	12.4	8.0	0.050		100	0.78	0.7	467				
750103		3.5	11.6	8.5	0.040	0.000	100	0.42	0.4	400				
741204		5.0	10.6	8.2	0.060	0.000	7000	0.42	1.4	463	0.09	0.5	45	40

BA 01 CALUMET RIVER
130TH STREET BRIDGE SOUTH OF LAKE CALUMET --CONTINUED

DATE	ARSENIC (MG/L)	BARIUM (MG/L)	BORON (MG/L)	CADMIUM (MG/L)	HEX- CHROM- JUN (MG/L)	TRI- CHROM- JUN (MG/L)	COPPER (MG/L)	TOTAL IRON (MG/L)	NICKEL (MG/L)	SIL- SILICUM (MG/L)	SILVER (MG/L)	ZINC (MG/L)	BRAS (MG/L)	DOE (MG/L)
770309	0.000	0.0	0.1	0.000	0.00	0.00	0.07	0.3	0.0	0.00	0.000	0.1		
770126	0.000	0.0	0.1	0.000	0.00	0.00	0.00	0.2	0.0	0.00	0.000	0.0		
761005	0.000	0.2	0.1	0.000	0.00	0.00	0.04	0.5	0.0	0.00	0.000	0.1		
760428	0.000	0.0	0.2	0.000	0.00	0.00	0.04	0.6	0.0	0.00	0.000	0.6	0.20	
760112	0.000	0.0	0.2	0.000	0.00	0.00	0.01	0.7	0.0	0.00	0.000	0.0	0.40	
750610	0.000	0.1	0.2	0.000	0.00	0.00	0.00	0.6	0.0	0.00	0.000	0.0	0.20	
750227	0.000	0.1	0.1	0.000	0.00	0.00	0.06	0.5	0.0	0.00	0.000	0.0	0.30	
750103													0.20	
741204	0.000	0.1	0.1	0.000	0.00	0.00	0.10	0.2	0.0	0.00	0.000	0.0	0.30	

BA 01 CALUMET RIVER
130TH STREET BRIDGE SOUTH OF LAKE CALUMET --CONTINUED

DATE	SUS- PENDED SOLIDS (MG/L)	CYANIDE (MG/L)	DATE- ARSEN (MG/L)	HEX- CHROM- (MG/L)	TRI- CHROM- (MG/L)	DATE- LIMIT (MG/L)
770309		0.020	0.03	0.0	150	120
770126		0.010	0.03	0.0		
761005		0.000	0.09	0.0		
760428		0.010	0.09	0.0		
760112		0.000	0.08	0.0		
750610		0.000	0.05	0.0		
750227		0.000	0.11	0.0		
741204		0.000	0.05	0.2		

BA 02 CALUMET RIVER
US 41-BRING AVENUE BRIDGE NEAR SOUTH AT LANE
LAB: CHICAGO

DATE	DIS- CHARGE (CFS)	TEMP- FRA- TUBE DEG/C	DIS- SOLVED OXYGEN (MG/L)	PH UNITS	TOTAL PHOS- PHOSPHORUS (MG/L)	PHOS- PHOSPHORUS (MG/L)	FECAL COLIFORM (100/L)	AMMONIA NITRO- GEN (MG/L)	NITRO- NITRO- GEN (MG/L)	SPFC COND UMHOS	LEAD (MG/L)	FLUOR- IDE (MG/L)	CHLOR- IDE (MG/L)	SULFATE (50%) (MG/L)
770314		3.5	11.2	8.3	0.070	0.000	100	0.12	0.3	320	0.00	0.2	12	25
770105		3.0	12.0	8.0	0.070		100	0.22	0.3	317				
761114		6.0	12.1	8.4	0.000	0.000	100	0.09	0.2	243	0.00	0.3	10	21
760920		10.5	8.1	8.6	0.000		100	0.09	0.3	300				
760830		14.5	6.4	8.3	0.000		100	0.10	0.2	300				
760429		14.5	9.8	8.5	0.020		100	0.12	0.3	350				
760324		10.0	11.3	8.2	0.120		100	0.12	0.5	350				
760104		6.0	11.3	8.3	0.750	0.000	100	0.19	0.4	317	0.05	0.3	13	25
760112		4.5	13.4	8.4	0.020		100	0.17	0.3	317				
760125		8.0	14.4	8.3	0.000		100	0.21	0.4	333				
751210		5.0	10.0	8.1	0.060		100	0.35	0.5	433				
751103		14.5	9.2	7.9	0.000		100	0.17	0.4	317			0.3	26
751002		15.5	8.5	8.1	0.050		100	0.40	0.0	317				20

MAA C2 CALUMET RIVER
US 41-EMING AVENUE BRIDGE NEAR MOUTH AT LAKE --CONTINUED

DATE	DIS- CHARGE (CFS)	TEMP- FRA- TURE (DEG/C)	DES- SOLVED OXYGEN (MG/L)	PH	TOTAL PHOS- PHORUS (MG/L)	PHENOLS (MG/L)	PCAL COLIFORM (NO./1L)	AMMONIA NITRO- GEN (MG/L)	NO3+NO2 NITRO- GEN (MG/L)	SPEC COND (UMHOS)	LEAD (MG/L)	FLUOR- IDE (MG/L)	CHLOR- IDE (MG/L)	SULFATE (SO4) (MG/L)
750905		21.5	7.2	8.3	0.020		200	0.18	0.4	317				
750907		21.5	8.3	8.2	0.010	0.300	100	0.22	0.4	317	0.00	0.3	8	29
750910		21.4	8.6	8.0	0.450		100	0.20	0.3	317				
750325		5.0	11.2	8.3	0.030	0.000	100	0.52	0.4	347	0.04	0.4	17	26
750319		9.0	11.1	8.1	0.040		100	0.86	0.4	400				
750203		4.5	11.4	8.4	0.020	0.000	100	0.64	0.4	400	0.04	0.5	21	30
750106		3.5	12.6	8.2	0.050		100	0.16	0.3	417				
741205		8.0	10.2	8.2	0.040	0.000	100	0.20	0.4	350				

MAA C2 CALUMET RIVER
US 41-EMING AVENUE BRIDGE NEAR MOUTH AT LAKE --CONTINUED

DATE	ARSENIC (MG/L)	BARIUM (MG/L)	BORON (MG/L)	CADMIUM (MG/L)	HEX CHROM- IUM (MG/L)	TRI CHROM- IUM (MG/L)	COPPER (MG/L)	TOTAL IRON (MG/L)	NICKEL (MG/L)	SEL- ENIUM (MG/L)	SILVER (MG/L)	ZINC (MG/L)	SEAS (MG/L)	SOX (MG/L)
770314	0.000	0.0	0.0	0.000	0.00	0.00	0.00	0.1	0.0	0.00	0.000	0.0		
761118	0.000	0.0	0.0	0.000	0.00	0.00	0.02	0.3	0.0	0.00	0.000	0.0		
760304	0.000	0.0	0.1	0.000	0.00	0.00	0.06	0.6	0.0	0.00	0.000	0.0	0.10	
751103														0.10
750807	0.000	0.0	0.1	0.000	0.00	0.00	0.01	0.2	0.0	0.00	0.000	0.0	0.10	
750325	0.000	0.0	0.1	0.000	0.00	0.00	0.12	0.2	0.0	0.00	0.000	0.2	0.20	
750203	0.000	0.1	0.1	0.000	0.00	0.00	0.12	0.3	0.0	0.00	0.000	0.0		0.10
741205														

MAA C2 CALUMET RIVER
US 41-EMING AVENUE BRIDGE NEAR MOUTH AT LAKE --CONTINUED

DATE	SUS- PENDED SOLIDS (MG/L)	CYANIDE (MG/L)	MANG- NESE (MG/L)	MERCURY (MG/L)	HARD- NESS (CAC03) (MG/L)	ALKA- LITY (MG/L)
770314	0.000	0.02	0.0		140	120
761118	0.000	0.04	0.0			
760830	0.070					
760304	0.070	0.04	0.0			
750807	0.000	0.03	0.0			
750325	0.020	0.04	0.0			
750203	0.030	0.16	0.0			

MAA882 WOLF LAKE
INDIANA STATE LINE BRANCH
LAB: CHICAGO

DATE	DIS- CHARGE (CFS)	TEMP- FRA- TURE (DEG/C)	DES- SOLVED OXYGEN (MG/L)	PH	TOTAL PHOS- PHORUS (MG/L)	PHENOLS (MG/L)	PCAL COLIFORM (NO./1L)	AMMONIA NITRO- GEN (MG/L)	NO3+NO2 NITRO- GEN (MG/L)	SPEC COND (UMHOS)	LEAD (MG/L)	FLUOR- IDE (MG/L)	CHLOR- IDE (MG/L)	SULFATE (SO4) (MG/L)
770314		4.0	10.3	8.4	0.040	0.000	10	0.30	0.3	355	0.00	0.2	20	31
770125		6.5	7.5	8.2	0.040		100	0.26	0.2	433				
770105		3.5	11.7	8.0	0.020		100	0.34	0.1	433				
761118		5.0	13.1	8.4	0.000	0.000	100	0.16	0.1	400	0.01	0.5	28	42
760930		17.0	10.2	8.5	0.020		100	0.12	0.0	383				
760830		21.0	7.9	8.4	0.040	0.006	100	0.04	0.2	383	0.01	0.5	35	40
760429		10.5	11.0	8.5	0.040		100	0.08	0.3	450				
760324		11.0	11.3	8.4	0.090		100	0.04	0.4	417				
760304		6.0	11.5	8.3	0.130	0.000	10	0.28	0.4	400	0.04	0.5	28	42
751210		2.0	12.8	8.1	0.030		100	0.10	0.2	417				
751103		14.5	10.2	7.9	0.000	0.000	100	0.12	0.1	417	0.21	0.4	50	41
751002		11.5	9.8	8.3	0.000		100	0.05	0.0	400				
750807		20.5	8.6	8.7	0.020	0.000	100	0.10	0.2	350	0.00	0.4	40	40
750430		27.0	7.7	8.3	0.010		100	0.10	0.0	367				
750413		23.5	9.6	8.4	0.040		100	0.00	0.1	383				

APPENDIX E

No. 1

Cargill, Inc. IL0037087

Effective date of permit: 8/26/79

Expiration date of permit: 4/30/84

Receiving waters: Calumet River

Cargill, Inc. - Elevator/Grain Division IL0037087

DAF = 0.007 MGD

1

DMF = 0.01 MGD

Outfall

Treated sanitary waste to the Calumet River.

001 Limits:	Avg./Max. Flow	6/9 P.H.	TSS 45/75	BOD 45/75	400 F.C.	CL ₂ .75
Jan. '81	.0054/.0059	6.7/8.3	21.3/35	.6/2	60	2.1*2
March '81	5450/6100.	6.9/7.8	18/31	.4/4	---*1	---*1
June '81	.006/.006	---*1	19/40	5/25	30/100	0.75
April '82	.006/.007	7.3/7.6	17/27	2/4	56	3.0*2
Aug. '82	.006/.007	7.3/7.6	9/14	5/11	9400*2	---*1
Sept. '82	.006/.007	7.4/7.9	7/16	2/3	8200*2	N/R*1
EXCURSIONS	---	---	---	---	2	2

001/Sanitary wastewater

*1 Not reported

*2 excursion(s)

DR:ds:8018C/3,sp

No. 2

Cargill, Inc. IL0056057

Effective date of permit: 7/13/79

Expiration date of permit: 1/31/84

Receiving waters: Calumet River via drainage ditch

Cargill, Inc. - Domestic Soybean Crushing Division

DAF = 0.0059 MGD

1

DMF = 0.0065 MGD

Outfall

Treated sanitary and industrial wastewater to the Calumet River.

001	Avg./Max.		A/M	BOD	*	F.C.	FOG	
Limits:	Flow	6/9 P.H.	TSS 30/75	30/75	-	400	15/30	NH3
January '81	.854/.083	7.0/7.9	13/28	3.9/8	-	10	1/1	
April '82	.0731/.095	7.0/7.7	11/25	3/4		346	5/5	.5

002			15			15/30	
Limits:	Flow	P.H.	TSS	BOD	F.C.	FOG	NH3
April '82	.0731/.095	7.0/7.7	11/25	3/4	346	5/5	.5

EXCURSIONS							

DR:ds:8018C/2,sp

001/Industrial, sanitary
wastewater & yard drainage.

* = temperature (no excursions)

002/surface runoff from

002/surface runoff from
parking lot area

(1) once per month sampling

No. 3
Republic Steel Corp. IL0002593
Effective date of permit: 2/25/79
Expiration date of permit: 9/30/80
Receiving waters: Calumet River

Five outfalls listed which discharge to the Calumet River. 001, 002, and 005 are inactive but remain in existence. 003 is non-contaminated stormwater runoff. 004 is non-contact cooling water.

001, 002 and 005 process water overflow limits and or parameters applied to these outfalls: (concentration)

Flow	P.H	Temp.	TSS	Iron	Zinc	Lead	Chrom-Total-Max
---	6-9	<93/<100	15	2.0	1.0	0.1	0.3
Chrom-Total-tri		Oil/Fats and Grease					
1.0		30					

002 Treated process water blow down when discharge to Calumet River but not effective when discharged to MSDGC sewer system.

limits and/or parameters applied to this outfall

	Concentration			Load		
	30	7	Max	30	7	Max
Flow						
P.H.			(6 - 9)			
Temp			(<93/<100)			
TSS		15		414.3		441.3
TDS			750/3500 (background)			
Iron	2.0			55.2		58.8
Zinc	1.0			27.6		29.4
Lead	0.1			2.76		2.94
Chr.tot.-hex	0.3					
Chr.tot.-tri	1.0					
Chr.total						
Oil, fats, a gr	30			27.2		29.0
Fluoride	15			828.6		882.6
CH	0.2			.65		0.7
CN (Oxide)				.126		.252

004 Non-contact cooling water, reports flow and temp.

In the past year, Republic Steel has only discharged four times with most months reported no flow results as they for the most part operate a closed system. Additionally they have the ability to discharge to MSDGC and then have no limits. The company hasn't reported any excursions in the last year.

DR:ds:8018C/6,sp

No.'s 4 and 5
 Interlake, Inc. (Chicago furnace plant) IL0002101
 Effective date of permit: 9/23/75
 Expiration date of permit: 7/1/78
 Receiving waters: Calumet River

Permit allows direct discharge to the Calumet River from two outfalls which serve the Chicago Blast Furnace Plant (denoted on Map as a4) and One outfall which serves the Chicago Coke Plant (denoted on Map as a5). All discharges are once-through, non-contact cooling water. Potential exists for stormwater runoff to enter the stream prior to final sampling and discharge.

Q01	A/M Temp.	P.H. 6/9	Res. Dis.	Res. Susp.	G/O	Max NH ₃	M CN+	M Iron+	M Phen.	M Flow
8/82	25/26	7.6/8.5	174.3	12.8	.897/1.6	.254	.010	.900	.255	8.640
9/82	21/22	7.8/8.4	171.5	76.8	1.3/2.4	.204	.015	1.024	.010	8.640
10/82	17/20	7.8/8.3	185.7	20.3	1.1/1.8	.250	.010	1.437	.010	8.640
11/82	11.5/14.4	7.7/9.4	250.	25.9	.941/1.772	.700	.010	1.767	.010	8.640
12/82	8.4/10.5	7.7/8.4	322.	15.8	1.17/1.412	1.050	.012	.741	.077	8.640
1/83	3.8/5.5	7.9/8.7	396.8	9.1	1.4/2.0	1.450	.025	.788	.027	8.640
2/83	4.8/5.5	7.9/8.8	280.7	18.2	2.4/5.5	.750	.012	.618	.017	8.640
3/83	7.3/11.1	8/8.2	259.1	10.7	5.0/11.1	.900	.030	1.52	.027	8.640
4/83	13.8/19.4	7.9/8.1	374.7	15.8	4.5/6.7	1.199	.010	1.19	.011	8.640
5/83	14.6/16.6	8/8.2	413.5	30.3	3.3/5	.850	.010	1.27	.022	8.640
6/83	19.8/21.1	7.7/8.4	211.0	15.0	3.1/8.6	.505	.010	.867	.100	8.640
7/83	22.5/22.7	7.6/8.2	213.0	14.5	2.81/6.3	.562	.010	1.09	.010	8.640

NPDES Permit: "For the purpose of this permit, these discharges are limited solely to non-contact cooling water and storm water uncontaminated by process wastewater. In the event that the permittee shall require the use of water treatment additives, this permit must be modified in accordance with Part II."

EXCUNSTONS

002 No Results

003	34/37(c) A/M Temp.	P.H.	Max. Res. Dis.	M Res. Susp.	A/M G/O	Max NH ₃	M CN+	M Iron+	M Phen.	M Flow
8/82	25/26	7.7/8.2	190	8.8	.943/1.463	.503	.036	.952	.033	9.648
9/82	21/23	7.9/8.5	176.9	15.6	1.4/2.8	.400	.010	.602	.010	9.648
10/82	17.6/19.4	7.8/8.3	180.8	13.2	1.2/2.4	.503	.010	.659	.015	9.648
11/82	11.5/14.4	8/8.9	235.6	210.3	5.3/16.4	5.3	.825	17.1	.076	9.648
12/82	8.1/10.	7.7/8.3	419.2	72.7	2.2/5.0	1.9	.021	1.120	.044	9.648
1/83	4.5/6.1	7.8/8.4	349.2	16.7	1.6/3.9	1.5	.045	.545	.024	9.648
2/83	5.4/6.6	7.8/8.1	316.8	11.8	3.1/7.9	1.3	.017	.768	.016	9.648
3/83	7.7/11.6	7.8/8.0	355.9	26.4	1.3/1.9	2.2	.017	.926	.029	9.648
4/83	15.1/22.7	7.8/8.3	414.8	16	4.4/7.1	1.5	.027	1.179	.010	9.648
5/83	14.8/16.6	7.5/8.2	431.0	12.9	5.9/16.3	1.2	.085	.827	.065	9.648
6/83	19.5/21.1	7.6/8.3	226.3	8.1	1.8/3.4	.740	.015	.844	.107	9.648
7/83	26.5/36.6	7.5/8.1	200.4	9.3	2.4/5.5	1.2	.048	.763	.013	9.648

Part II:

1. Change of Discharge
2. N.O.M.'s
3. Facility Operation
4. Adverse Impact
5. Bypassing
6. Removed Substances
7. Power Failure
8. Right of Entry
9. Ownership
10. Available reports
11. Permit mod.
12. Toxic pollutants
13. C/C liability
14. Oil and Hazardous Substance liab.
15. State Laws
16. Property Rights
17. Severability
18. Other requirements

DR:ds:8018C/5.sp

No. 6
 Interlak. (Riverdale) IL0002119
 Effective date of permit: 3/19/79
 Expiration date of permit: 9/30/80
 Receiving waters: Little Calumet to Des Plaines River

Permit allows direct discharges to the Little Calumet River from four outfalls serving this facility. All outfalls are once-through, non-contact cooling water. The potential exists for stormwater runoff to enter the streams prior to final sampling and discharge.

Limits 002 Month	Flow		34/37(c) 003 Temp.	6.0/9.0 P.H.	Avg./Max. Flow	Max. Temp. Intake	002/Intake Screen backwash. 003/Cooling water disc. from basic oxygen furnaces and auxiliaries.
	Average	Max.					
July '83	4.151	5.727	23.8/25.5	7.6/7.8	7.7/12	25.5	
June '83	3.482	3.841	20.8/23.3	7.6/8/3	4.9/6.8	23.3	
May '83	3.538	3.738	16.4/18.3	7.6/7.9	6.3/6.8	18.3	
April '83	2.889	4.079	12.3/15.5	7.5/7.8	7.1/9.0	15.5	
March '83	3.453	3.738	10.6/12.7	7.7/7.9	6.3/7.9	12.7	
Feb. '83	4.022	4.623	8.7/27.7	7.5/8.6	7.5/9.0	27.7	
Jan. '83	2.924	3.738	7.1/7.8	7.8/8.4	8.6/2.1	8.8	
Dec. '82	3.088	3.738	10.6/12.2	7.5/8.6	8.6/12.4	12.2	
Nov. '82	2.693	3.402	14.1/18.5	7.5/8.4	7.4/9.8	18.5	
Oct. '82	3.911	5.769	17.9/21.1	7.6/8.1	7.6/11.9	21.1	
Sept. '82	4.040	6.182	22.5/24.4	7.8/7.9	7.1/10.6	24.4	
Aug. '82	2.844	4.454	24.6/27.7	7.6/8.0	12/13.9	27.7	

EXCURSIONS --- --- --- --- ---

004			005					004/Cooling water discharge from primary mill and billet mill rolling operations	
Limits	Temp. 34/37	PH 6/9	Flow Avg/Max	Limits	Temp. 34/37	P.H. 6/9	Flow Avg./Max.	P.H. Intake	005/Cooling water discharge from hot strip mill operations
July '83	23.8/25	7.5/7.6	.897/1.006	23/25	7.5/8	8.8/11.2	7.5/7.8		
June '83	20.8/23	7.4/8.4	.719/.828	20/23	7.4/8.3	8.9/10.5	7.4/8.3		
May '83	16.4/18.3	7.5/7.9	.790/1.035	16.4/18.3	7.6/7.9	10.6/11.9	7.8/7.9		
April '83	12.3/15.5	7.4/7.7	.927/1.257	12.3/15.5	7.5/7.8	10.8/11.2	7.5/7.8		
March '83	10.6/12.7	7.7/7.8	.932/1.492	10.6/12.7	7.8/7.9	10.6/15.2	7.7/8.5		
Feb. '83	8.7/27.7	7.5/7.5	.827/.991	8.7/27.7	7.7/8.8	11.9/15.4	7.3/8.0		
Jan. '83	7.1/7.8	7.7/8.7	.836/.943	7.1/7.8	7.8/8.6	8.3/11.2	7.7/8.2		
Dec. '82	10.6/12.2	7.4/8.5	.643/.955	10.6/12.2	7.7/8.3	9.3/11.2	7.8/8.7		
Nov. '82	14.1/18.5	7.5/7.9	1.298/2.852	14.1/18.5	7.5/8.6	8.5/10.5	7.6/8.8		
Oct. '82	17.9/21.1	7.5/7.9	1.4/3.4	17.9/21.1	7.6/8.0	11.7/12.8	7.5/7.8		
Sept. '82	22.5/24.4	7.6/8.1	1.5/2.3	22.5/24.4	7.5/8.1	12.5/14.5	7.4/7.7		
Aug. '82	24.6/27.7	7.5/7.9	1.7/2.2	24.6/27.7	7.6/7.8	9.7/12.8	7.4/8.1		

EXCURSIONS --- --- --- --- ---

DR:ds:8018C/1.sp

No. 7

Wisc. Steel (Envirodyne) 1L0001660

Effective date of permit: 5/16/74

Expiration date of permit: 12/31/78

Receiving waters: Calumet River

Facility is inactive at this time. Past discharges have been to the Calumet River.

DR:ds:8Q18C/7.sp

No. 8

MSOGC Ca t Sewage Treatment Works aIL0028061

Municipal wastewater treatment plant with a DAF of 219 MGD and a DMF of 330 MGD. Discharge is to the Little Calumet River. Plant is served by a combined sewer system consisting of 130 miles of District interceptors and 3,213 miles of local sewers. A large number of combined sewer overflows/STP bypasses are also incorporated into this system and discharge to various receiving streams. Outfalls 001 and 002 both discharge at the location denoted on the map. 001 is the actual outfall and 002 is the plant's surge chamber overflow. Plant improvements now under construction to expand average design flow 353 MGD and improve final effluent quality. Calumet TARP under construction to receive combined sewer overflows.

Parameter Permit Limit	Flow 220/330	P.H. 6-9	Avg. BOD ₅ 33352	BOD ₅ 40/60	TSS ₅ 33352	TSS ₅ 40/60	Max NH ₃ 30	Fec. Coll. 400
June '82	218/286	7.2/7.7	10,900	14/20	14,600	18/25	22.4	60,000*1
July	234/284	7.5/7.7	13,300	15/15	20,400	23/25	19.2	24,000*1
Aug	213/280	7.0/7.6	15,500	20/21	22,000	28/32	21.2	60,000*1
Sept	186/246	7.3/7.5	14,900	22/29	15,900	23/34	23.6	1,200,000*1
Oct	173/237	7.0/7.7	16,400	27/31	14,700	24/28	23.4	50,000*1
Nov	214/269	7.3/7.6	9,660	12/13	12,800	16/20	22.8	160,000*1
Dec	232/247	7.2/7.6	9640	11/17	13,600	16/20	18.3	200,000*1
Jan '83	202/225	7.2/7.5	9,910	13/19	14,500	20/29	21.2	1,500,000*1
Feb	196/210	7.3/7.6	11,400	16/22	15,200	21/23	19.6	900,000*1
Mar	205/227	7.3/7.6	10,400	13/23	15,500	20/24	20.1	330,000*1
Apr	225/252	7.4/7.9	6,920	8/11	12,200	14/18	16.7	60,000*1
May	266/297	7.2/7.6	14,900	15/20	19,600	20/20	15.6	59,000*1
Jun	236/294	7.2/7.5	19,000	21/27	23,700	27/31	19.2	11,000*1

EXCURSIONS	---	---	---	---	---	---	---	12
------------	-----	-----	-----	-----	-----	-----	-----	----

	CL2 2/1.0	Min D.O. 5.2	Q. C Arsenic	Q. C Bar	Q. C CAD	Max total Chrom	Q tri C Chrom 1251/1.0	Q Hex C Chrom 375/.30
June	*1.0*1	6.2	*/*	*/*	*/*	*	*	
July	0.2/0.9	5.6	**	*/*	*/*	*	*	
Aug	*1.90*1	4.3*1	*	*	*	*	*	30.7/.04
Sept	*1.10*1	5.5	*	*	*	.02	16.6/.02	16.6/.02
Oct	.1/.7*1	5.4	*	*	*	.03	26.4/.03	26.4/.03
Nov	.2/1.0	5.4	*	*	*	*	*	*
Dec	.2/.5	5.2	*	*	*	*	*	*
Jan '83	*1.2*1	4.3*1	*	*	*	.02	14.9/.02	14.9/.02
Feb	*1.1.0	6.1	*	*	*	*	*	*
Mar	.4/.9	5.9	*	*	*	.03	25.3/.03	25.3/.03
Apr	.1/1.0*1	6.8	*	*	*	.03	27.1/.03	27.1/.03
May	.4/1.0	5.3	*	*	*	*	*	*
June	.2/1.0	5.8	*	*	*	.03	24.4/.03	24.4/.03

EXCURSIONS	6	2	---	---	---	---	---	---
------------	---	---	-----	-----	-----	-----	-----	-----

DR:ds:8018C/11.sp

See page (2 of 2)

MSOGC Ca t... (1 of 2)

	Q/M C Copper 12/51/1.0	Q C CN 575/.460	Q C Flor 18760/15	Q Total C Iron 2752/2.2	Q Dis C Iron 625/0.5	Q Dis C Lead 225/.18	Q C Mang. 1251/1.00	Merc. 2.2/.0018
June	29/.03	91.1/.122	1050/1.27	543/0.7	77.2/0.1	*/*	137/.16	40/.0004
July	20.3/.02	48.2/.058	1170/1.19	633/0.6	101/0.1	*	122/.14	.405/.0004
Aug	25.5/.03	30.5/.047	914/1.19	702/.09	234/0.3	*	93.6/.12	.14/.002
Sept	51.2/.06	37.9/.057	931/1.278	512/0.6	67.2/0.1	*	92.5/.11	.076/.0001
Oct	26.4/.04	49.3/.056	892/1.19	1140/1.3	88/0.1	*	96.8/.16	.14/0.2
Nov	20.7/.02	115/.165	880/1.15	417/.6	99/0.1	*	111/.12	.226/.0004
Dec	*	149/.18	1040/1.26	680/.08	89.5/0.1	*	116/.14	.327/.0004
Jan '83	15.2/.02	66.1/.086	1090/1.3	478/0.7	204/0.3	*	112/.14	.483/.0006
Feb	22.1/.03	34.4/.045	906/1.22	685/0.9	304/0.4	*	95.6/.13	.153/.0002
Mar	16.1/.02	69/.089	1170/1.45	395/0.5	80.2/0.1	16.1/.02	92.8/.11	1.2/.0014
Apr	16.6/.02	192/.24	850/.94	520/.0.6	181/0.2	25.5/.03	1081.12	.091.001
May	30.9/.03	65/.068	1030/1.0	662/0.7	189/0.2	*	163/.15	.111/.0001
June	20.7/.02	153/.195	107/1.19	779/0.9	318/0.4	17.4/.02	136/.14	.111/.0001

EXCURSIONS:

	Q C Nic 1251/1.0	Q C 011 77543/.62	Q C Phen. 375/.300	Q C Sc1 1251/1.0	Q C Silver 125/.1	Q C Zinc 1251/.1	003 800	TSS	Flow
June	*/*	6060/8	68.2/.090	*/*	*/*	254/.34	68	142	39
July	*	8420/9	92.7/.109	*	*	694/0.7			
Aug	*	9030/13	121/.132	*	*	822/.95			
Sept	*	8370/4	83.7/.126	*	*	658/.77			
Oct	*	14,100/16	33.1/.049	*	*	521/.85			
Nov	*	7370/8	26.7/.032	*	*	170/.22			
Dec	*	8050/9	89.7/.106	*	*	248/0.3			
Jan '83	*	18,300/27	8.88/.013	*	*	110/0.16			
Feb	*	24,700/34	7.8/.011	*	*	162/.23			
Mar	*	7490/9	10.5/.011	*	*	124/.13			
Apr	*	8920/9	26.9/.025	*	*	236/.25			
May	*	8920/9	26.9/.025	*	*	236/.25			
June	*	8700/10	14.5/.014	*	*	582/.63			

EXCURSIONS:

*Below detectable limits

*INPDES Excursions

DR:ds:8018C/12,sp

No. 9

Wolf Lake minals, Inc. Hammond, Ind.

An industrial center/tank farm which is located in Indiana but discharges storm water to Wolf Lake in Illinois. Facility is currently in litigation for allegedly discharging contaminated stormwater into waters of the States of Illinois and Indiana.

No Illinois NPDES permit exists. Sample results obtained from the Agency's Records Unit are as follows:

- 5/14/82

From run-off water north end westside of plant facility of W.L.T. sampled by MSDGC.

BOD 26, SS 46, D.S. 596, C.O.D. 161, NH₃ (free) 0.2, CN .024, Phen. 60 ppb, TOC 44, P.H. 7.1

- March 25, 1982: Sample(s) by IEPA: (selected) discharge pipe

BOD 42/COD 360/O₁₁ 96/TSS 33/NH₃ 1.2.1

- Run-off to Lake:

BOD 170/COD 1840/O₁₁ 700/TSS 1100/NH₃ 19.0/

OR:ds:8018C/9,sp

No. 10

U.S. Steel (South Works) IL0002691

Effective date of permit: 10/2/82

Expiration date of permit: 8/31/87

Eight permitted outfalls of which seven are discharging to Lake Michigan and one to the Calumet River via the facility's south slip. Lone discharge to the Calumet River is currently out of service (NCCW).

Discharge Number and Name:	Receiving Waters:	NPDES Limits:
001: Noncontact cooling water from a5 Power Station condenser	Lake Michigan	Fe 2/4, ZN 1/2, PH 6/9, TSS 15/30*1
002: Noncontact cooling water from a8, 11, and 12 blast furnaces and engine room compressors	Lake Michigan	PH 6/9, TSS 15/30*1, temp.
003: Noncontact cooling water from electric furnace, roof drains and storm water	Lake Michigan via North Slip	TSS 15/30*1, F.C. 400, Fe 2/4, Mag. 1/2
004: Noncontact cooling water from the basic oxygen process, and continuous caster and gas cooling tower water and roof drains and storm runoff	Lake Michigan via North Slip	Same as 002 above
005: Clarifier overflow to recycle system		PH 6/6, TSS 15/30, Gd 15, 30, Fe rept, 2M 45/1.35
005: Overflow from surge basing	Lake Michigan via North Slip	Report same as 005 and ZN, manganese
006: Process water overflow and noncontact cooling water	Calumet River via South Slip	Report same as 005 and ZN, Manganese
008: Intake screen backwash water	Lake Michigan	Report flow

Permittee has had no effluent excursions in the last year.

DR:ds:8018C/10

1981-001 1st quarter report

No. 11
Continen Grain Co. IL0037401
Effective date of permit: 11/4/79
Expiration date of permit: 7/31/84
Receiving waters: Calumet River

Treated sanitary waste to the Calumet River.

DAF = 0.005 MGD

001 Limits:	Flow	BOD 30/45	TSS 30/45	F.C. 400	P.H. 6/9	001/Domestic Waste Discharge
July '81	.003	4/16	6/11	---*1	7/7.3	*1 Not reported
Aug '81	.003	1/2	6/10	6000*2	6.7/7.4	*2 excursions(s)
Sept '81	.003	3/10	14/38	700*2	7.0/7.4	
Oct '81	.003	1/1	4/7	700*2	7.0/7.4	
Dec '81	.003	1/2	5/7	---*1	7.0/7.5	
Nov '81	.003	1/2	6/16	1500*2	7.2/7.8	

EXCURSIONS	---	---	---	4	---
------------	-----	-----	-----	---	-----

OR:ds:8018C/4.sp

No. 12

Car Carriers, Inc. IL0002721

Effective date of permit: 6/6/75

Expiration date of permit: 7/31/79

Receiving waters: Grand Calumet River

Treated sanitary waste to the Grand Calumet River. DAF 0.004 MGD. NPDES Permit expired on July 31, 1979; a renewal had not been submitted as of February 28, 1983.

No discharge monitoring reports could be found. The latest inspection was August 11, '82. A sample was taken from a manhole south of plant. Those results were:

(grab)	<u>P.H.</u>	<u>BOD</u>	<u>TSS</u>	<u>Oil</u>	<u>Res. on Evap.</u>	<u>NH3</u>	<u>NO</u> ₃	<u>+NO</u> ₂	<u>F.C.</u>
	12.1+1	<1.5	22+1	2	1046	2.9		1.4	<10

NPDES Permit limits: *2

<u>P.H.</u>	<u>BOD</u>	<u>TSS</u>	<u>D₅₀</u>	<u>F.C.</u>
6/9	4/10	5/13	15 (Max)	400

*1 excursions(s) *2 If granted an exemption BOD/TSS limits could be

	<u>Daily Average</u>	<u>Daily Max</u>
TSS	10	30
BOD	12	25

DR:ds:8018C/8,sp

APPENDIX F

Appendix F

The information for Illinois air pollution sources is contained in the IEPA data bank called the Total Air System (TAS). The TAS was established to meet a variety of needs: air quality analyses, permit reviews, setting field investigation and enforcement priorities, and special studies.

Any plant for which an air pollution permit is required is on file in the TAS. Information about a plant is organized into three basic categories: (1) information about an entire plant or facility; (2) information about a specific operation within the facility; or (3) information about an emissions source, control system or exhaust point within an operation.

The information concerning an entire facility found in the TAS includes:

- Plant name, address, city, zip code;
- Company name, address, city, state, and zip code;
- Various state, county, city, and major metropolitan area codes;
- Ownership code, plant Standard Industrial Classification (SIC), number of employees, and plant Universal Traverse Mercator (UTM) coordinates;
- Compliance status and date, plant inspection date and engineer's initials, warning letter date, and date plant ceased operation;
- Date permit received, permit expiration date, and analysis engineer's initials;
- Identity of owner and person submitting the application, and number of times processed;
- Process weight rate, operating rate, hours of operation (all maximum and average) and percent throughput by quarter;
- Heat input, percent space heat, percent sulfur and ash, and heat content;
- Uncontrolled and allowable emission rates, estimation method, and limiting rule (maximum and average) for each of the five criteria contaminants;
- Control equipment name, and control equipment codes and overall efficiency for each of the five criteria contaminants; and
- Stack height (for an effective plume height), diameter, exhaust rate, temperature, and stack UTM coordinates.

The emissions for the point source facilities in the study area are shown in the printout following this section. The various data items listed are as follows: (1) a written number identifies a plant as a major emitter (100 tons per year) of a pollutant; (2) the "Reg" and "ID" are Agency identifiers and have no particular relevance to this study; (3) the term "ST" is the status of the facility in regard to compliance with air pollution regulations:

- | | |
|-----------------------|---------------------|
| 1 = in compliance | 4 = unknown |
| 2 = not in compliance | 5 = minor violation |
| 3 = has a variance | |

(4) the term "Class" is the classification of the facility with respect to its potential to emit 100 tons per year (TPY) of any pollutant if its air pollution control devices were not operating:

Class A = has the potential to emit 100 TPY of any
single pollutant

Class B = does not have this potential; and

(5) the term "SIC" refers to the facility's Standard Industrial Classification code which identifies the primary business of the facility. A table showing the major groups of SIC codes is incorporated as Appendix G of this report. The name and address of the facility is given next and is followed by the emissions of each pollutant in tons per year. At the end of the address line following the zip code are two sets of numbers; starting with the number four, which have no consequence in this study.

ILLINOIS ENVIRONMENTAL PROTECTION AGENCY
 DIVISION OF AIR POLLUTION CONTROL
 TOTAL AIP SYSTEM
 SOUTH CHICAGO ENV. POLL. STUDY

REG	ID	SIC	SI	CLASS	NAME	PART	SO2	NOX	HC	CO
1	104 031600ASE	3251	1	A	AMERICAN BRICK CO 1400 E 138TH ST	295.6 CHICAGO	1,570.7	5.3 60627	.5 4453	1.0 46102
2	105 031600EGV	4953	2	A	AMERICAN INCINERATION INC. (ALBURN) 2200 E 119 STR	91.6 CHICAGO	.0	.0 60617	1,300.0 4523	.0 46137
3	102 031039AAA	2821	1	A	ASHLAND CHEMICAL COMPANY 142 ST & PAXTON AVE	142.0 CALUMET CITY	84.6	48.4 62501	16.8 4521	1.7 46096
4	102 031069AA1	3221	1	A	BALL GLASS CONTAINERS INC 138 ST & CUTTAGE GROVE	105.2 DOLTON	441.0	93.7 60419	12.0 4500	.0 46102
	105 031600DVV	1473	5	A	CAMECO INC. 3200 EAST 95TH STREET	2.5 CHICAGO	.0	1.5 60617	.0 4545	.0 46187
5	105 031600ANE	5153	1	A	CARGILL INC - COMMODITY MARKETING DIV 122 & TORRENCE	454.1 CHICAGO	181.0	74.5 60617	26.2 4535	6.4 46133
	105 031600CG1	2951	2	A	CHICAGO PAVING AND CONSTRUCTION CO 12701 S DUTY AVE	3.5 CHICAGO	.1	16.9 60633	.3 4497	1.6 46138
6	105 03160000Q	3295	2	A	CINDERS INC 12009 AVENUE O	135.3 CHICAGO	.0	.0 60617	.0 4550	.0 46128
7	105 031600AMJ	4912	1	A	COM ED --CALUMET PEAKING UNITS 3200 E. 100TH ST.	67.5 CHICAGO	121.3	1,916.4 60617	32.3 4546	119.7 46181
	105 031600AMQ	5153	1	A	CONTINENTAL GRAIN CO-ELEVATOR B 11700 S TORRENCE AVE	64.9 CHICAGO	.0	.0 60617	.0 4534	.0 46144
	105 031600AOE	5153	1	A	CONTINENTAL GRAIN CO-ELEVATOR C 127TH ST & CALUMET	18.6 CHICAGO	.0	.0 60633	.0 4534	.0 46132
8	102 031039AAC	2821	1	A	COSDEN OIL & CHEM CO - CALUMET CITY PLT 142ND & PAXTON	62.7 CALUMET	.0	202.2 60409	17.2 4520	8.1 46096
	105 031600BUG	2899	1	A	DOMTAR INDUSTRIES INC-SIFT TO SALT DIV 9267 SO HARBOR AVE	12.9 CHICAGO	.0	.0 60617	.0 4548	.0 46195
	105 031600DPK	5039	2	A	DUNDEE CEMENT COMPANY 3221 EAST 95TH STREET	1.2 CHICAGO	.0	.0 60617	.0 4545	.0 46187
	102 031258AAG	2865	1	A	FARCO OIL & CHEM DIV HANDSCHY INDUSTRIES 13601 S. ASHLAND AVENUE	.0 RIVERDALE	.0	.9 60627	16.8 4450	.0 46106
9	105 031600AAR	3711	5	A	FORD MOTOR COMPANY 12600 TORRENCE AVE	19.8 CHICAGO	41.7	33.3 60633	2,082.1 4533	6.7 46125
	104 031600EFR	3297	5	A	FOSECO, INC.-CHICAGO PLANT 10823 SOUTH LANGLEY AVE	6.4 CHICAGO	.0	8.0 60628	23.0 4416	.0 46155

9/08/85

ILLINOIS ENVIRONMENTAL PROTECTION AGENCY
DIVISION OF AIR POLLUTION CONTROL
TOTAL AIR SYSTEM
SOUTH CHICAGO ENV. POLL. STUDY

PAGE 2

REG	ID	SIC	ST	CLASS	NAME	PART	SO2	NOX	HC	CO
10	105 031600DET	2041	1	A	GENERAL MILLS INC 10459 MUSKEGON AVE	263.4 CHICAGO	.0	54.1 60617 4538	.9 46171	5.0
11	104 031600AAW	3743	1	A	GENERAL MOTORS - ELECTRO-MOTIVE DIV PL12 900 E 103RD STREET	2.8 CHICAGO	6.4	33.5 60628 4499	171.1 46171	.7
12	105 031600AFV	2999	1	A	GREAT LAKES CARBON CORP 2701 E 114TH ST	30.1 CHICAGO	1,642.8	.0 60617 4536	.0 46150	.0
13	105 031600BUW	3245	2	A	HECKETT ENGINEERING 112TH & TORRENCE	109.2 CHICAGO	.0	.0 60617	.0	.0
14	105 031600EFV	3245	2	A	HECKETT ENGINEERING CO DIV OF HARSCO CORP 12315 S BURLY AVE	109.1 CHICAGO	.0	.0 60633 4547	.0 46132	.0
	104 031600ADL	3341	2	A	IMPERIAL SMELTING CORPORATION 1031 E 103RD STREET	5.8 CHICAGO	.0	.0 60628 4460	.0 46171	.0
	105 031600ATE	5153	1	A	INDIANA GRAIN CO-OPERATIVE 12700 S.BUTLER DRIVE	10.6 CHICAGO	.0	.0 60633 4535	.0 46130	.0
15	105 031600AMA	3312	2	A	INTERLAKE - CHICAGO BLAST FURNACE PLANT 10730 BURLY AVE	1,052.9 CHICAGO	108.5	5,281.5 60617 4544	86.9 46163	602.3
16	105 031600BFH	3312	1	A	INTERLAKE, INC - CHICAGO COKE PLANT 11236 SOUTH TORRENCE AVE	661.3 CHICAGO	1,907.1	14.4 60617 4533	1,773.1 46152	317.8
17	102 031258AAI	3312	2	A	INTERLAKE, INC. RIVERDALE PLANT 13500 PERRY AVE.	2,394.2 RIVERDALE	585.2	1,302.2 60627 4479	41.0 46115	5,408.8
	102 031258AAK	5039	1	A	LOUISVILLE CEMENT COMPANY 1400 W 134TH STREET	6.2 RIVERDALE	.0	.0 60627 4459	.0 46110	.0
	104 031600AUJ	2641	1	A	LUDLOW SPECIALTY PAPERS-FINE PAPER DIV. 11234 S FORRESTVILLE AVE	.0 CHICAGO	.0	.0 60628 4493	73.2 46153	.0
18	105 031600ADY	3274	2	A	MANBLEHEAD LIME CO 3245 E 103RD STREET	476.1 CHICAGO	2,119.7	.0 60617 4530	.0 46173	.0
19	104 031600CKM	2645	1	A	MEAD PACKAGING 9540 SO DORCHESTER AVE	7.5 CHICAGO	.0	.0 60628 4510	286.5 46187	.0
	105 031600BUN	4463	2	A	MEDUSA CORP 12101 S DOTY AVE	1.5 CHICAGO	.0	.0 60633	.0	.0
	105 031600AED	4463	2	A	MISSISSIPPI LIME CO 12200 SOUTH STONEY AVE	9.3 CHICAGO	.0	.0 60633 4500	.0 46134	.0
	105 031600CKP	3297	1	A	NALCO CHEMICAL CO - METAL INDUSTRY CHEM 9165 SO HARBOR	1.4 CHICAGO	.4	2.1 60617 4550	10.4 46196	.4

9/08/83

 ILLINOIS ENVIRONMENTAL PROTECTION AGENCY
 DIVISION OF AIR POLLUTION CONTROL
 TOTAL AIR SYSTEM
 SOUTH CHICAGO ENV. POLL. STUDY

PAL

3

REF	ID	SIC	SI	CLASS	NAME	PART	SO2	NOX	HC	CO
20	105 031600ALC 2819 5	A			PVS CHEMICALS INC 12260 S CARONDOLET AVE	13.6 CHICAGO	141.6	30.8 60633	.4 4542	3.0 46136
21	105 031600AMC 3312 2	A			REPUBLIC STEEL CORPORATION 11600 SOUTH BUNLEY AVENUE	2,578.5 CHICAGO	1,960.5	1,962.2 60617	407.5 4546	9,381.8 46142
	105 031600AGL 4953 1	A			SCA CHEMICAL SERVICES INC 11700 STONEY ISLAND	43.9 CHICAGO	.0	46.8 60617	.0 4522	1.3 46145
22	105 031600BLY 4226 1	A			SEATANK INC. 12200 STONEY ISLAND AVE	7.0 CHICAGO	.9	89.8 60633	404.6 4530	13.1 46149
23	104 031600AMJ 2851 1	A			SHERWIN-WILLIAMS CO 11541 S. CHAMPLAIN AVE.	773.8 CHICAGO	331.1	144.1 60628	1,152.1 4494	11.4 46148
	104 031600AGW 2874 1	A			STAUFFER CHEM - WATERWAY PLANT 612 EAST 138 TH	35.1 CHICAGO	.0	2.4 60627	.0 4469	.6 46102
24	105 031600ALZ 3312 2	A			U S STEEL - SOUTH WORKS 3426 E. 89TH ST.	2,583.7 CHICAGO	259.3	4,084.9 60617	21.0 4552	26,565.6 46206
	105 031600BFD 3479 2	A			VALLEY MOLD & IRON 108TH & CALUMET RIVER STS	33.1 CHICAGO	5.8	13.1 60617	.0 4548	.0 46166
	102 031069AAP 3551 1	B			A M MANUFACTURING CO 14152 IRVING AVE	.0 DOLTON	.0	.0 60419	.0 4497	.0 46094
	104 031600EVS 2013 1	B			AGAR FOOD PRODUCTS COMPANY 700 EAST 107TH STREET	.3 CHICAGO	.0	2.8 60628	44.5 4496	.3 46165
	105 031600EXT 2999 4	B			AGLOMET(FLUE DUST HDLG-REPUBLIC STEEL) 12345 S. CARONDOLET AVE.	3.0 CHICAGO	.0	.0 60617	.0 4543	.0 46130
	102 031069AAM 3714 1	B			AGRI-CHAIN PRODUCTS INC 13943 PARK AVENUE	5.6 DOLTON	.0	36.1 60419	29.9 4494	4.9 46098
	102 031069ARF	B			AIR POLLUTION CONTROL CORP 14901 SO GREENWOOD AVE	.0 DOLTON	.0	.1 60419	.0	.0
	104 031600BKY 2899	B			AIR PRODUCTS & CHEMICALS 12721 SOUTH MENTWORTH AVE	.0 CHICAGO	.0	.0 60628	.0 4480	.0 46122
	104 031600ARY 2951 1	B			AMERICAN ASPHALT PAVING CO 700 E 120TH STREET	.0 CHICAGO	.0	.0 60628	.0 4468	.0 46137
	104 031600CTA 3471	B			AMERICAN CLYBOURN FINISHING 11730 SO FRONT AVE	.0 CHICAGO	.0	.0 60628	.0 4488	.0 46142
	104 031600ALV 7216	B			AMERICAN IDEAL CLEANING CO 10341 SO. MICHIGAN AVE	.0 CHICAGO	.0	.0 60628	.0 4484	.0 46171

4/08/83

ILLINOIS ENVIRONMENTAL PROTECTION AGENCY
DIVISION OF AIR POLLUTION CONTROL
TOTAL AIR SYSTEM
SOUTH CHICAGO ENV. POLL. STUDY

PAGE

4

REG	ID	SIC	SI CLASS	NAME	PART	SU2	NOX	HC	CO
105	0316000GL	3731	B	AMERICAN SHIP BLDG 101ST ST & CALUMET RIVER	CHICAGO .7	10.3	4.2 60617	.5 4551	.5 46178
102	031039AHK	2899 1	B	AMERICAN THERMOPLASTICS CORPORATION 142ND AND PAXTON ST	CALUMET CITY .1	.0	.0 60409	.0 4527	.0 46093
102	031258AAA	3361 1	B	ATHENTON FOUNDRY PRODUCTS INC 13000 S HALSTED ST	RIVERDALE .1	.0	.0 60627	.0	.0
104	031600CSA	3444	B	B L HARDER CO 9551 COTTAGE GROVE AVE	CHICAGO .3	2.7	1.3 60628	.0 4497	.0 46188
102	031258AAJ	4013	B	BALTIMORE & OHIO CHICAGO TERMINAL 733 W 136TH ST	RIVERDALE .6	12.1	23.9 60627	1.3 4466	.6 46106
105	031600ERB	8211	B	BD ED ADAMS SCHOOL 10810 S AVE M	CHICAGO .0	.0	.0 60617	.0 4556	.0 46162
104	031600EGE	8211	B	BD ED BENNETT SCHOOL 10115 SO PRAIRIE ST	CHICAGO .0	.0	.0 60628	.0 4486	.0 46175
105	031600ERD	8211	B	BD ED BOWEN HIGH SCHOOL 2710 E 89 ST	CHICAGO .0	.0	.0 60617	.0 4536	.0 46201
104	031600EFT	8211	B	BD ED BRENNAN SCHOOL 11411 S EGGLESTON	CHICAGO .0	.0	.0 60628	.0 4473	.0 46719
104	031600ESJ	8211	B	BD ED CARVER HIGH SCHOOL 801 E. 153RD PLACE	CHICAGO .0	.0	.0 60627	.0 4499	.0 46111
104	031600EXW	8211	B	BD ED CARVER SCHOOL 909 E 132ND ST	CHICAGO .1	.0	.0 60627	.0 4498	.0 46115
105	031600ERI	8211	B	BD ED COLES SCHOOL 8440 S PHILLIPS AVE	CHICAGO .0	.0	.0 60617	.0 4529	.0 46209
104	031600E9Z	8211	B	BD ED CURTIS SCHOOL 32 E 115 ST	CHICAGO .0	.0	.0 60628	.0	.0
105	031600ERY	8211	B	BD ED GALLISTEEL SCHOOL 10347 S EMING AVE	CHICAGO .0	.0	.0 60617	.0 4554	.0 46171
104	031600ERA	8211	B	BD ED KOHN SCHOOL 10414 S STATE ST	CHICAGO .0	.0	.0 60628	.0 4480	.0 46169
104	031600DVE	8211	B	BD ED LANGSTON HUGHES SCHOOL 226 WEST 104TH STREET	CHICAGO .4	.1	.2 60628	.2 4474	.6 46171
105	031600EFS	8211	B	BD ED MANN SCHOOL 8050 S CHAPPEL	CHICAGO .0	.0	.0 60617	.0 4521	.0 46216

ILLINOIS ENVIRONMENTAL PROTECTION AGENCY
 DIVISION OF AIR POLLUTION CONTROL
 TOTAL AIR SYSTEM
 SOUTH CHICAGO ENV. POLL. STUDY

RFG	ID	STC	ST CLASS	NAME	PART	SO2	NOX	HC	CO
104	031600ERC	8211	B	BD ED PJE SCHOOL 10538 S LANGLEY AVE	CHICAGO .0	.0	.0 60628	4495	.0 46166
104	031600ESS	8211	B	BD ED PULLMAN SCHOOL 11311 S FORREST VILLE AVE	CHICAGO .0	.0	.0 60628	4493	.0 46151
104	031600UGP	8211	B	BD ED SCANLAN SCHOOL 11725 S PERRY AVE	CHICAGO .3	.0	.0 60628		.0
105	031600LEM	8211	B	BD ED TAYLOR SCHOOL 99TH & AVE H	CHICAGO .0	.0	.0 60617	4556	.0 46180
104	031600DSV	8211	B	BD ED THEOPHILUS SMITH SCHOOL 9755 SOUTH GREENWOOD AVE	CHICAGO .0	.0	.0 60628		.0
105	031600DFI	8211	B	BD ED WILLIAM K SULLIVAN SCHOOL 8255 S. HOUSTON	CHICAGO .0	.0	.0 60617		.0
102	031069ABI	2511	1	BEACH BROOK FURNITURE 14825 SOUTH DREXEL	DOLTON .0	.0	.0 60419		.0
102	031069ARE		B	BERGER-VANDENBERG SCHOOL 14833 AVALON	DOLTON .2	.0	.0 60419		.0
104	031600ASL	3255	1	BLACK PRODUCTS CO 13513 SO CALUMET AVE	CHICAGO 3.1	.0	.0 60627	4487	3.8 46110
102	031258AAC	3547	1	BONELL MANUFACTURING CO 13521 S HALSTED ST	RIVERDALE .1	.4	.0 60627	4466	1.1 46109
102	031069AAH	2819	1	BREDDO FOOD PROD CORP DIVISION I T C 14622 LAKESIDE	DOLTON .3	.0	8.3 60419	4490	.1 46084
102	031039AAT	2011	B	BROWN PACKING COMPANY 15800 GREENWOOD ROAD	CALUMET CITY .0	.0	.0 60409		.0
102	031039AMS	7216	B	BURNHAM CLEANERS 224 GOLD COAST LANE	CALUMET CITY .0	.0	.0 60409		11.7
102	031036AAD	3315	1	BURNHAM STEEL & WIRE 14146 SO MACKINAW	BURNHAM .0	.0	.0 60633		.0
105	031600CHX	2511	5	BUTLER SPECIALTY 8200 S. CHICAGO AVE.	CHICAGO 6.4	.0	1.1 60617	4519	62.0 46215
102	031039AAV		1	C I D LANDFILL 136TH STREET & CALUMET EX	CALUMET CITY .0	.0	.0 60409		.0
102	031258AAZ		4	CALUMET ARMATURE & ELECTRIC CO 1050 W 134TH ST	RIVERDALE .0	.0	.1 60627		1.6

9/08/93

ILLINOIS ENVIRONMENTAL PROTECTION AGENCY
DIVISION OF AIR POLLUTION CONTROL
TOTAL AIR SYSTEM
SOUTH CHICAGO ENV. POLL. STUDY

PAGE 6

REG	ID	STC	ST CLASS	NAME	PART	SU2	NOX	HC	CO
102	031069AAE	3362	1	B CALUMET BRASS FOUNDRY INC 14610 LAKESIDE	2.7 DOLTON	.0	.0 60419 4491	.0 46085	.0
102	031039AAZ	3271	2	B CALUMET READY-MIX BURNHAM AVE & STATE STR	.1 CALUMET CITY	.0	.0 60409	.0	.0
102	031036AAA	2992	1	B CALUMET REFINING CO 13921 WACKINAW AVE	.4 BURNHAM	.0	6.0 60633	.0	.4
104	031600DIA	6513		B CHA-ALIGELD GARDENS VANTUUS	.0 CHICAGO	.0	.0 60627	.0	.0
104	031600DJA	6513		B CHA-PHILIP MURRAY HOMES ILL 2-11 660 E 133RD ST	.0 CHICAGO	.0	.0 60627	.0	.0
105	031600CLU	6513	2	B CHA-TRUMBULL PARK HOMES NUMERONS	3.0 CHICAGO	27.3	18.6 60617 4530	.4 46164	1.7
105	031600DTE		1	B CHEM-CLEAR 11800 SOUTH STONEY ISLAND	.0 CHICAGO	.0	.0 60617	.0	.0
102	031258ABA	1629		B CHEMICAL WASTE MANAGEMENT-TECH CENTER 150 W 137TH ST	.0 RIVERDALE	.0	.0 60627	.0	.0
105	031600CST	4013		B CHICAGO ROCK ISLAND PACIFIC RAILROAD CO 95TH ST AND ESSEX AVE	.0 CHICAGO	.0	.0 60617 4531	.0 46188	.0
105	031600CSS	4013		B CHICAGO ROCK ISLAND PACIFIC RAILROAD CO 95TH AND OGLESBY ST	.0 CHICAGO	.0	.0 60617 4527	.0 46188	.0
105	031600CSH	4013		B CHICAGO ROCK ISLAND PACIFIC RAILROAD CO 95TH AND CULFAX AVE	.0 CHICAGO	.0	.0 60617 4533	.0 46188	.0
105	031600DTM	2092	1	B CHICAGO SHORTING CORP 9101 S BALTIMORE AVENUE	1.7 CHICAGO	11.2	22.4 60617 4543	.4 46196	3.2
104	031600DLX	8221	1	B CHICAGO STATE UNIVERSITY NINETY-FIFTH ST KINGDRIVE	3.5 CHICAGO	.0	14.0 60628 4489	.0 46188	3.5
105	031600ASU	3315	1	B CHICAGO STEEL & WIRE - DIV KEYSTONE 10257 S TORRENCE AVE	1.8 CHICAGO	.0	.0 60617 4461	.0 46191	.0
105	031600ENA	3547	2	B CHICAGO STEEL AND PICKLING CO 12500 SO STONY ISLAND	.0 CHICAGO	.0	.0 60633	.0	.0
104	031600CFH	4941	1	B CHICAGO WATER DEPT - ROSELAND PUMPING ST 351 W 104TH ST	3.9 CHICAGO	.0	49.4 60628 4474	1.0 46170	6.4
102	031036AAF		2	B CITY OF BURNHAM CITY HALL	.0 BURNHAM	.0	.0 60633	.0	.0

ILLINOIS ENVIRONMENTAL PROTECTION AGENCY
 DIVISION OF AIR POLLUTION CONTROL
 TOTAL AIR SYSTEM
 SOUTH CHICAGO ENV. POLL. STUDY

REG	ID	SIC	SI	CLASS	NAME	PART	SO2	NOX	HC	CO	
105	031600ECU	2643	1	B	CLEAR-VIEW PLASTICS INC 1650 E 95 STR	CHICAGO	.0	.0	.1	.0	.0
102	031600AAF	2631	1	B	CONTAINER CORPORATION OF AMERICA 301 E 144 STREET	DOLTON	.8	.0	.0	.0	.0
104	031600EXB	5093	1	B	CRYOGENICS INC 11900 SOUTH COTTAGE GROVE	CHICAGO	.0	.0	.0	.0	.0
105	031600EZY		2	B	DEEMSTER ROER 3200 E 106TH STREET	CHICAGO	.0	.0	.0	.0	.0
105	031600DDL	7216		B	DELUXE CLEANERS 3046 E 92ND ST	CHICAGO	.0	.0	.0	.0	.0
102	031039AAN	2833	5	B	DYNAGEL INC WENTWORTH AND PLUMMER	CALUMET CITY ILLINOIS	.8	.0	32.0	1.7	2.5
105	031600FAH	7216		B	ELLIS CLEANERS 3026 EAST 91ST STREET	CHICAGO	.0	.0	.0	.0	.0
105	031600BMF	4953	2	B	ELM TREE FOODS 11207 EWING AVENUE	CHICAGO	.0	.0	.0	.0	.0
102	031039AAF	2819	1	B	ESTECH GENERAL CHEMICALS CORP 150 MARBLE ST	CALUMET CITY	.0	.0	.0	.0	.0
104	031600ETR	3441		B	FABRICATING AND WELDING COMP 12206 S. HALSTED ST.	CHICAGO	.0	.0	.0	.0	.0
105	031600AWJ	2083	5	B	FALSTAFF BREWING COMPANY 103RD ST & INDIANAPLS BLV	CHICAGO	.0	.0	.0	.0	.0
102	031258AAY	3540		B	FEM TOOL & DIE CO 13417 S HALSTED ST	RIVERDALE	.0	.0	.0	.0	.0
104	031600CYM	7216		B	FLAIR CLEANERS 11518 SO MICHIGAN	CHICAGO	.0	.0	.0	17.5	.0
105	031600ERU	3462		B	FORGED TOOTH GEAR CO 10241 SO COMMERCIAL	CHGO	.1	.0	.0	.0	.0
102	031258AAE	2499	1	B	FRANK MILLER AND SONS INC 13831 SOUTH EMERALD AVE	RIVERDALE	.1	.0	1.5	.0	.0
104	031600BMP	3563		B	FRANKS PAUL & DRUM SERVICE 545 W 119TH ST	CHICAGO	.1	.0	.0	16.8	.0
102	031258AAX	5093	5	B	FRITZ ENTERPRISES INC 1200 WEST 138 STREET	RIVERDALE	26.4	.0	.0	.0	.0

ILLINOIS ENVIRONMENTAL PROTECTION AGENCY
 DIVISION OF AIR POLLUTION CONTROL
 TOTAL AIR SYSTEM
 SOUTH CHICAGO ENV. POLL. STUDY

REG	ID	STC	SI	CLASS	NAME	PART	SO2	NOX	HC	CO
105	031600BTZ	2	B		GALLITEL SCHOOL 10307 SO EWING	CHICAGO .0	.0	.0	.0	.0
104	031600EPN 3281		B		GALLOU & VAN ETEN, INC 11756 S HALSTED ST	CHICAGO .0	.0	.0	.0	.0
102	031066AAH 3317 1		B		GENERAL TUBE CORP 139TH AND SEELEY BOX27036	DIXMOOR 39.6	.0	.0	.0	.0
102	031039AHQ	3	B		GETTY SYNTHETIC FUELS INC P O BOX 1306	CALUMET CITY .0	.0	33.1	13.9	19.6
102	0310694AK 2911		B		GETTY SYNTHETIC FUELS INC 138TH ST & COTTAGE GROVE	DOLTON .0	.0	.0	.0	.0
102	031258AAS 3295 2		B		HECKETT ENGINEERING (HARSCO) PLANT 27 135TH ST AND PERRY AVENUE	RIVERDALE, IL 11.6	.0	.0	.0	.0
105	031600CHV 3441		B		HIBBEN & CO 9376 EWING AVE	CHICAGO .0	.0	.0	.0	.0
102	031036AAD 3357 1		B		HOFFMAN INSULATION MFG CO. MARTHA & EXCHANGE AVE	BURNHAM .1	.0	.0	.0	.0
105	031600BAS 2291 1		B		IND MANUFACTURING INC. 2648 EAST 126 STREET	CHICAGO .0	.0	.0	.0	.0
105	031600BSU	1	B		ILLINOIS SCRAP IND INC 9331 S EWING	CHICAGO .0	.0	.0	.0	.0
105	031600ADJ 3295 1		B		ILLINOIS SLAG AND BALLAST CO 2817 E 99TH STREET	CHICAGO 1.6	.0	.0	.0	.0
104	031600ASH 3341 1		B		INLAND METALS REFINING COMPANY 651 E. 119TH ST	CHICAGO .0	.0	.0	.0	.0
105	031600CKL 3295 2		B		INTERNATIONAL MILL SERVICE INC BOX 17105	CHICAGO .0	.0	.0	.0	.0
102	031258AAI 4463 1		B		INTERNATIONAL MINERALS & CHEMICAL CO 130TH & INDIANA	RIVERDALE 16.9	.0	.0	.0	.0
105	031600AUB 3341 1		B		INTERSTATE SMELTING & REFINING CO 9651 S TURRENCE	CHICAGO .0	.0	.0	.0	.0
104	031600AVM 2099 1		B		JAYS FOODS INC 825 E 99TH ST	CHICAGO 47.0	.0	.0	.0	.0
105	031600ETC 3559 2		B		JOHN MOHR & SONS 3200 E 96TH STREET	CHICAGO .1	5.1	5.0	.2	.9

ILLINOIS ENVIRONMENTAL PROTECTION AGENCY
 DIVISION OF AIR POLLUTION CONTROL
 TOTAL AIR SYSTEM
 SOUTH CHICAGO ENV. POLL. STUDY

REG	ID	SIC	SI	CLASS	NAME	PART	SO2	NOX	HC	CO
102	031039ARA		B		JOHNSON TRUCK SERVICES INC 453 COMMERCIAL AVE	.0 CALUMET CITY	.0	.0 60409	.0	.0
102	031069AAD	3341	1	B	KAISER ALUMINUM & CHEMICAL CORP-DOLTON 142 & COTTAGE GROVE	12.2 DOLTON	.0	11.9 60419	.4 4503	.4 46095
104	031600DDI	2077	1	B	KAPPA PRODUCTS CORP 1301 E 99TH ST	.0 CHICAGO	4.0	.0 60628	.0 4454	.0 46179
104	031600CKU	2899	1	B	KAYE CONTRACT PACKAGING CORP 340 E 138TH ST	.3 CHICAGO	.0	.0 60627	.0 4482	.0 46102
104	031600EPI	2099	B		KEEBLER CO - ILLINOIS BAKING DIVISION 10839 S LANGLEY	.0 CHICAGO	.0	.0 60628	.0	.0
105	031600DSU	3295	2	B	LAKE SIDE SLAG SOUTH SHORE DOCK	.0 CHICAGO	.0	.0 60617	.0 4552	.0 46206
102	031069ARM	5052	1	B	LAKES-RIVERS DOLTON DOCK 140TH COTTAGE GROVE	.0 DOLTON	.0	.0 60419	.0	.0
105	031600CKJ	2813	2	B	LIQUID AIR CORP 10924 SO TURKENCE AVE	.0 CHICAGO	.0	.0 60617	.0 4534	.0 46160
102	031039AAE	2813	1	B	LIQUID CARBONIC CORP. 2000 W.DOLTON	.0 CALUMET CITY	.0	.0 60409	.0 0777	.0 00539
102	03125RAAP	5171	1	B	LIQUID TERMINALS 520 W 138TH ST	.0 RIVERDALE	.0	.0 60627	.0 4466	.0 46106
105	031600COW	4612	1	B	MARATHON PIPE LINE CO-LAKE CALUMET DOCK 2530 E 130TH ST	.0 CHICAGO	.0	.0 60633	.0	.0
102	031066AAJ	5093	2	B	MARFAX RAILWAY EQUIPMENT CO INC 2247 W 139TH STREET	.0 DIXMOOR	.0	.0 60627	.0	.0
104	031600DCV	2842	2	B	MASURY COLUMBIA CO 1140 E 103 STREET	2.2 CHICAGO	.0	2.2 60628	.0 4500	.4 46171
102	031069ABG	5171	1	B	MCKESSON CHEMICAL 634 EAST 138TH ST	.0 DOLTON	.0	.0 60419	.0	.0
102	031069AAJ	2851	1	B	MCKESSON CHEMICAL CO 633 E DOLTON	4.4 DOLTON	10.5	19.2 60419	18.4 4496	.9 46102
105	031600BNJ	3316	4	B	METRON STEEL CORP 12900 SO METHON DR	.0 CHICAGO	.0	.0 60633	.0	.0
104	031600DQV	4952	B		METROPOLITAN SANITARY DIST - CALUMET ST 125TH ST & INDIANA AVE.	.0 CHICAGO	.0	.0 60628	.0 4492	.0 46125

9/08/83

ILLINOIS ENVIRONMENTAL PROTECTION AGENCY
DIVISION OF AIR POLLUTION CONTROL
TOTAL AIR SYSTEM
SOUTH CHICAGO ENV. POLL. STUDY

PAGE 10

REG	ID	SIC	ST CLASS	NAME	PART	SU2	NOX	HC	CO
104	03160000J	4952	B	METROPOLITAN SANITARY DIST - CALUMET WKS 400 E 130TH ST.	CHICAGO .0	.0	.0	.0	.0
							60628	4492	46123
105	03160000M	4952	B	METROPOLITAN SANITARY DIST - 95TH ST ST 9512 S. BALTIMORE AVE.	CHICAGO .0	.0	.0	.0	.0
							60617	4544	46188
102	03125RAAN	3399 1	B	MIDWEST SINTERED PRODUCTS CORP 13605 SO HALSTED ST	RIVERDALE .0	.0	.3	4.0	.0
							60627	4466	46105
104	03160000B	7216	B	MONARCH LAUNDRY CO 140 W 111ST STREET	CHICAGO .0	.5	2.8	.7	1.4
							60628	4478	46155
104	0316000BE	2515 1	B	NACHMAN CORPORATION 901 E 104TH ST	CHICAGO 1.2	.0	.0	.0	.0
							60628	4388	46406
105	0316000CEY	4013	B	NORFOLK & WESTERN RAILWAY CO 2040 E 106TH ST	CHICAGO .0	.0	.0	.0	.0
							60617	4524	46164
102	031039AMK	3297 1	B	OGLEBY MORTON CO-FERRO ENGINEERING DIV 602 STATE STREET	CALUMET CITY .0	.0	.0	.0	.0
							60409		
104	03160000B	2653 1	B	OWENS ILLINOIS CHICAGO ROX PLANT 53 440 E 130TH STREET	CHICAGO .8	.0	14.7	.0	2.9
							60627	4493	46103
104	03160000D	3241 2	B	PASCHEN-NEUBERG-FOSTER 400 EAST 130TH STREET	CHICAGO 10.9	.0	.0	.0	.0
							60628		
105	03160089A		B	PEOPLES GAS LIGHT & COKE CO - CALUMET ST 3200 E 98TH ST	CHICAGO .0	.0	.4	.0	.0
							60617		
105	0316000WM	3433	B	PHIL'S FOOD CENTER INC 13209 SO BALTIMORE AVE	CHICAGO .8	.0	.0	.0	.0
							60633		
104	0316000LM	3743 1	B	PULLMAN-STANDARD DIVISION 720 E 111TH STREET	CHICAGO 1.5	11.5	6.5	.0	.8
							60628	4493	46155
102	031036AAE	3743 1	B	PURDY COMPANY BRINARD AVENUE	BURNHAM .9	.0	.0	.0	.0
							60633		
105	0316000EU	2041 2	B	RAIL TO WATER TRANSFER CORP. 3017 EAST 102 STREET	CHICAGO .0	.0	.0	.0	.0
							60617	4543	46175
105	0316000AM1	4463 1	B	RAIL-TO-WATER CORPORATION E. 101ST ST & CALUMET RIV	CHICAGO 10.2	.0	.0	.0	.0
							60617	4548	46179
105	0316000EXM	3694 5	B	RELIABLE ARMATURE SERVICE 10115 S TOMPENCE AVE	CHICAGO .0	.0	.0	.0	.0
							60617		
102	03125PAAL	2813 1	B	RIVERDALE IND. GASES 14150 S HALSTED ST	RIVERDALE .0	.0	.0	.0	.0
							60627	4464	46096

ILLINOIS ENVIRONMENTAL PROTECTION AGENCY
 DIVISION OF AIR POLLUTION CONTROL
 TOTAL AIR SYSTEM
 SOUTH CHICAGO ENV. POLL. STUDY

REG	ID	SIC	ST	CLASS	NAME	PART	SO2	NOX	HC	CO
102	031258AAM	3471	1	B	RIVERDALE PLATING AND HEAT TREATING CO 680 W 134TH STREET	19.4 CHICAGO	.0	3.2 60627 4467	1.1	.0 46110
105	031600BMX		5	B	S H BELL CO 10218 SOUTH AVE U	.0 CHICAGO	.0	.0 60617	.0	.0
105	031600EUD	8661		B	SACRED HEART CHURCH SCHOOL 96TH ST AND S EXCHANGE	.0 CHICAGO	.0	.0 60617 4539	.0	.0 46187
102	031069ABC	8211		B	SCHOOL DIST 149 - DIEKMAN SCHOOL 15121 DORCHESTER AVENUE	.4 DOLTON	.0	.0 60419 4514	.0	.0 46075
102	031039AAP	8211		B	SCHOOL DIST 149 - DIRKSEN JUNIOR H S 154TH ST AND MICH CITY RD	.0 CALUMET CITY	.0	.0 60409 4528	.0	.0 46071
102	031039AAS	8211		B	SCHOOL DIST 149 - SANDRIDGE SCHOOL 600 UGLESRY	.4 CALUMET CITY	.0	.0 60409 4529	.0	.0 46076
104	031600DNY	6512	2	B	SECRETARY OF STATE - DRIVER FACILITY 9901 DR MARTIN LUTHER KING	.0 CHICAGO	7.6	.0 60628 4489	.0	.0 46180
105	031600SSK			B	SERVICE STATION ID NUMBER REG 1 DIST 05	.0 DUMMY ID NUMBER	.0	.0 60617	.0	.0
102	031036SSI			B	SERVICE STATION ID NUMBER REG 1 DIST 02	.0 DUMMY ID NUMBER	.0	.0 60000	.0	.0
104	031600DNY	2654	1	B	SOLO CUP COMPANY 1501 E. 96TH ST.	3.4 CHICAGO	.0	.0 60628 4452	.0	.0 46769
105	031600BRX			B	SOUTH CHICAGO COMMUNITY HOSPITAL 2320 EAST 93RD ST	.6 CHICAGO	1.2	1.3 60617	1.3	4.4
104	031600AYA	3341	1	B	STAINLESS PROCESSING CO 11900 SOUTH COTTAGE GROVE	.0 CHICAGO	.0	.0 60628	.0	.0
102	031066AAJ		1	B	STANFA TIRE CO 14249 WESTERN AVE	.0 DIXMOOR	.0	.3 60627	.0	.0
104	031600CEH	2851	1	B	STUART CHEMICAL & PAINT INC 11740 S FRONT ST	.0 CHICAGO	.0	.0 60628 4415	.0	.0 46323
104	031600CIN	2051	1	B	TORTINO BAKING CO 210 S WASHINGTON	.0 CHICAGO	.0	2.0 60628 4485	.0	.0 46146
102	031039AAX	3499	1	B	TRANSCO INC 700 STATE ST	.0 CALUMET CITY	.0	.0 60409	.0	.0
102	031069AAC	3412		B	U S STEEL CORP 14700 HARVARD AVE	.0 DOLTON	.0	.0 60419 4472	.0	.0 46083

4/08/83

ILLINOIS ENVIRONMENTAL PROTECTION AGENCY
DIVISION OF AIR POLLUTION CONTROL
TOTAL AIR SYSTEM
SOUTH CHICAGO ENV. POLL. STUDY

PAGE 12

REF	ID	SIC	SI	CLASS	NAME	PART	SO2	NOX	HC	CO
105	031600EXC	2	B		U S STEEL SUPPLY DIVISION 13535 S TORRENCE	CHICAGO .0	.0	4.5 60633	.0	.4
104	031600ECE	3714	4	B	UNITED AIR CLEANER CO 9705 COTTAGE GROVE	CHICAGO .0	.0	.0 60628 4498	9.8 46185	.0
105	031600CFW	3317	1	D	WELDED TUBE CO OF AMERICA 1845 E 122ND ST	CHICAGO .0	.0	.0 60633	.0	.0
102	031039AAK	5399	B		WENTWORTH WOODS SHOPPING CENTER 231 GOLD COAST LANE	CHICAGO .1	.0	.0 60409	.0	.2
104	031600EZA	1	B		WEST PULLMAN IRON & METAL 11956 S PEORIA	CHICAGO .0	.0	.0 60628	.0	.0
105	031600AMB	3312	1	B	WISCONSIN STEEL WORKS 2800 E 106TH ST	CHICAGO 4.4	.0	.0 60617 4538	.0 46162	.0
105	031600ESZ	4226	B		X-RAIL SYSTEMS INC - CHICAGO TERMINAL 2050 E 104TH ST	CHICAGO .0	.1	.0 60617 4520	.0 46170	.0

194 RECORDS PRINTED

APPENDIX G

Appendix G
Standard Industrial Classification Codes

- Division A. Agriculture, forestry, and fishing
Major Group 01. Agricultural production - crops
Major Group 02. Agricultural production - livestock
Major Group 07. Agricultural services
Major Group 08. Forestry
Major Group 09. Fishing, hunting, and trapping
- Division B. Mining
Major Group 10. Metal mining
Major Group 11. Anthracite mining
Major Group 12. Bituminous coal and lignite mining
Major Group 13. Oil and gas extraction
Major Group 14. Mining and quarrying of nonmetallic minerals, except fuels
- Division C. Construction
Major Group 15. Building construction - general contractors and operative builders
Major Group 16. Construction other than building construction - general contractors
Major Group 17. Construction - special trade contractors
- Division D. Manufacturing
Major Group 20. Food and kindred products
Major Group 21. Tobacco manufacturers
Major Group 22. Textile mill products
Major Group 23. Apparel and other finished products made from fabrics and similar materials
Major Group 24. Lumber and wood products, except furniture
Major Group 25. Furniture and fixtures
Major Group 26. Paper and allied products
Major Group 27. Printing, publishing, and allied industries
Major Group 28. Chemicals and allied products
Major Group 29. Petroleum refining and related industries
Major Group 30. Rubber and miscellaneous plastic products
Major Group 31. Leather and leather products
Major Group 32. Stone, clay, glass, and concrete products
Major Group 33. Primary metal industries
Major Group 34. Fabricated metal products, except machinery and transportation equipment
Major Group 35. Machinery, except electrical
Major Group 36. Electrical and electronic machinery, equipment, and supplies
Major Group 37. Transportation equipment
Major Group 38. Measuring, analyzing, and controlling instruments; photographic, medical and optical goods; watches and clocks
Major Group 39. Miscellaneous manufacturing industries

- Division E. Transportation, communications, electric, gas, and sanitary services
- Major Group 40. Railroad transportation
 - Major Group 41. Local and suburban transit and interurban highway passenger transportation
 - Major Group 42. Motor freight transportation and warehousing
 - Major Group 43. U.S. Postal Service
 - Major Group 44. Water transportation
 - Major Group 45. Transportation by air
 - Major Group 46. Pipe lines, except natural gas
 - Major Group 47. Transportation services
 - Major Group 48. Communication
 - Major Group 49. Electric, gas, and sanitary services
- Division F. Wholesale trade
- Major Group 50. Wholesale trade - durable goods
 - Major Group 51. Wholesale trade - nondurable goods
- Division G. Retail trade
- Major Group 52. Building materials, hardware, garden supply, and mobile home dealers
 - Major Group 53. General merchandise stores
 - Major Group 54. Food stores
 - Major Group 55. Automotive dealers and gasoline service stations
 - Major Group 56. Apparel and accessory stores
 - Major Group 57. Furniture, home furnishings, and equipment stores
 - Major Group 58. Eating and drinking places
 - Major Group 59. Miscellaneous retail
- Division H. Finance, insurance, and real estate
- Major Group 60. Banking
 - Major Group 61. Credit agencies other than banks
 - Major Group 62. Security and commodity brokers, dealers, exchanges, and services
 - Major Group 63. Insurance
 - Major Group 64. Insurance agents, brokers, and service
 - Major Group 65. Real estate
 - Major Group 66. Combinations of real estate, insurance, loans, law offices
 - Major Group 67. Holding and other investment offices
- Division I. Services
- Major Group 70. Hotels, rooming houses, camps, and other lodging
 - Major Group 72. Personal services
 - Major Group 73. Business services
 - Major Group 75. Automotive repair, services, and garages
 - Major Group 76. Miscellaneous repair services
 - Major Group 78. Motion pictures
 - Major Group 79. Amusement and recreation services, except motion pictures
 - Major Group 80. Health services

Major Group 81. Legal services
Major Group 82. Educational services
Major Group 83. Social services
Major Group 84. Museums, art galleries, botanical and
zoological gardens
Major Group 86. Membership organizations
Major Group 88. Private households
Major Group 89. Miscellaneous services
Division J. Public administration
Major Group 91. Executive, legislative, and general
government, except finance
Major Group 92. Justice, public order, and safety
Major Group 93. Public finance, taxation, and monetary policy
Major Group 94. Administration of human resource programs
Major Group 95. Administration of environmental quality and
housing programs
Major Group 96. Administration of economic programs
Major Group 97. National security and international affairs
Division K. Nonclassifiable establishments
Major Group 99. Nonclassifiable establishments

APPENDIX H

APPENDIX H

Chicago Area
Composite Exhaust Lead Emission Factors for Stop-and-Go, City-Type Traffic
(Lead in Grams Per Thousand Vehicle Miles)

Average Vehicle Speed (mph)

<u>Calendar Year</u>	<u>5</u>	<u>00</u>	<u>05</u>	<u>20</u>	<u>25</u>	<u>30</u>	<u>35</u>	<u>40</u>	<u>45</u>	<u>50</u>	<u>55</u>
1974	269.64	165.72	130.29	112.85	102.51	96.17	91.54	88.34	86.13	85.08	85.71
1975	267.22	165.40	129.83	112.46	102.44	96.01	91.29	88.14	85.86	84.80	85.28
1976	243.89	150.96	119.25	103.51	94.42	90.67	84.11	81.17	79.13	78.06	78.63
1978	166.14	104.39	82.39	72.16	66.30	62.22	59.33	57.44	56.27	60.98	61.15
1983	45.28	30.53	25.98	22.62	21.30	20.31	19.73	19.17	18.99	20.14	20.19
1985	43.34	31.17	25.76	22.77	22.10	21.62	20.76	19.90	19.80	19.78	19.87

Area/Roadway Type: Chicago, arterials

Vehicle Mix: 89.9 percent LDV, 4.4 percent LDT, 3.2 percent HDG, 2.5 percent HDD and MC

Percent of Lead Exhausted - a_s : 70 percent assumed for arterials under city-type driving conditions

Traffic Flow: Assumed stop-and-go, city-type driving; $c_t = 0.866$

Southeast Chicago (Steel Mills) Study Area

Area Source Emissions Data Summary

(Tons Per Year)

<u>Year</u>	<u>0978</u>	<u>0983</u>	<u>0985</u>
<u>Freeway</u>			
Exhaust	11.74	3.71	3.64
Reentrainment	<u>5.86</u>	<u>0.85</u>	<u>0.82</u>
Total	17.61	5.56	5.46
<u>Arterial</u>			
Exhaust	21.44	6.01	6.69
Reentrainment	<u>00.68</u>	<u>2.99</u>	<u>3.33</u>
Total	<u>32.03</u>	<u>9.00</u>	<u>00.02</u>
Total Lead Emissions	49.74	14.56	15.48

Grid Summary: 247 Freeway Grids
547 Arterial Grids
17 Combination Grids

811 Total Grids

Southeast Chicago (Steel Mills) Study Area
Point Source Emissions Inventory

Facility Name ID Number	CDM Source Number	Source Name	Permit Number	Stack No.	Lead Emissions (T/Y)		
					0978	0983	0985
U.S. Steel 031600ALZ	1	Electric Arc Furnace	3110009	1,3	1.5	1.4	.9
	2	No. 11 Blast Furnace	3110127	2	nil	nil	nil
	3	No. 10 Blast Furnace	3110127	3	nil	nil	nil
	4	No. 8 Blast Furnace	3110127	4	nil	nil	nil
	5	No. 12 Blast Furnace	3110127	5	nil	nil	nil
	6	No. 8 Blast Furnace	3110127	6	16.5	12.4	9.4
	7	Flue Dust Storage Piles	3110127	8	nil	nil	nil
	8	BOP	3110180	1,2,3	4.9	3.6	2.8
	9	BOP	3110180	2,4	2.0	1.5	1.1
	10	Electric Arc Furnace	4050012	1	nil	nil	nil
	11	Sinter Plant Windbox	5050147	1	.5	.4	.3
	12	Sinter Plant Breakerbox	5050147	2	nil	nil	nil
		Total			25.4	19.3	14.5
Interlake Steel- Blast Furnace Plant 031600AMA	13	Blast Furnace A	2090059	1	nil	nil	nil
	14	Blast Furnace B	2090059	2	.1	.1	.1
	15	Sinter Plant Windbox	3070079	1	3.6	4.7	4.7
	16	Sinter Cooler and Screens	3070079	2	.1	.1	.1
	17	Sinter Plant Breakerbox	3070079	1	.4	.6	.6
	18	Unpaved Roads	9990530	1	nil	nil	nil
	19	Mill Fines Storage Piles	9990530	2	nil	nil	nil
	20	Blast Furnace Dust Storage Piles	9990530	3	nil	nil	nil
	21	Sinter Machine Discharge and Screens	9990530	4	nil	nil	nil
	22	Sinter Cooler	9990530	5	nil	nil	nil
	23	Sinter Handling	9990530	6	nil	nil	nil
		Total			4.2	5.5	5.5
Wisconsin Steel 031600AMB	24	BOF	2090090	1	31.8	20.1	10.8
	25	No. 1 Blast Furnace	2090101	4	nil	nil	nil
	26	No. 2 Blast Furnace	2090101	5	nil	nil	nil
	27	No. 2 Blast Furnace	2090101	6	nil	nil	nil
		Total			31.8	20.1	10.8
Republic Steel 031600AMC	28	Blast Furnace	2100325	1	nil	nil	nil
	29	Coke Oven Combustion Stack	4020078	4	.1	.1	.1
	30	Coke Oven Doors	4020078	5	.1	.1	.1
	31	Q-BOP Furnace Stack	7100054	1,11	1.3	1.2	1.2
	32	Q-BOP Furnace No. 2	8010054	1,11	1.3	1.2	1.2
	33	3-225 Ton Electric Arc Furnace	8060013	1	2.8	2.7	2.6
	34	Unpaved Roads	9990532	1	.6	.6	.6
		Total			6.2	5.9	5.8
		Study Area Total			67.5	50.8	36.6

APPENDIX I

UNITED STATES ENVIRONMENTAL PROTECTION AGENCY
REGION V

DATE: SEP 28 1983

SUBJECT: Core Sampling Southeast Side - Chicago, Illinois

FROM: William H. Sanders III, Director
Environmental Services Division

TO: Charles H. Sutfin, Director
Water Division

Attached is the report on the core sampling survey conducted by Central District Office on the southeast side of Chicago, Illinois, during the week of June 6, 1983. This survey was requested by the Dredge and Fill Section.

The results of the survey indicate that two of the sampling locations had high metal concentrations. One of the locations was used by Interlake Steel to dispose of the steel mill's waste. The other location is in the flood plain of the Calumet River.

Polynuclear aromatic hydrocarbons were detected at a number of the sampling locations. Since this class of compound are residues of coal tar, it is believed that the compounds were caused by air pollution from the steel mills in this area.

Copies of this report and the reports of the water sampling surveys conducted in this area have been provided to CDC for a health impact assessment.



William H. Sanders III, Director

Attachments

cc: Kenneth Fenner, WQ
Elmer Shannon, WQD

REPORT OF SURVEY FOR THE U.S.
ENVIRONMENTAL AGENCY'S CORE SAMPLING SOUTHEAST SIDE
CHICAGO, ILLINOIS

U.S. ENVIRONMENTAL PROTECTION AGENCY

REGION V

ENVIRONMENTAL SERVICES DIVISION

CENTRAL DISTRICT OFFICE

CHICAGO, ILLINOIS

JUNE 1983

1. INTRODUCTION

The Water Division requested that sediment core samples be collected in the wetlands and drainage area on the southeast side of Chicago, Illinois. Considerable public interest in the environment of this area has developed over the last year. The objectives of the survey were to determine the degree of contamination of the wetlands near the active landfills and the proposed landfills, characterize the discharge into the Calumet River from drainage ditches along side of the Norfolk and Western Railroad tracks and, if any, characterize the leachate from Paxton Landfill. There was no leachate from Paxton Landfill; therefore, these samples were not collected.

2. SCOPE

The study area is located in southeast Chicago, Illinois. The area is bounded by 103rd Street on the north, 146th Street on the south, Avenue "O" on the east, and Stony Island Avenue extended on the west (See maps in Appendix B).

Core sediment samples were obtained at 18 sampling sites, with triplicate samples collected at one site. Mr. David Beno, of the Dredge and Fill Section, Water Quality Branch, obtained permission from MSD and Waste Management Inc. to enter their properties. He also selected the sampling sites.

3. DISCUSSION

a. Dates of Sampling

June 6, 7, 8, 9 and 10, 1983.

b. Participants

Central District Office Personnel:

John F. Connell, Chief, IL/IN Field Investigation Section
John J. Mc Guire, Chief, Field Support Team
Charles J. Miller, Environmental Scientist
Stephan Wynnychenko, Environmental Scientist
Stanley J. Bojczuk, Physical Science Technician

Dredge and Fill Section, Water Quality Branch:

David Beno, Environmental Protection Specialist

MSD Personnel:

Ross Dring, MSD Operation Division

Bill Schmeelk, MSD Research Division

Waste Management, Inc. Personnel:

Tee Forshaw
Jane Fitzgerald
Mike Healy, Gulf Coast Lab

c. Sampling Protocol

The sampling device was a "WILDCO" K-B Core Sampler with a four foot barrel. The sampler was restructured using a 2" to 0.75" reducer, various lengths of 0.75" galvanized pipes (nipples) and coupling. Core liners were fitted inside the barrel tube. Prewashed clear plastic liners were used for inorganic analysis samples. Stainless steel liners, prewashed in acetone, were used for the samples intended for organic analysis. A plastic cover nose piece, prewashed in metal free water, was used for the inorganic samples and a stainless steel cover nose, prewashed in acetone, was used for the organic samples. The nose cone was screwed on over the end of the barrel, after the liner was inserted into the barrel. The reducer piece allowed the passage of the air through the galvanized pipe when the device was submerged into the water. By hammering on the extended pipe with a sledge hammer, the core sampler was driven two feet deep into the sediment.

At each sampling location, before obtaining the core samples, the water depth was determined by lowering a carpenter ruler until it rested on the surface of the sediment. The corer was retrieved by working the sampler in each direction and then pulling the core sampler out. The nose cone was then removed. The sediment in the nose cone was discarded. An aluminum foil square was placed over the liner end before the plastic end caps were pushed on. The unit was kept near vertical position and the core liner was removed, dewatered and the length of the sediment was measured. The length of the sediment in the plastic tube was measured directly. The length of the sediment in the stainless steel tubes was measured by lowering a carpenter ruler into the tube while held upright until the ruler rested on the top of the sediment in the tube. The length of the sediment was obtained by the difference between the length of the core liner and the length of ruler inserted into the liner.

After a core was measured, the upper end of the liner was capped and the liner was taped on both ends. The liner was immediately labeled and secured in an upright position. The samples were brought back to the Central Regional Laboratory intact in their liners, except for the following sample sites which were extracted in the field:

S02 - 122nd St., west of Paxton Landfill (north side of the street)

S03 - D01, D02 - 122nd St., (south side of the street)

S01 - 116th St. (right-of-way)

S06 - 122nd St. at the Norfolk and Western railroad (SE corner)

S04 - 122nd St. (NE corner)

S05 - 122nd St. (NW corner)

All samples were handled using custody procedures. The samples were either in sight at all times or were locked in the van. The samples were returned to the CRL Custodian and checked into the custody room.

d. Sample Extraction

A brass core pusher was used for the core samples extracted in the field. For each sample extracted, the core pusher was cleaned, prewashed and rinsed with distilled water and acetone, and the end of the piston was wrapped in aluminum foil. For the inorganic cores, the pusher was precleaned, rinsed with metal free water, and the piston end was wrapped in aluminum foil. The aluminum foil was changed for each core. The stainless steel spatulas and stainless steel buckets were cleaned and rinsed, prior to extracting each core for organic analysis, with distilled water and acetone. A plastic bucket and teflon spatula were rinsed, prior to extracting each core for inorganic analysis, with metal free water. The core samples were homogenized with the spatulas. A portion of the homogenized samples was placed into eight 8-ounce jars with teflon-lined screw caps.

The core samples that were brought to CRL were extracted in Room 1027 using a brass core pusher. For the organic samples, the piston end was wrapped with aluminum foil. The aluminum foil was changed for each core. Aluminum foil was not used for the metal samples. For the organic cores, a stainless steel spatula and enamel pan were wiped off and rinsed prior to extracting each core with distilled water and methylene chloride. For the inorganic cores, a plastic pan and teflon spatula were rinsed prior to extracting each core with distilled water. The brass pusher was cleaned with tap water and distilled water prior to extracting each core. Core samples were homogenized with the spatulas. Sticks and rocks were left in. When the core sample was homogenized, it was split into 3 to 4 sections. From these sections, split samples were made by placing one scoopful in alternate order into separate jars. The aluminum foil and sample jars, 16 ounce capacity with teflon-lined screw caps, were prerinsed in methylene chloride. The extracted split samples were under CRL custody until they were picked up by Waste Management, Inc. and MSD.

4. SAMPLE ANALYSIS REVIEWS

The results of the sample analysis are tabulated in Appendix C, all of the results are on a dry weight basis. All of the metals analysis and the percent solids are listed in the Appendix. For the organic analysis, only those compounds that were detected have been tabulated. The organics sample analysis sheets with tentatively identified compounds are located in Appendix D. Only samples S01 through S06 and R01 were analyzed for volatile organics. The blank (R01) was not analyzed for GL/MS scan, PCBs or pesticides. Sample numbers S16 through S19 were not used in this study.

No significant metals or volatile organics concentrations were detected in the blank sample (R01). The triplicate sample (S03, D01 and D02) are in good agreement for both the metals and the organic analysis with one exception. 1,1,1 Trichloroethane was detected in one of the triplicates (D02) but was not detected in either the sample (S03) or the other triplicate (D01).

The samples from 116th Street (S01) and the river at the MSD site (S07) had the lower overall metals concentration. The highest metals concentration were in the samples from the east side of the Burnham site (S12) and the tar pit at the Interlake site (S21).

Arsenic was detected in all of the samples except for the sample from the NE corner of 122nd Street and the railroad tracks (S04). The highest concentrations were in the samples from the ditch on the west side of the MSD site (S08 - 31 ug/g) and both samples from the Burnham site (S12 - 26 ug/g and S13 - 20 ug/g).

Cadmium was detected at ten of the sampling locations with the highest concentrations at the east side of the Burnham site (S12 - 14 ug/g) and the tar pit at the Interlake site (S21 - 20 ug/g). Chromium, copper, lead, nickel and zinc were detected in all of the samples. The sample from the east location at the Burnham site (S12) had the highest concentration for chromium (210 ug/g), copper (250 ug/g) and nickel (73 ug/g). The highest concentration of lead was in the sample from the tar pit at the Interlake site (S21 - 4.4 mg/g). The highest concentrations of zinc were in the samples from the east side of the Burnham site (S12 - 1.8 mg/g) and the tar pit at the Interlake site (S21 - 12 mg/g). Mercury was detected at eight of the sampling locations. The highest concentrations were in both samples from the Burnham site (S12 - 2.8 ug/g and S13 - 2.0 ug/g) and from the NW location at the Interlake site (S22 - 2.3 ug/g). Silver was detected at seven of the sampling locations. The highest concentrations were at the east location of the Burnham site (S12 - 7.4 ug/g) and the tar pit at the Interlake site (S21 - 6.6 ug/g).

Only a few organic compounds were detected in all four samples from the MSD site (S07, S08, S09, S10), the Heil site (S11), the sample from the west side of the Burnham site (S13), and three samples from the Interlake site (S14, S15, S20). At all the other sampling locations, a number of organic compounds were detected in the ppm range. The high acetone concentrations are from contamination resulting from cleaning the sampling equipment with acetone. Since methylene chloride was detected in the blanks (R01), the reported values for samples S01, S03, S04 and S05 should be disregarded as contamination. Three chlorinated ethanes were detected in the samples from the south side of 122nd Street (S03, D02): Chloroethane (S03 - 480 ug/kg), 1, 1-dichloroethane (S03 38 ug/kg) and 1,1,1 - Trichloroethane (D02 - 900 ug/kg). Toluene was also detected in the sample from the south side of 122nd Street (D02 - 9.0 ug/kg). Benzene was not detected in any of the samples.

Most of the acid/base neutral compounds detected were Polynuclear aromatic hydrocarbons. A significant number of this class of compounds were detected at 116th Street (S01), both the north and south sides of 122nd Street (S02, S03), the three samples from 122nd Street and the railroad tracks (S04, S05, S06), the east location of the Burnham site (S12) and the tar pit and the NW location at the Interlake site (S21, S22). Five phthalate esters compounds were detected in the samples. For the most part, this class of compounds was detected at the same sample locations as the polynuclear aromatic hydrocarbons except that none were detected in the sample from the NW location of the Interlake site (S22).

PCBs were detected at the east side of the Burnham site (S12 - Aroclor 1254 - 33 mg/kg) and the tar pit at the Interlake site (S21 - Aroclor 1242 8.0 mg/kg and aroclor 1254 - 3.0 mg/kg). Pesticides were detected at four locations. PP' DDT was detected at the ditch on the west side of the MSD site (S08 - 0.1 mg/kg), the pond on the MSD site (S09 - 0.3 mg/kg), the west side of the Burnham site (S13 - 0.1 mg/kg), and the center location at the Interlake site (S20 - 0.6 mg/kg). Dieldrin was detected at the pond on the MSD site (S09 - 0.1 mg/kg) and the west side of the Burnham site (S13 - 0.1 mg/kg). PP' - DDD was detected at the pond on the MSD site (S09 - 0.3 mg/kg), the west location of the Burnham site (S13 0.1 mg/kg) and the center location of the Interlake site (S20 - 0.4 mg/kg).

5. CONCLUSION

The highest concentration of metals were in the samples from the east location of the Burnham site (S12) and the tar pit on the Interlake site (S21). The highest concentration of organic compounds were at 116th Street (S01), both sides of 122nd Street (S02, S03), the three locations at 122nd Street and the railroad tracks (S04, S05, S06), the east location of the Burnham site (S12), the tar pit (S21) and the NW location (S22) of the Interlake site.

Since the tar pit (S21) was used by Interlake Steel to dispose of their waste, it would be expected for this site to have a high concentration of pollutants. The sampling location on the east side of the Burnham site is in the flood plain of the Calumet River. This would account for the high level of pollutants at this location. Most of the organic compounds detected were polynuclear aromatic hydrocarbons, which are residues of coal tar. Since there are two operating and one closed coke plant in their area, (see first map- Appendix B), it would be expected for this class of compounds to be detected in the core samples in the area. Four of the phthalate esters (di-n-butyl phthalate, butyl benzyl phthalate, and bis(2-ethylhexyl) phthalate, diethyl phthalate) detected in the samples, have been detected in many surveys conducted by the Central District Office at about these same concentrations.

UNITED STATES ENVIRONMENTAL PROTECTION AGENCY
REGION V

DATE: SEP 30 1983

SUBJECT: Report of Survey Conducted near South Deering,
Chicago, Illinois

FROM: William H. Sanders III, Director
Environmental Services Division

TO: Valdas V. Adamkus
Regional Administrator

INTRODUCTION

On May 9, 1983, the Central District Office performed a sampling survey in the South Deering section of Chicago, Illinois at your request. The survey was initiated after inquiries by Senator Percy and a citizens group who were concerned about water contamination in the area. After receiving the report on the first survey, the citizen's group raised additional concerns about the water quality at other locations within the area. Horst Witschonke, Waste Management Branch, requested the Central District Office to sample three additional sites.

DISCUSSION

Water samples were collected at the three sites for total metals, mercury, arsenic, volatile organics and organics scan analysis. Triplicate samples were collected at one of the sites for quality assurance. Attached is a map showing the sampling locations (Attachment 1).

All of the sampling sites were along the Norfolk and Western Railroad tracks which are west of Torrance Avenue. Two of the sites were sampled on June 6, 1983. Both of these locations were approximately 1000 feet north of 122nd Street on each side of the railroad tracks. Sample CC05S17 was collected on the east side of the tracks just south of the foot bridge to Paradise Pond. Sample CC05S16 and triplicates CC05D03 and CC05D04 were collected from the ditch on the west side of the tracks directly across from the point where S17 was collected. The third sample, CB05S01, was collected on June 29, 1983, from the pond on the west side of the tracks approximately 2000 feet north of 122nd Street. This sample was a composite of three points near the drums, which are in the pond. The two sampling sites on the west side of the tracks are the same ditch but 1000 feet apart. No flow was noticed in this ditch on either sampling day. There was a slight flow in the ditch on the east side of the tracks.

Participants:

June 6, 1983

John Connell, Environmental Engineer
Stephan Wynnynchenko, Environmental Scientist
Stanley Bojczuk, Physical Science Technician

June 29, 1983

Sylvester Bernotas, Environmental Engineer

FINDINGS

The water quality data is summarized in Attachment 2 and 3. Attachment 2 is a tabulation of the metal analysis, pH, and water temperature and Attachment 3 is a tabulation of the organic compounds which were above the detection limits.

The pH of the samples ranged from 6.9 to 7.8 and the water temperature varied from 22°C to 27°C.

The metals concentration of the samples were compared with the IEPA Rule 203 General Water Quality Standards. Four metals exceeded the standards. Samples S16 and S17 exceeded the 1.0 mg/l standard for boron with 1.43 and 1.02 mg/l respectively. Sample S01 exceeded the 20 ug/l standard for copper with a concentration of 25.4 ug/l and exceeded the 1.0 mg/l standard for manganese with a concentration of 1.4 mg/l. The 1.0 mg/l standard for iron was exceeded at all three locations: S01 - 5.88 mg/l, S16 - 1.23 mg/l, and S17 - 1.23 mg/l. Total chromium was detected in both samples from the west side of the railroad tracks. Sample S01 had a concentration of 39.1 ug/l and sample S16 had a concentration of 8.4 ug/l. The standard for total hexalent chromium is 50 mg/l.

Six volatile organic compounds were detected, all in the ppb range. Since methylene chloride was found in both blanks (R01 and R02), the 6.3 ppb concentration in sample S01 should be discarded as either sampling or laboratory contamination. 1,2 dichlorethane was detected in both samples from the west side of the railroad tracks; the sample at the northern site (S01) had a concentration of 16 ppb compared to the concentration of the sample at the southern site (S16) of 1.0 ppb. Chlorobenzene was detected at a concentration of 3.5 ppb at the southern site on the west side of tracks (S16) but it was not detected at the northern site. Chloroform and carbon tetrachloride were detected at the northern site on the west side of the tracks (S01) at concentrations of 30 ppb and 0.7 ppb respectively but neither compound was detected at the southern site (S16). 1,1 dichloroethane was detected in the sample from the east side of the

tracks at a concentration of 0.5 ppb but not detected in either site on the west side of the tracks.

Seven compounds were detected in the GC/MS organic scan, all in the ppb range, in the sample from the northern site on the west side of the tracks (S01). The results for two of the compounds, diethyl phthalate and di-n-butyl phthalate should be disregarded since these compounds were present in the laboratory blanks at or near the sample concentration. The other compounds detected were aniline (30 ppb), phenol (8.7 ppb), 4-methylphenol (73 ppb), isophorone (40 ppb), bis (2-ethylhexyl) phthalate (60 ppb).

Illinois EPA Water Pollution Rules and Regulation do not cover many of the metals and none of the organics which were detected in these water samples.


CONCLUSION

All three of the sampling locations exceeded the Illinois water quality standards for some of the metals. Also a number of organic compound were detected in the two samples from the west side of the railroad tracks, with the northern sample showing the highest concentrations. For these reasons it is recommended that the water on both sides of the railroad tracks not be used for body contact.

W. Sanders

William H. Sanders III, Director

cc: Mary Canavan
Horst Witschonke
Kenneth Fenner



Industrial Waste Disposal Sites

Appendix J

COMPREHENSIVE PLAN 1984



CHICAGO REGIONAL PORT DISTRICT

BOARD OF DIRECTORS

JOHN J. SERPICO, CHAIRMAN
HENRY M. SOLTYSINSKI, VICE CHAIRMAN

I. ANDREW MOORE, SECRETARY

THOMAS G. CAMPBELL
JAMES G. GIDWITZ
EVERETTE B. HARRIS
THOMAS M. HOGAN
SAMUEL C. MARAGOS
RAYMOND T. O'KEEFE
PAUL J. RANDOLPH

GILBERT J. CATALDO,
GENERAL MANAGER

EARL L. NEAL
GENERAL COUNSEL

EPSTEIN CIVIL ENGINEERING, INC.
ENGINEERS

MANN, GIN, EBEL & FRAZIER LTD.
ARCHITECTS

JAMES G. THOMPSON, GOVERNOR
STATE OF ILLINOIS

HAROLD M. WASHINGTON, MAYOR
CITY OF CHICAGO



JANUARY 20, 1984

TO PUBLIC OFFICIALS AND MEMBERS OF THE PUBLIC.

ON BEHALF OF THE BOARD OF DIRECTORS OF THE CHICAGO REGIONAL PORT DISTRICT, I AM PLEASED TO PRESENT FOR YOUR INFORMATION OUR PROPOSED PLAN FOR THE DEVELOPMENT OF THE PROPERTIES ENTRUSTED TO THE PORT.

ECONOMIC DEVELOPMENT IS THE KEYNOTE OF THE ENTIRE EFFORT. THE VARIOUS PROJECTS PROPOSED MEAN JOBS AND THE GENERATION OF NEW ECONOMIC BASE FOR THE COMMUNITY.

IT IS THE INTENTION OF THE BOARD TO MARSHALL ALL THE TOOLS AVAILABLE TO IT TO ENSURE THE SUCCESS OF THE PROPOSAL. THE PROVISIONS OF THE NEW ENTERPRISE ZONE OFFER CONSIDERABLE ADVANTAGES TO BUSINESS AND WILL SERVE AS PART OF AN ARRAY OF BENEFITS TO PARTICIPANTS. FURTHER, THE DISTRICT CONTEMPLATES THE OFFERING OF INDUSTRIAL REVENUE BONDS AND DEVELOPMENT OF THE POTENTIAL OF THE FOREIGN TRADE ZONE AS PART OF A PROGRAM OF ACTION.

WE LOOK FORWARD TO WORKING WITH BUSINESSES, GOVERNMENTS AND CITIZENS IN BUILDING A VIABLE COMPLEX OF MARITIME, RECREATIONAL, INDUSTRIAL, COMMERCIAL AND TRANSPORTATION SERVICES.

JOHN J. SERPICO, CHAIRMAN


INTRODUCTION

CONCEIVED ORIGINALLY IN 1909, THE PLAN FOR CHICAGO'S PORT AND ITS INLAND HARBOR AT LAKE CALUMET WAS BASED ON A SERIES OF ASSUMPTIONS WHICH HELD FOR MANY YEARS. AMONG THESE ASSUMPTIONS WERE THAT CHICAGO WOULD CONTINUE TO GROW AS AN INDUSTRIAL AND MANUFACTURING CENTER, AN EXPORTER AND IMPORTER OF GOODS IN THE WORLD MARKET, AND MAJOR CENTER OF WATERBORNE TRADE. IN RECENT YEARS, THESE ASSUMPTIONS ARE NO LONGER CORRECT, AS CHICAGO HAS BECOME INCREASINGLY A PROVIDER OF SERVICES AND LESS A MANUFACTURER OF GOODS, AS SHIPPING HAS YIELDED TO THE DOMINANCE OF LAND AND AIR TRANSPORT, AND AS THE ECONOMY HAS READJUSTED TO MORE TEMPERATE INVESTMENT AND ALLOCATION OF RESOURCES.

LAKE CALUMET HARBOR WAS DESIGNED ORIGINALLY IN A FINGER-LIKE SYSTEM OF DOCKS, NEVER COMPLETED, WHICH WOULD ACCOMMODATE LARGE NUMBERS OF SHIPS. BY TODAY'S STANDARDS, THE SHIPS PLANNED FOR ARE SMALL AND DEPENDENT ON MANUAL LABOR AND A LOW ORDER OF TECHNOLOGY. NOT ONLY ARE SHIPPING AND CARGO TRANSFER NEEDS DIFFERENT TODAY, BUT ALSO THE FUNCTION OF THE ORIGINAL PLAN HAS NEVER MET PAST ANTICIPATIONS. AS THE ECONOMY HAS SETTLED INTO NEW PATTERNS, ONE OF THE NEEDS THAT HAS BECOME MORE SHARPLY APPARENT IS THE CONTINUING STRENGTH OF TRADE AND TRANSPORT IN BASIC RAW GOODS - SUCH AS LIMESTONE, FERTILIZERS, COAL, CRUDE PETROLEUM, IRON ORE - WITHIN THE GREAT LAKES AND THE INLAND RIVER SYSTEMS. THIS TYPE OF TRANSPORT REQUIRES BARGES, BULK TERMINAL AND BULK HANDLING SYSTEMS. OTHER WATERBORNE TRADE RELIES MORE HEAVILY ON AN ENTIRELY DIFFERENT FORM OF SHIPPING, ON THE NEWER TECHNOLOGIES OF CONTAINERS, REFRIGERATION, MECHANIZATION.

IN ORDER TO MEET THE CHANGING NEEDS OF WATER TRANSPORT, THE PORT DISTRICT MUST REVAMP SUBSTANTIALLY THE TURN-OF-THE-CENTURY PHYSICAL PLAN FOR LAKE CALUMET. THE NEW PLAN MUST BE RESPONSIVE TO A REALISTIC ANTICIPATION OF TRAFFIC IN TERMS OF VOLUME AND TYPE. IT NEEDS FLEXIBILITY TO ACCOMMODATE CHANGES THAT CANNOT BE ANTICIPATED. FINALLY IT MUST ADDRESS THE ISSUE OF THE PORT'S UNDERDEVELOPED REAL ESTATE.

THE DISTRICT OWNS APPROXIMATELY 3000 ACRES AT IROQUOIS LANDING AND LAKE CALUMET. MOST OF IT SURROUNDS LAKE CALUMET. I-94 RUNS ALONG ITS WESTERN BORDER AND STONEY ISLAND ON ITS EASTERN. RAILROAD LINES SERVE IT. THE PORT'S TERMINAL AND CARGO HANDLING FACILITIES TIE ALL THE VARIOUS FORMS OF TRANSPORTATION TOGETHER. THIS IS THE GREATEST STRENGTH OF THE PROPERTY. THE PROBLEM WHICH MUST BE OVERCOME IS THAT CONSIDERABLE FILL IS NEEDED TO PROVIDE DEVELOPABLE SITES. OTHERWISE, THERE IS TREMENDOUS POTENTIAL FOR MARITIME SUPPORTIVE, MARITIME RELATED AND OTHER DEVELOPMENT THAT STIMULATES THE ECONOMY OF THE COMMUNITY.



THE LONG RANGE VIEW

ULTIMATELY, THE PORT DISTRICT'S FACILITIES WILL COMBINE MARITIME, RECREATIONAL, TRANSPORTATION, LIGHT INDUSTRY AND COMMERCIAL NEEDS IN A COMPLEMENTARY AND AESTHETIC MIX.

THE CHANNEL AND CENTER OF LAKE CALUMET WILL BE LONGER, DEEPER AND WIDER THAN AT PRESENT IN ORDER TO ACCOMMODATE SHIPPING, CARGO HANDLING, AND TRANSFER MORE EFFICIENTLY AND EFFECTIVELY. SITES FOR VARIOUS TYPES OF BULK TERMINAL FACILITIES WOULD BE CLOSE AT HAND FOR STORAGE, AND SPACE WILL BE AVAILABLE FOR LIGHT MANUFACTURING OR ASSEMBLY OR TRANSFER AS NEEDED. THIS FORM OF MARITIME SUPPORT WILL CONSTITUTE THE FIRST "LAYER" AROUND THE NEW LAKE CALUMET.


AT THE NORTH END OF THE LAKE A MARINA AND RECREATIONAL AREA WILL SERVE THE PUBLIC IN A LAGOON SETTING. THE GOLF COURSE TO THE NORTH WILL SERVE AS A BACKDROP FOR THE SETTING AND WILL AUGMENT THE RECREATIONAL AMENITIES. THROUGHOUT, LANDSCAPING WILL REFLECT THE NATURAL ENVIRONMENT OF WETLANDS AND THE NATIVE FLORA AND FAUNA. NEW TECHNOLOGIES WILL BE UTILIZED TO CREATE A CLEAN, SAFE, VISUALLY APPEALING SITE SYMBIOTIC WITH THE ENVIRONMENT.

A SECOND LAYER AROUND THE BASIC CORE DESCRIBED ABOVE WILL PROVIDE SERVICES TO IT AS WELL AS THE NEXT LAYER WHICH WILL BE COMMERCIAL IN NATURE. THIS SERVICE STRIP WILL CONTAIN RAIL AND ROAD ACCESS, WATER, SEWERS, AND OTHER UTILITIES. IT WILL MOVE PEOPLE AND GOODS TO AND FROM THE VARIOUS FUNCTIONS. ON THE EAST SIDE OF THE LAKE THE SAME CONCEPT WILL BE APPLIED ALONG STONEY ISLAND.

THE COMMERCIAL LAYER WILL LIE PRIMARILY ALONG I-94 AND UTILIZE CURRENT ACCESS AT 111TH AND 113TH STREETS. IT WILL BE HIGHWAY ORIENTED. EXAMPLES OF THE TYPES OF BUSINESSES WHICH MIGHT BE FOUND HERE INCLUDE A TRUCK STOP AND TRUCK TERMINAL, AND RESTAURANTS, AT 111TH. A HOTEL OR MOTEL IS ENVISIONED IMMEDIATELY TO THE NORTH. TO THE SOUTH, OFF 113TH, VARIOUS TYPES OF COMMERCIAL OPERATIONS ARE ENVISIONED. EVENTUALLY, EXTENSION OF 111TH ALL THE WAY TO TORRENCE WOULD COMPLETE HIGH ACCESSIBILITY TO TRANSPORTATION THAT IS THE HALLMARK OF THE ENTIRE AREA.

LEGEND

- COMMERCIAL
- LIGHT INDUSTRY
- MARITIME RELATED
- EXISTING DEVELOPED PORT FACILITY
- ▨ PARK RECREATION
- WATER



PHASE I

THE COMMERCIAL STRIP ALONG I-94 WILL UTILIZE CURRENT ACCESS AT 111TH AND 113TH STREETS WHICH IS ADEQUATE FOR THE NEEDS. AMONG THE VARIOUS SERVICES TO BE OFFERED ARE CONTEMPLATED A TRUCK STOP AND TRUCK TERMINAL OF APPROXIMATELY 43 ACRES. THERE WILL BE A RESERVE ACREAGE IMMEDIATELY TO THE EAST FOR POTENTIAL EXPANSION IF AND AS NEEDED. THE CONFIGURATION OF THE FACILITY AND THE ATTENDANT LANDSCAPING WILL BE SPECIFICALLY PLANNED TO PROVIDE AN AESTHETICALLY PLEASING ASPECT TO THE COMMUTER ON THE EXPRESSWAY AND WILL REFLECT APPROPRIATELY THE GOLF COURSE FURTHER TO THE NORTH.

THE HOTEL OR MOTEL OPERATION WOULD BE IMMEDIATELY TO THE NORTH NEXT TO THE GOLF COURSE SO THAT THE TWO RESTFUL AREAS COMPLEMENT EACH OTHER.

PHASE II

SOUTHWARD. DRAWING ON THE 113TH STREET ACCESS WILL BE THE COMMERCIAL AREA. THE DEVELOPMENT WILL PROVIDE FOR POSSIBLE USES SUCH AS WAREHOUSE FOOD OPERATIONS, DISCOUNT STORES, HOME APPLIANCE, HARDWARE, AUTO EQUIPMENT AND LIKE OUTLETS WHICH WILL STRONGLY ATTRACT THE COMMUTER. PARKING AREAS WILL BE PLENTIFUL AND PROVIDED BY EACH DEVELOPMENT.

DEVELOPMENT WILL BEGIN FOR THE PARK AREA AND THE MARINA TO THE EAST. THE MARINA WILL SERVE APPROXIMATELY 800 BOATS.

AS RECLAMATION OF LAND BECOMES FEASIBLE, GROWTH WILL CONTINUE SOUTHWARD WITH COMMERCIAL DEVELOPMENT AND EASTWARD FOR LIGHT INDUSTRY APPLICATIONS.

PHASE III


THE PARK AREA WILL BE COMPLETED. GREAT EMPHASIS WILL BE PLACED ON PRESERVATION OF THE NATURAL ENVIRONMENT OF THE WETLANDS. A RELAXING AREA FOR MARINE USERS, SHOPPERS AND PASSERSBY, IT WILL ULTIMATELY OCCUPY ABOUT 20% OF THE ENTIRE AREA.


COMMERCIAL DEVELOPMENT WILL PROCEED SOUTHWARD ALONG I-94 AND MARITIME AND INDUSTRIAL FACILITIES TO THE EAST AS LAND IS RECLAIMED.

111 m

115 m

130 m






111 m

115 m

130 m



PLANNING ELEMENTS

ENVIRONMENT - RECREATION

IN KEEPING WITH ENVIRONMENTAL STUDIES ALREADY CONDUCTED AND THE ADVICE OF EXPERTS, THE DEVELOPMENT PLANNED WILL NOT HARM OR DISPLACE ANY SIGNIFICANT NATURAL RESOURCES. FURTHER, THE DESIGN OF THE AREA WILL BE ORIENTED SPECIFICALLY TO PRESERVATION AND AUGMENTATION OF THE WETLANDS, THE NATIVE FOWL, ANIMAL AND AQUATIC INHABITANTS, THE NATIVE GRASSES, FLOWERS AND SO ON. THIS WILL BE A RATHER SIZEABLE AREA CONSTITUTING ABOUT 20% OF THE PORT'S PROPERTIES AT LAKE CALUMET.


TRAFFIC


THE SYSTEM OF CIRCULATION OF TRAFFIC DESIGNED FOR LAKE CALUMET IS BASED ON THE ALREADY ADVANTAGEOUS CONFIGURATION OF ACCESS ROUTES, NAMELY I-94 AND ITS EXIT RAMPS, THE RAILROAD SPURS AND OTHER INTERNAL CONNECTIONS AVAILABLE NOW. THE SERVICE CORE OF ROAD AND RAIL ACCESS NOTED IN THE EXHIBIT WILL EXTEND AND AMPLIFY THE CURRENT TRANSPORTATION CONFIGURATION. THE DESIGN EMPHASIZES INTERACTION OF ROAD, RAIL AND WATER TRANSPORTATION AND TIES THE THREE TOGETHER IN THE INTEREST OF SERVING MARITIME, RECREATIONAL, INDUSTRIAL AND COMMERCIAL APPLICATIONS.


INFRASTRUCTURE

AT PRESENT WATER SERVICE IS AVAILABLE THROUGH A 42" MAIN ALONG COTTAGE GROVE TO THE WEST AND A 12" MAIN ON 122ND STREET FROM THE EAST THAT PROCEEDS SOUTH ON STONEY ISLAND. EXISTING SEWERS ARE ON 111TH AND THE SOUTH END OF STONEY ISLAND.

THE FOLLOWING EXHIBIT SHOWS EXTENSIONS OF THE WATER MAIN ON THE WEST ALONG 111TH AND 115TH STREETS, AND A SANITARY SEWER CONNECTION IN 111TH TO SERVE THE WEST SIDE OF THE DEVELOPMENTS PROPOSED. SERVICE ON THE EAST SIDE WILL BE SERVED BY THE CONNECTIONS SHOWN AT 122ND AND STONEY ISLAND. AS REQUIRED BY THE METROPOLITAN SANITARY DISTRICT, SEPARATE STORM DETENTION WILL BE PROVIDED BY EACH DEVELOPMENT.







LEGEND

- WATER
- SANITARY SEWER
- STORM SEWER
(ON-SITE STORM DETENTION
BY INDIVIDUAL DEVELOPMENTS)

TURBINE
BASIN

CONCLUSION

IN SUMMARY, THE PLAN CONTAINS THE FOLLOWING KEY ELEMENTS

- **IT MAXIMIZES THE POTENTIAL OF THE LAKE CALUMET AREA AS A TRANSPORTATION CENTER PROVIDING COST-EFFICIENT, MULTI-MODAL SERVICES**
- **BY REARRANGING TERMINAL AND CARGO-HANDLING FACILITIES, MARITIME OPERATIONS WILL MEET CURRENT NEEDS MORE EFFECTIVELY AND WILL BE PREPARED TO MEET FUTURE DEVELOPMENTS IN SHIPPING**
- **SIGNIFICANT ENVIRONMENTAL RESOURCES WILL BE PRESERVED AND SAFEGUARDED WITHIN A PARK-LIKE SETTING**
- **SPACE FOR LIGHT INDUSTRY WILL SUPPORT MARITIME OPERATIONS AND ENCOURAGE INCREASE IN TRADE**
- **THE MARINA AND RELATED RECREATIONAL FACILITIES WILL ADD A NEW DIMENSION IN A COMMUNITY WHERE SUCH AMMENITIES ARE FEW**
- **THE COMMERCIAL DEVELOPMENTS ON THE WEST SIDE WILL PROVIDE GOOD LOCATION FOR THAT CATEGORY OF BUSINESS DUE TO ACCESSIBILITY AND VISIBILITY AS WELL AS LITTLE COMPETITION FROM NEARBY AREAS**
- **THE PARTICULAR MIX OF DEVELOPMENTS AND THE SUBSTANTIAL GREENSPACE INTERACTING IN A NEW WAY WITH LAKE CALUMET WILL IMPROVE SIGNIFICANTLY THE VISUAL IMPACT OF THE AREA AND THE QUALITY OF LIFE THERE IN GENERAL**

BUT MOST IMPORTANT TO ALL IS THAT THE NEW COMPLEX OF MARITIME, RECREATIONAL, INDUSTRIAL, COMMERCIAL AND TRANSPORTATION OPERATIONS WILL PROVIDE A SIGNIFICANT DEVELOPMENT TO THE ECONOMY OF THE SOUTH SIDE AND CHICAGO.

Appendix K



Illinois Environmental Protection Agency

BORING NO. <u>Bnd 3</u>		WELL NO. <u>---</u>		GROUNDLEVEL ELEV. <u>---</u>		PAGE <u>1</u> OF <u>1</u>				
COUNTY <u>Cook</u>		SITE NO. <u>---</u>		START DATE <u>8-21-84</u> FINISH DATE <u>8-21-84</u>		ABOVE PACKING				
BORING LOCATION <u>South Side Chicago Study</u>		DRILLING EQUIPMENT <u>Post hole digger</u>		START TIME <u>1:15P</u> FINISH TIME <u>1:35P</u>		PACKING				
COMPLETION DEPTH <u>2.0 ft.</u>		BEDROCK DEPTH <u>---</u>		TOP OF CASING <u>---</u>		SCREEN				
WELL CASING		TYPE AND QUANTITY		SAMPLES				PERSONNEL		
SCREEN INTERVAL		TYPE AND QUANTITY		Sample No. <u>3A + 3B</u>				J. Ehrat D. Tolan K. Basie		
ELEV.	DESCRIPTION			DEPTH	Sample No.	Sampler Type	Sample Recovery %	Penetration (lb/ft)	N Value (blows)	REMARKS
	0.0 - 2.0 sand, light brn, med. to fine grained, some roots			0						
				1						
				2						dug 2.0ft
	Note: Sample 3A - tested for Metals acid digest. (Selenium)									
	Sample 3B - tested for EP Toxicity									
	★ Sample collected at 2.0ft									

Time Collected: 1:15 P

Lab # C01029 AUG22'84

Date Collected: 8-21-84

SPECIAL ANALYSIS FORM

Date Received 8-21-84

ILLINOIS ENVIRONMENTAL PROTECTION AGENCY
DIVISION OF LAND/NOISE POLLUTION CONTROL

COUNTY:

Cook

FILE HEADING:

FILE NUMBER:

SOURCE OF SAMPLE: (Exact Location)

Grid#3 Luella Playground School

(3A)

smpld - @ 2'

PHYSICAL OBSERVATIONS, REMARKS: soil

TESTS REQUESTED: Metal acid digest

COLLECTED BY: J. L. Hall

TRANSPORTED BY: J. L. Hall

LABORATORY

RECEIVED BY: D. J. Hamay

DATE
COMPLETED:

DATE
FORWARDED:

Selenium 4.3 mg/kg (µg/gram)

Daugherty

RESULTS EXPRESSED IN
MICROGRAMS PER GRAM
OF SAMPLE (P.P.M.).
DRY WEIGHT BASIS UNLESS
OTHERWISE SPECIFIED.

RECEIVED

JAN 25 1985

IESA-DI PC

Time Collected: 1:15P

Date Collected: 8-21-84

SPECIAL ANALYSIS FORM

Lab # C01030 AUG22'84
Date Received 8-21-84

ILLINOIS ENVIRONMENTAL PROTECTION AGENCY
DIVISION OF LAND/NOISE POLLUTION CONTROL

COUNTY: Cook FILE HEADING: FILE NUMBER:

SOURCE OF SAMPLE: (Exact Location)

Grid #3 Luella Playground School - sampled from 2.0' to 2.2'
(3B)

PHYSICAL OBSERVATIONS, REMARKS: soil

TESTS REQUESTED: EP Toxicity

COLLECTED BY: [Signature] TRANSPORTED BY: [Signature]
LABORATORY

RECEIVED BY: [Signature] DATE OCT 10 1984
COMPLETED: FORWARDED:

Selenium - 0.028
(0.028) RESULTS EXPRESSED IN
MG/LITER UNLESS
OTHERWISE SPECIFIED.

Initial pH 9.7
Final pH 5.0

RECEIVED

OCT 11 1984

IEPA-D.L.C.



Illinois Environmental Protection Agency

BORING NO. <u>Good 8</u>		WELL NO. <u>-</u>		GROUNDLEVEL ELEV. <u>-</u>		PAGE <u>1</u> OF <u>1</u>	
COUNTY <u>Cook</u>		SITE NO. <u>-</u>		DATE <u>8-21-84</u>		FINISH <u>8-21-84</u>	
SITE <u>South Side Chicago Study</u>		START <u>8-21-84</u>		FINISH <u>8-21-84</u>		ABOVE PACKING	
BORING LOCATION <u>Bright School</u>		TIME <u>1:50P</u>		FINISH <u>2:05P</u>		PACKING	
DRILLING EQUIPMENT <u>Post hole digger</u>		START <u>1:50P</u>		FINISH <u>2:05P</u>		SCREEN	
COMPLETION DEPTH <u>2.0 ft.</u>		BEDROCK DEPTH <u>-</u>		TOP OF CASING <u>-</u>		SCREEN	
WELL CASING		TYPE AND QUANTITY		SAMPLES		PERSONNEL	
SCREEN INTERVAL		TYPE AND QUANTITY		Sample No.		PERSONNEL	
ELEV.		DESCRIPTION		DEPTH		REMARKS	
0.0 - 0.4		Silt, grey to black, tight		0			
0.4 - 2.0		Sand, brown, assorted sizes of grains		1			
				2		dug 2.0 ft.	
		Note: Sample 8A					
		- tested for Metals Acid					
		Digest. (Selenium)					
		Sample 8B					
		- tested for E.P. Toxicity					
		* Sample collected from 6" to 2'					

Time Collected: 1:50 P

Lab # C01031 AUG22'84

Date Collected: 8-21-84

SPECIAL ANALYSIS FORM

Date Received 8-21-84

ILLINOIS ENVIRONMENTAL PROTECTION AGENCY
DIVISION OF LAND/NOISE POLLUTION CONTROL

COUNTY:

Cook

FILE HEADING:

FILE NUMBER:

SOURCE OF SAMPLE: (Exact Location)

Brid #8 Bright School

(8H)

PHYSICAL OBSERVATIONS, REMARKS: soil

TESTS REQUESTED: Metal acid digest

COLLECTED BY:

Gene Ehnat

TRANSPORTED BY:

Gene Ehnat

LABORATORY

RECEIVED BY:

M. Plamany

DATE

COMPLETED:

DATE

FORWARDED:

Selenium

5.8 mg/kg (µg/gram)

J. Daugherty

RESULTS EXPRESSED IN
MICROGRAMS PER GRAM
OF SAMPLE (P.P.M.).
DRY WEIGHT BASIS UNLESS
OTHERWISE SPECIFIED.

RECEIVED

JAN 25 1985

IFPA DLPC

IL 532-0314
LPC 8A 4/77

C001031

(NOT FOR DATA PROCESSING)

Environmental Protection Agency
Division of Laboratory Services
2121 W. Taylor Street
Chicago, Illinois 60612

Time Collected: 1:50P

Lab # C01032 AUG22

Date Collected: 8-21-84

SPECIAL ANALYSIS FORM

Date Received 8-21-84

ILLINOIS ENVIRONMENTAL PROTECTION AGENCY
DIVISION OF LAND/NOISE POLLUTION CONTROL

COUNTY:

Cook

FILE HEADING:

FILE NUMBER:

SOURCE OF SAMPLE: (Exact Location)

Grid #8 Bright School sampled from 16" to 2'

(8B)

PHYSICAL OBSERVATIONS, REMARKS: soil

TESTS REQUESTED: EPToxicity

COLLECTED BY:

Jane Phat

TRANSPORTED BY:

Jane Phat

LABORATORY

RECEIVED BY:

M. J. Tamay

DATE
COMPLETED:

DATE OCT. 10. 1984
FORWARDED:

Selenium

Daugherty

Selenium - 0.039

RESULTS EXPRESSED IN
MG/LITER UNLESS
OTHERWISE SPECIFIED.

Initial pH 9.3

Final pH 5.1

RECEIVED

OCT 11 1984

IEPA-DLPC

IL 532-0314
LPC 8A 4/77

(NOT FOR DATA PROCESSING)

C001032

Environmental Protection Agency
Division of Laboratory Services
2121 W. Taylor Street
Chicago, Illinois 60608

Illinois Environmental Protection Agency

BORING NO. Grid 10		WELL NO.		GROUND LEVEL ELEV.		PAGE 1 OF 1	
COUNTY Cook		SITE NO.		DATE 8-21-84		ANNULUS FILL MATERIAL ABOVE PACKING	
SOUTH SIDE CHICAGO STUDY Adams Elementary School		DRILLING EQUIPMENT Post hole digger		TIME 2:20P		PACKING 2:35P	
COMPLETION DEPTH 1.3 ft.		BEDROCK DEPTH		TOP OF CASING		SCREEN	
WELL CASING		TYPE AND QUANTITY		SAMPLES		PERSONNEL	
SCREEN INTERVAL		TYPE AND QUANTITY		Sample No.		L. J. Ehrat D. Tolan K. Bosie	
ELEV.		DESCRIPTION		DEPTH		REMARKS	
		0.0-1.3 Silt, sand, and Gravel, dark brown to black		0			
		0.9-1.3 Cinders		1		dug 1.3 ft.	
		Note: Sample 10A - tested for Metals Acid Digest (Selenium)		2			
		Sample 10B - tested for E.P Toxocity					
		★ Sample collected from 6" to 1.3'					

Time Collected: 2:20 P

Lab # C01033 AUG22'84

SPECIAL ANALYSIS FORM

Date Collected: 8-21-84

Date Received 8-21-84

ILLINOIS ENVIRONMENTAL PROTECTION AGENCY
DIVISION OF LAND/NOISE POLLUTION CONTROL

COUNTY:

Cook

FILE HEADING:

FILE NUMBER:

SOURCE OF SAMPLE: (Exact Location)

Grid #10 Adams Elementary School Playground

10A

PHYSICAL OBSERVATIONS, REMARKS: soil

TESTS REQUESTED: Metal acid digest

COLLECTED BY:

TRANSPORTED BY:

LABORATORY

RECEIVED BY:

DATE
COMPLETED:

DATE
FORWARDED:

Selenium

1.8 mg/kg (ug/gram)

Daugherty

RESULTS EXPRESSED IN
MICROGRAMS PER GRAM
OF SAMPLE (P.P.M.).
DRY WEIGHT BASIS UNLESS
OTHERWISE SPECIFIED.

RECEIVED

JAN 25 1985

IESA-DLPC

Time Collected: 2:20P

Lab # C01034 AUG22

Date Collected: 8-21-84

SPECIAL ANALYSIS FORM

Date Received 8-21-84

ILLINOIS ENVIRONMENTAL PROTECTION AGENCY
DIVISION OF LAND/NOISE POLLUTION CONTROL

COUNTY:

Cook

FILE HEADING:

FILE NUMBER:

SOURCE OF SAMPLE: (Exact Location)

Grid #10 Adams Elementary School Playground

(10B) sampled from 10" to 1.3'

PHYSICAL OBSERVATIONS, REMARKS: Soil

TESTS REQUESTED: E.P. Toxicity

COLLECTED BY: Jane Chhat

TRANSPORTED BY: Jane Chhat

LABORATORY

RECEIVED BY: M. Tammy

DATE
COMPLETED:

DATE OCT 10 1984
FORWARDED:

Selenium - 0.054

Daugherty

RESULTS EXPRESSED IN
MG/LITER UNLESS
OTHERWISE SPECIFIED.

Initial pH 9.1

Final pH 5.0

RECEIVED

OCT 11 1984

IEPA-DLPC



★ Sample collected from 0 to 6"

Time Collected: 3:10P

Lab #

C01035 AUG22

Date Collected: 8-21-84

SPECIAL ANALYSIS FORM

Date Received 8-21-84

ILLINOIS ENVIRONMENTAL PROTECTION AGENCY
DIVISION OF LAND/NOISE POLLUTION CONTROL

COUNTY:

Cook

FILE HEADING:

FILE NUMBER:

SOURCE OF SAMPLE: (Exact Location)

Grid #14 Republic Steel 0-10"

14A

PHYSICAL OBSERVATIONS, REMARKS: soil

TESTS REQUESTED: Metal acid digest

COLLECTED BY:

Jane Echat

TRANSPORTED BY:

Jane Echat

LABORATORY

RECEIVED BY:

M. Putnam

DATE COMPLETED:

DATE

FORWARDED:

Selenium - 1.8 mg/kg

Chromium - 1921 mg/kg

} ug/gram

Daugherty

RESULTS EXPRESSED IN
MICROGRAMS PER GRAM
OF SAMPLE (P.P.M.).
DRY WEIGHT BASIS UNLESS
OTHERWISE SPECIFIED.

Time Collected: 3:10P

Lab # C01036 AUG22'84

Date Collected: 8-21-84

SPECIAL ANALYSIS FORM

Date Received 8-21-84

ILLINOIS ENVIRONMENTAL PROTECTION AGENCY
DIVISION OF LAND/NOISE POLLUTION CONTROL

COUNTY:

Cook

FILE HEADING:

FILE NUMBER:

SOURCE OF SAMPLE: (Exact Location)

Grid #14 Republic steel 0-6"

14B

PHYSICAL OBSERVATIONS, REMARKS: Soil

TESTS REQUESTED: EP Toxicity

COLLECTED BY:

Jane Echal

TRANSPORTED BY:

Jane Echal

LABORATORY

RECEIVED BY:

M. Milam

DATE

COMPLETED:

DATE

OCT 10 1984

FORWARDED:

Selenium - 0.054

RESULTS EXPRESSED IN
MG/LITER UNLESS
OTHERWISE SPECIFIED.

Chromium - 0.01

Daugherty

Initial pH 9.7

Final pH 6.3

RECEIVED

OCT 11 1984

IEPA-DLPC

Illinois Environmental Protection Agency

BORING NO.		WELL NO.		GROUNDLEVEL ELEV.		PAGE		OF	
COUNTY		SITE NO.		DATE		ANNUAL FILL MATERIAL		ABOVE PACKING	
SITING LOCATION		SITING EQUIPMENT		START		FINISH		PACKING	
COMPLETION DEPTH		BEDROCK DEPTH		TOP OF CASING		START		FINISH	
ELL CASING		TYPE AND QUANTITY		SCREEN		PERSONNEL		REMARKS	
0.0 - 0.5		silt, sand, and Gravel, dark brn to grey		15A				Aug 6"	
Note Sample 15A		- tested for Metals Acid Digest (Cadmium)							
- tested for E.P Toxicity									
* Sample collected from C-6"									

Time Collected: 2:50 P

Date Collected: 8-21-84

Lab #
SPECIAL ANALYSIS FORM

CO1037 AUG22 84
Date Received 8-21-84

ILLINOIS ENVIRONMENTAL PROTECTION AGENCY
DIVISION OF LAND/NOISE POLLUTION CONTROL

COUNTY:

Cook

FILE HEADING:

FILE NUMBER:

SOURCE OF SAMPLE: (Exact Location)

Brid #15 Wolf Lake sampled from 0 to 6"

(15 H)

PHYSICAL OBSERVATIONS, REMARKS: Soil

TESTS REQUESTED: Metals acid digest and EP Toxicity

* Note only one bottle

COLLECTED BY:

Jane E. Hest

TRANSPORTED BY:

Jane E. Hest

LABORATORY

RECEIVED BY:

P. Butanay

DATE
COMPLETED:

DATE OCT. 10, 1984
FORWARDED:

Cadmium 52.5 mg/kg

"C.P. Toxicity"
Cadmium < 0.0 / mg/liter

(ppm dry weight basis)

Initial pH 8.6
Final pH 5.1

RESULTS EXPRESSED IN
MG/LITER UNLESS
OTHERWISE SPECIFIED.

RECEIVED

OCT 11 1984

IEPA-DLPC

J. Daugherty